

FINAL

July 6, 2007

SAMPLING AND ANALYSIS PLAN FOR ACTIVITY-BASED OUTDOOR AIR EXPOSURES OPERABLE UNIT 4 LIBBY, MONTANA, SUPERFUND SITE

Prepared by
US Environmental Protection Agency
Region 8
Denver, CO



With Technical Assistance from:

Syracuse Research Corporation Denver, CO



and

CDM Federal Programs Corporation.
Denver, CO



TO:3032951895

P.003/003

FINAL- July 6, 2007

APPROVAL PAGE

This sampling and analysis plan for activity-based indoor air exposures for Operable Unit 4 of the Libby, Montana, Superfund Site has been prepared by the U.S. Environmental Protection Agency, Region 8, with technical support from Syracuse Research Corporation and CDM, Inc. Study activities addressed in this Plan are approved.

Paul Peronard

Team Leader, Libby Site

7/9/07.
Date

Distribution List

Paul Peronard (4 copies)
U.S. Environmental Protection Agency Region VIII
8EPR-ER
Denver, Colorado 80202-2466

EPA Technical Assistance Unit (3 copies)
U.S. Environmental Protection Agency Region VIII
Denver, Colorado 80202-2466

EPA Information Center (5 copies) 501 Mineral Avenue Libby, Montana 59923

Catherine LeCours (1 copy)
Montana Department of Environmental Quality
1100 North Last Chance Gulch
Helena, MT 59601

Steve Losier (3 copies)
John A. Volpe Center
National Transportation Systems Center
Environmental Engineering Division, RTV-4E
55 Broadway, Kendall Square
Cambridge, Massachusetts 02142

Dee Warren (2 copy)
CDM Federal Programs Corporation
1331 17th Street, Suite 1100
Denver, Colorado 80202

Project Files (1 copy)
CDM Federal Programs Corporation
1331 17th Street, Suite 1100
Denver, Colorado 80202

Thomas Cook (18 copies)
CDM Federal Programs Corporation
60 Port Blvd, Suite 201
Libby, Montana 59923

Anni Autio (1 copy)
CDM Federal Programs Corporation
One Cambridge Place
50 Hampshire Street
Cambridge, Massachusetts 02139

CDM Federal Programs Corporation (1 copy)
One Cambridge Place
50 Hampshire Street
Cambridge, Massachusetts 02319

Syracuse Research Corporation (1 copy) 999 18th Street, Suite 1975 Denver CO 80202

Naresh Batta (1 copy)
Batta Environmental Associates, Inc.
Delaware Industrial Park
6 Garfield Way
Newark, DE 19713-5817

Robert DeMalo (1 copy) EMSL Analytical Inc. 107 Haddon Avenue Westmont, NJ 08108

Ron Mahoney (1 copy) EMSL Analytical Inc. 107 4th Street West Libby, MT 59923

Kyeong Corbin (1 copy) Hygeia Laboratories Inc. 82 West Sierra Madre Blvd Sierra Madre, CA 91024-2434

Michael Mount (1 copy) MAS 3945 Lakefield Court Suwannee, GA 30024

Jeanne Orr (1 copy) Reservoirs Environmental Services Inc. 2059 Bryant Street Denver, CO 80211

DOCUMENT REVISION LOG

Revision	Date	Primary Changes
0	07/06/2007	

TABLE OF CONTENTS

1.0	INTRODUCTION	1
2.0	BACKGROUND AND PROBLEM DEFINITION	2
2.1	Problem Definition	
2.2	Overview of Existing Data	3
3.0	DATA QUALITY OBJECTIVES	6
3.1	State the Problem	6
3.2	Identify the Decisions	7
3.3	Identify the Types of Data Needed	8
3	.3.1 Sampling Locations	8
3	.3.2 Types of Air Samples	9
3	.3.3 Target Analyte List	9
3	.3.4 Types of Soil Disturbances	9
3	.3.5 Soil Condition Data	9
3.4	Define the Bounds of the Study	10
3	.4.1 Spatial Bounds	10
3	.4.2 Temporal Bounds	10
3.5	Define the Decision Rule	10
3.6	Define the Acceptable Limits on Decision Errors	11
3.7	Optimize the Design	12
3	.7.1 Limiting the Uncertainty in Estimates of Long-Term Average Concentration	12
3	.7.2 Estimating the Required Analytical Sensitivity for Outdoor Air	13
3	7.3 Refinements to the Design as Data are Collected	16
4.0	SAMPLING PROGRAM	18
4.1	Pre-Sampling Activities	19
4.	1.1 Selection of Sampling Locations	19
4.	1.2 Community Coordination	20
4.	1.3 Field Planning Meeting	20
4.	1.4 Training Requirements	20
4.	1.5 Inventory and Procurement of Equipment and Supplies	20
4.2	Sample Collection	21
4.	2.1 Outdoor Air Sampling	21
4.	2.2 Outdoor Soil Sampling	24
4.3	General Processes	25
4.	3.1 Equipment Decontamination	25

4	.3.2	Sample Labeling and Identification	26
4	.3.3	Videotape Documentation	26
4	.3.4	Field Logbooks	26
4	.3.5	FSDSs	26
4	.3.6	Photographic Documentation	27
4	.3.7	GPS Point Collection	27
4	.3.8	Field Equipment Maintenance	27
4	.3.9	Handling IDW	27
4	.3.10	Field Sample Custody and Documentation	27
4	.3.11	Sample Packaging and Shipping	28
4	.3.12	Modification Forms	28
4	.3.13	Field Surveillances and Audits	28
4.4	Q	uality Assurance/Quality Control (QA/QC) Activities	28
5.0	LAF	BORATORY ANALYSIS AND REQUIREMENTS	. 32
5.1		nalytical MethodsAir	
_		Soil	
_		Sample Archival	
5.2		nalytical Sensitivity for TEM Analyses	
5.3		olding Times	
5.4		aboratory Custody Procedures and Documentation	
5.5		ocumentation and Records	
5.6		ata Management	
6.0	ASS	ESSMENT AND OVERSIGHT	35
6.1	As	ssessments	35
6.2	Re	esponse Actions	35
6.3	Re	eports to Management	36
7.0	DAT	A VALIDATION AND USABILITY	37
7.1	Da	ata Review, Validation, and Verification Requirements	37
7.2		econciliation with Data Quality Objectives	
8.0		OJECT SCHEDULE	
0 0	DEE	EDENCES	20

LIST OF TABLES

Table 4-1 Summary of Field QC Samples by Media

LIST OF FIGURES

Figure 2-1	Total LA Levels in Personal ABS Air Samples Near Soil Disturbances
Figure 3-1	Example Uncertainty in the Mean of a Lognormal Data Set with $\sigma = 2.0$
Figure 4-1	Study Area Boundaries
Figure 4-2	Procedures for Pump Fault and Flow-Rate Errors
Figure 4-3	Effect of Pump Time on Grid Openings Required

LIST OF APPENDIXS

Appendix A	Standard Operating Procedures
Appendix B	Activity-Based Sampling Property Background and Sampling Form
Appendix C	Field Sample Data Sheets
Appendix D	Libby Asbestos Project Record of Modification Form

LIST OF ACRONYMS

ABS Activity-Based Sampling

ASTM American Society for Testing and Materials

CAR Corrective Action Request

CDM CDM Federal Programs Corporation
CIC Community Involvement Coordinator

COC Chain-of-Custody day/yr Days Per Year

DQOs Data Quality Objectives

EABS Exterior Activity Based Sampling

ED Exposure Duration

EDD Electronic Data Deliverable

EF Exposure Frequency

EPA Environmental Protection Agency

ERT Emergency Response Team

ET Exposure Time

f/cc Fiber per Cubic Centimeter FSDS Field Sample Data Sheet FSP Field Sampling Plan

GO Grid Opening

GPS Global Positioning System

hrs/day Hours Per Day

HASP Health and Safety Plan

HQ Hazard Quotient

IDW Investigation Derived Waste

ISO International Organization for Standardization

Kg Kilogram L Liters

L/min Liters Per Minute

LA Libby Amphibole asbestos

MCE Mixed-Cellulose Ester

MET Meteorological

mm Millimeter

mm² Square Millimeter mph Miles Per Hour

ND Non-Detect

NOAA National Oceanic Atmospheric Administration

NSUA Non-Specific Use Area

NVLAP National Voluntary Laboratory Accreditation Program

OU Operable Unit

PCM Phase Contrast Microscopy

PCME Phase Contrast Microscopy Equivalent

PLM Polarized Light Microscopy

PLM-VE Polarized Light Microscopy – Visual Estimation

PLN Poisson Lognormal PM Project Manger

PPE Personal Protective Equipment

QA Quality Assurance

QAPP Quality Assurance Project Plan

QC Quality Control

RAM Real-Time Aerosol Monitor

RBF Risk-Based Fraction
RfC Reference Concentration

s/cc Structures Per Cubic Centimeter
SAP Sampling and Analysis Plan
SOP Standard Operating Procedure
SRC Syracuse Research Corporation

SUA Specific Use Area

SWQAPP Site-Wide Quality Assurance Project Plan

TEM Transmission Electron Microscopy

TL Team Leader

TWF Time Weighting Factor
UCL Upper Confidence Limit
ug/m³ micrograms per cubic meter

um micrometer UR Unit Risk

VCS Vermiculite Containing Soil

VI Vermiculite Insulation

yrs years

°F Degrees Fahrenheit
≥ Greater Than or Equal To
≤ Less Than or Equal To

Greater ThanLess ThanPercent

SAMPLING AND ANALYSIS PLAN FOR ACTIVITY-BASED OUTDOOR AIR EXPOSURE OPERABLE UNIT 4 LIBBY, MONTANA, SUPERFUND SITE

1.0 INTRODUCTION

This document is the Sampling and Analysis Plan (SAP) for the collection and analysis of samples of outdoor air in the immediate vicinity of activities that actively disturb outdoor soil at residential and commercial properties located within Operable Unit (OU) 4 of the Libby, Montana, Superfund Site. OU4 includes most current homes and businesses in the community of Libby.

This SAP contains the elements required for both a field sampling plan (FSP) and quality assurance project plan (QAPP). This SAP has been developed in accordance with the Environmental Protection Agency (EPA) Requirements for Quality Assurance Project Plans (EPA 2001), the Guidance on Systematic Planning Using the Data Quality Objectives Process – EPA QA/G4 (EPA 2006a), and the Site-Wide QAPP (SWQAPP) (CDM 2007a). The SAP is organized as follows:

Section 1 - Introduction

Section 2 – Background and Problem Definition

Section 3 – Data Quality Objectives (DQOs)

Section 4 – Sampling Program

Section 5 - Laboratory Analysis and Requirements

Section 6 – Assessment and Oversight

Section 7 – Data Validation and Usability

Section 8 – Project Schedule

Section 9 – References

2.0 BACKGROUND AND PROBLEM DEFINITION

Libby is a community in northwestern Montana that is located near a large open-pit vermiculite mine. Vermiculite from this mine contains varying levels of a form of asbestos referred to as Libby Amphibole asbestos (LA). Historic mining, milling, and processing operations at the Site are known to have caused releases of vermiculite and LA to the environment that have caused a range of adverse health effects in exposed people, including not only workers at the mine and processing facilities (Amandus and Wheeler 1987, McDonald et al. 1986, McDonald et al. 2004), but also in residents of Libby (Peipens et al. 2003).

Starting in 2000, EPA began taking a range of cleanup actions at the Site to eliminate sources of LA exposure to residents and workers. In the early stages, efforts were focused mainly on wastes remaining at former vermiculite processing areas (the screening plant, export plant, etc.). As work progressed, attention soon shifted to cleanup of current homes and workplaces in OU4. The protocol that EPA developed for investigating sources of LA at specific properties and deciding when to take action is detailed in a Technical Memorandum issued in December 2003 (EPA 2003). Cleanup actions taken under this protocol typically include removal of unenclosed vermiculite insulation (VI) from any living spaces and any other readily accessible spaces (e.g., unfinished attics), removal of some or all contaminated outdoor soils, and may, in some cases, include cleanup of indoor dusts.

2.1 Problem Definition

One issue of high priority to EPA is an evaluation of the efficacy of the current cleanup strategy. That is, answers are needed for the following questions:

- At a property that EPA has investigated and found no reason to take any cleanup actions under the approach described in EPA (2003), are the risks that remain sufficiently small to be considered acceptable?
- At a property where EPA has investigated and determined that one or more sources was present that required cleanup under the approach described in EPA (2003), are the risks that remain after the cleanup is complete sufficiently small to be considered acceptable?

Note: For convenience, in this document, the phrase "post-cleanup property" will be used to indicate any property where EPA has investigated sources and has either taken cleanup action or else tentatively determined that no cleanup action is needed.

Residual exposures and risks that may remain at post-cleanup properties may be divided into two main types:

- Exposures that occur inside the building
- Exposures that occur outside the building

This SAP is focused on collection of the data needed to support an evaluation of the residual level of exposure and risk that may exist outside the building at post-cleanup properties. Collection of data needed to evaluate residual exposures and risks from exposures that occur inside the building at post-cleanup properties is addressed in a separate sampling plan (EPA 2007).

There are several different pathways by which residents and workers in OU4 might be exposed to residual LA contamination in outdoor soil. It is currently believed that the most important of these is inhalation of air in the immediate vicinity of an active soil disturbance that causes a release of LA fibers from soil into air. For convenience, measurement of asbestos in air in the immediate vicinity of an active soil disturbance is referred to as "activity-based sampling" (ABS).

2.2 Overview of Existing Data

EPA has collected some initial data on the levels of LA that occur in air in association with active disturbance of outdoor soil (EPA 2005). In brief, these data include ABS personal and stationary air samples that were collected in association with three types of outdoor soil disturbance activities (digging, mowing, and raking) at several different locations with varying levels of LA in the soil. Air samples were evaluated by transmission electron microscopy (TEM) with an average sensitivity of about 0.001 structures per cubic centimeter (s/cc). Soil samples were collected from the same location as the soil disturbance and these were evaluated by polarized light microscopy (PLM) in accord with site-specific standard operating procedures (SOPs) that has been developed for use at Libby. This site-specific approach is referred to as polarized light microscopy-visual area estimation (PLM-VE). In this approach, soil levels are categorized semi-quantitatively into "bins", as follows:

PLM-VE Bin	Meaning	
A	Asbestos not detected	
Bl	Asbestos is detected at a level estimated to be ≤ 0.2%	
B2	Asbestos is detected at a level estimated to be > 0.2% but < 1%	
С	Asbestos is detected at a level estimated to be ≥ 1%	

Notes: PLM-VE - polarized light microscopy-visual area estimation: \leq - less than or equal to; > - greater than; < - less than; \geq - greater than or equal to; % - percent

The initial data¹ are summarized in Figure 2-1. As seen, there is wide variability (4-5 orders of magnitude) in the levels of LA seen in ABS air. However, there is an apparent trend toward higher levels of LA in air as a function of increasing LA levels in soil (as indicated by PLM-VE measurements of the soil).


While informative, these initial data are not sufficient to support reliable risk assessment or risk management decisions for the outdoor soil disturbance activity because of the following data limitations:


- Not enough samples have been collected to adequately limit statistical uncertainty
- Not enough samples have been collected to ensure adequate spatial and temporal (seasonal) representativeness of the data
- ABS locations where soil is characterized as "Bin A" [non-detect (ND)] by PLM-VE may actually represent a range of residual soil contamination levels, since some may be characterized by the absence of visible vermiculite, while others may be characterized by the presence of visible vermiculite. Additionally, the PLM-VE method, which has a practical quantitation limit of about 0.2% (weight) for LA, may simply not be sensitive enough to identify levels in soils that, when disturbed, generate asbestos levels in air that are of potential concern.

Thus, the primary problem that this SAP seeks to address is the lack of sufficient ABS outdoor air data in OU4 to support risk assessment and risk management decisions about risks from residual contamination in post-cleanup soils.

¹ These data have not yet been fully validated. Thus, the data should be considered tentative and revisions may occur.

FIGURE 2-1
TOTAL LA LEVELS IN PERSONAL ABS AIR SAMPLES NEAR SOIL DISTURBANCES





	Soil Category			
Martin	Clean Fill	PLM Bin A	PLM Bin B1	PLM Bin B2/C
Metric	<u> </u>	LL CIM DILLY	וט	020
N	21	10	21	13
DF	24%	60%	67%	77%
Max	0.006	0.150	1.34	0.23
95%	0.002	0.097	0.374	0.123
75%	0.000	0.003	0.037	0.023
50%	0.000	0.001	0.002	0.008
25%	0.000	0.000	0.000	0.003
5%	0.000	0.000	0.000	0.000
Mean	0.00059	0.019	0.12	0.029

Notes: s/cc - structures per cubic centimeter; PLM - polarized light microscopy, % - percent

3.0 DATA QUALITY OBJECTIVES

DQOs are statements that define the type, quality, quantity, purpose and use of data to be collected. The design of a study is closely tied to the DQOs, which serve as the basis for important decisions regarding key design features such as the number and location of samples to be collected and the chemical analyses to be performed. In brief, the DQO process typically follows a seven-step procedure, as follows:

- 1. State the problem that the study is designed to address
- 2. Identify the decisions to be made with the data obtained
- 3. Identify the types of data inputs needed to make the decision
- 4. Define the bounds (in space and time) of the study
- 5. Define the decision rule which will be used to make decisions
- 6. Define the acceptable limits on decision errors
- 7. Optimize the design using information identified in Steps 1-6

Following these seven steps helps ensure that the project plan is carefully thought out and that the data collected will provide sufficient information to support the key decisions which must be made. The following paragraphs implement the DQO process for this project.

3.1 State the Problem

EPA has been working to clean up both indoor and outdoor sources of VI, vermiculite-containing soil (VCS), and LA at properties in OU4. In order to help evaluate the efficacy and protectiveness of these cleanup activities, information is needed to characterize the level of residual risk from outdoor exposures that may remain at post-cleanup properties. Under the current approach (EPA 2003), the triggers for cleanup (removal and replacement with clean fill) of outdoor soil are summarized below:

<u>Mandatory Triggers</u> (these conditions always trigger a soil clean-up in the location exceeding the trigger)

- Any visible vermiculite in a specific use area (SUA)
- Gross vermiculite visible in a non-SUA (NSUA) area (e.g. yard)
- Any location where PLM-VE ≥ 1%

<u>Conditional Trigger</u> (this condition does not trigger a clean-up of the area unless some other trigger for cleanup has been exceeded at the property)

• Any area where PLM-VE is > ND but < 1%

Based on these procedures, the types and levels of LA and vermiculite that may remain in outdoor soil at a post-cleanup property are summarized below:

Case	Potential Residual Sources in Outdoor Soil
No cleanup triggers were exceeded either indoors or outdoors;	- non-gross visible vermiculite in any NSUA - PLM-VE < 1% in any area
no action taken	
2. One or more triggers were	- non-gross visible vermiculite in a yard NSUA
exceeded (either indoors and/or outdoors); cleanup action taken	(PLM-VE = ND)

Note: NSUA – non-specific use area; PLM-VE – polarized light microscopy-visual area estimation; < - less than; % - percent; ND – non-detect

Based on this, the problem to be addressed in this SAP is to obtain sufficient ABS outdoor air data to determine if any of these residual sources of LA contamination in outdoor soil pose an unacceptable risk to human health.

3.2 Identify the Decisions

The data to be collected during this effort are intended to support the following decisions:

1) Is the current strategy for cleaning up outdoor soil in OU4 adequate to provide health protection from exposures that occur when residents disturb the soil?

Note: The method that EPA currently recommends for estimating excess risk of lung cancer and mesothelioma from inhalation exposure to asbestos in air is described in IRIS (2007). This method is currently undergoing review, and the approach may be revised in the future as new methods are developed and as new toxicity data on asbestos are obtained. In addition, the EPA has not yet developed a method for assessing non-cancer risks from inhalation exposure to asbestos. Thus, it is important to stress that all evaluations of protectiveness that are based on currently available risk assessment methods should be viewed as interim, and these interim decisions may be revised in the future as methods and data for assessing the cancer and non-cancer risks of asbestos are improved.

2) If not, what characteristics of the soil (e.g., presence of visible vermiculite and/or PLM-VE result) can be used to recognize areas that require further clean-up?

3.3 Identify the Types of Data Needed

The data needed to achieve the objectives of this effort consist of accurate and reliable measures of LA in outdoor air during ABS activities at different locations characterized by a range of residual levels of LA in soil. The following sections identify key attributes of the data needed for this effort.

3.3.1 Sampling Locations

Based on the current protocol for cleanup actions at a property, yards (or sub-parts of yards) at post-cleanup properties may be categorized into five types, as follows:

Soil	Residual Source		
Category	PLM-VE Analysis for LA	Visual Presence of Vermiculite	
1	None (clean fill has been added)		
2	Bin A (ND)	No	
3	Bin A (ND)	Yes	
4	Bin B1 (<0.2%)	Either Yes or No	
5	Bin B2 (0.2% - 1%) Either Yes or No		

Notes: PLM-VE - polarized light microscopy-visual area estimation; LA - Libby Amphibole asbestos; ND - non-detect; < - less than; % - percent

In order to determine if these categories of residual soil contamination may pose an unacceptable human health risk, the locations (yards or parts of yards) investigated by ABS in this SAP must include a number of examples of each soil category. This stratification will also help increase the ability to determine if a clear exposure-response relationship can be detected.

Clean fill is used as a point of reference against which the other four categories of soil may be evaluated. Greatest emphasis is placed on stratification of soils that contain low levels of LA (ND by PLM-VE), since these soils are generally left in place. Stratification of areas with higher levels by PLM-VE is considered less important because most of these soils are presently cleaned up under the current strategy.

Whenever possible, locations for outdoor ABS testing will be selected from post-cleanup properties. However, if an adequate number of sampling locations can not be located, then appropriate locations that meet the bin definitions above may be selected from other properties.

3.3.2 Types of Air Samples

Experience at Libby and at other sites has demonstrated that, in general, personal air samples (i.e., samples that collect air in the breathing zone of a person) tend to be higher than air samples collected by a stationary monitor, especially if the person is engaged in an activity that disturbs an asbestos source such as contaminated soil. Because of this, this SAP will focus on the collection of personal air samples during ABS.

3.3.3 Target Analyte List

Each air sample that is collected must be analyzed for asbestos particles. Specific methods and counting rules are provided in Section 5. Results should include the size (length, width) of each particle, along with the mineral classification (LA, other amphibole, chrysotile).

3.3.4 Types of Soil Disturbances

Residents may disturb soil in their yards by a wide variety of different activities. Conceptually, the ideal data set would include ABS data from many different types of disturbance that span the full range of intensities that may occur under residential land use. However, it is not feasible to evaluate every possible type of disturbance. Rather, this assessment will focus on three standardized activities which are considered to be realistic examples of relatively vigorous disturbances:

- Raking the lawn or yard with a metal-tined leaf rake
- Mowing the yard with a gasoline powered rotary lawn mover
- Digging in the soil with a shovel and pail (simulating a child's play)

3.3.5 Soil Condition Data

It is expected that the amount of dust (and asbestos) released from an ABS event may depend in part on the condition of the soil at the time of the ABS event. In order to help characterize this source of variability, and potentially to allow for some degree of normalization between locations, the following data items are needed for each ABS test area:

- Nature and extent of soil vegetative cover (documented in field notes and photographs)
- Real-time aerosol monitors (RAMs) set up in the immediate proximity of the ABS
 disturbance to measure dust levels in air in units of micrograms per cubic meter (ug/m³)
- · Soil moisture
- Soil texture

3.4 Define the Bounds of the Study

3.4.1 Spatial Bounds

The spatial bounds of this study are restricted to post-cleanup properties located within OU4 of the Libby Superfund Site. This OU includes most current residential and commercial properties in the community. Note, however, that the results of this study may also be useful in assessing cleanup efficacy under similar conditions in other OUs at the Site.

3.4.2 Temporal Bounds

Estimation of human health risk from exposure to LA in outdoor air following a series of active outdoor soil disturbances is based on the average concentration that occurs across the series of disturbances. Because the level of LA in outdoor ABS air may depend on factors that vary seasonally (disturbance patterns, soil moisture, wind speed, humidity, etc.), the data set needed for this effort should ideally consist of multiple samples from each area, spanning a range of time points and meteorological conditions. This will help ensure that reliable estimates of long-term average concentrations may be computed from the individual short-term measurements. The exact dates of ABS sampling are not important and may be selected at random (since the goal is to capture temporal variability). However, all samples collected in the summer of 2007 should be collected under conditions when the soil is relatively dry (less than 1/10-inch of rain within the past 36 hours), and a field moisture deficiency of at least 50% (see Section 4.2.2, below), to help ensure that the data are not biased low. For samples collected in the spring of 2008, ABS sampling should not occur if rainfall has exceeded ¼ inch in the past 36 hours. Home owners will be asked to not water or irrigate the portion of the property will ABS will be occurring starting 36 hours before sample collection.

During days when outdoor ABS activities are scheduled, meteorological (MET) weather station data will be downloaded from the local National Oceanic Atmospheric Administration (NOAA) station, LBBM8 to calculate the total accumulation of rain.

3.5 Define the Decision Rule

The decision rule for evaluating residual risks from disturbance of outdoor soils at post-cleanup properties is:

If the level of risk to humans from exposure to ABS air at a post-cleanup location, when combined with the level of risk which applies to the same individuals from other applicable exposure pathways, does not exceed a cancer risk of 1E-04 or a non-cancer Hazard Quotient (HQ) of 1.0, then risks at that location will be considered acceptable. If the total risk exceeds

a cancer risk of 1E-04 or an HQ of 1.0, then the feasibility of further reducing exposure from either the outdoor soil disturbance pathway and/or the other applicable exposure pathways at that location shall be assessed.

At present, EPA has not developed a quantitative procedure for evaluating non-cancer risks, but has developed a method for quantification of cancer risk (IRIS 2007). The basic equation is:

$$Risk(i) = C(i) \cdot TWF(i) \cdot UR(i)$$

were:

- Risk(i) = Risk of dying from a cancer that results as a consequence of exposure from specified exposure scenario "i"
- C(i) = Average concentration of asbestos fibers in air in units of fibers per cubic centimeter (f/cc) during exposure scenario "i"
- $UR(i) = Unit Risk (f/cc)^{-1}$ that is appropriate for exposure scenario "i"
- TWF(i)= Time weighting factor for exposure scenario "i". This factor accounts for less-than-continuous exposure during the exposure interval.

Because each person can be exposed from more than one source, the total cancer risk is calculated by summing the risks from each exposure pathway that applies:

Total risk =
$$\Sigma$$
 Risk(i)

As noted above, this document is focused on collection of data on the concentration of asbestos that occur in the breathing zone of people who are engaged in activities that disturb outdoor soil. These data will be used to evaluate the risk from the soil-disturbance pathway. This risk estimate will, in turn, be combined with risk estimates for other pathways to estimate total exposure.

As noted above, because of limitations in the current methods for assessing risks from asbestos, all decisions regarding residual risk levels are considered interim, and interim decisions may be revisited in the future as new methods and new data become available.

3.6 Define the Acceptable Limits on Decision Errors

In making decisions about the long-term average concentration of LA in outdoor ABS air and the level of health risk associated with that exposure, two types of decision errors are possible:

- A <u>false negative</u> decision error would occur if a risk manager decides that exposure to ABS air is not of significant health concern, when in fact it is of concern.
- A <u>false positive</u> decision error would occur if a risk manager decides that exposure to ABS air is above a level of concern, when in fact it is not.

EPA is most concerned about guarding against the occurrence of false negative decision errors, since an error of this type may leave humans exposed to unacceptable levels of LA in indoor air. For this reason, it is anticipated that decisions regarding this pathway will be based not only on the best estimate of the long term average concentration, but will also consider the 95% upper confidence limit (UCL) of the long-term average concentration. Use of the UCL to estimate exposure and risk helps account for limitations in the data, and provides a margin of safety in the risk calculations, ensuring that risk estimates are unlikely to be too low.

EPA is also concerned with the probability of making false positive decision errors. Although this type of decision error does not result in unacceptable human exposure, it may result in unnecessary expenditure of resources. For the purposes of this effort, the strategy adopted for controlling false positive errors is to set a goal that, if the exposure estimate based on the 95% UCL is above EPA's level of concern for this pathway, then the UCL is not larger than 3-times the best estimate of the mean. If the 95% UCL is at or above the range that is of potential concern, and the UCL is greater than 3 times the best estimate of the mean, then it will be concluded that there is a substantial probability of a false positive decision error and that more data may be needed to strengthen decision-making.

3.7 Optimize the Design

3.7.1 Limiting the Uncertainty in Estimates of Long-Term Average Concentration The method used to compute the UCL of a set of indoor air samples depends on the statistical properties of the data set. For samples from the Libby Site, the data are believed to be reasonably well represented by a Poisson lognormal (PLN) distribution, and the parameters of the PLN can be derived using a fitting procedure described by Haas et al. (1999). The fitted parameters (μ and σ) may then be used to compute the UCL of the mean using the approach for lognormal data sets described in EPA (1992). Based on this approach, the ratio of the UCL to the mean of a data set (an indication of the statistical uncertainty in the data) is given by:

$$\frac{UCL}{Mean} = \exp\left(\sigma H / \sqrt{(n-1)}\right)$$

where:

 σ = log standard deviation of the measured values

H = statistic described in EPA (1992)

n = number of samples

Figure 3-1 illustrates the ratio of the UCL to the mean as a function of n for an assumed value of σ of 2.0 (geometric standard deviation = 7.4). As seen, the ratio (a measure of uncertainty) approaches a value of about 2 as the number of samples approaches about 80-100, and continues to decline slowly as the number of samples increases. Based on this analysis, it is expected that if a total of about 80-100 samples per soil type were collected, the uncertainty in the average ABS air concentration for that soil type would be limited to less than a factor of 3, and that collection of additional samples would result in only minor decreases in uncertainty. Because three different types of ABS samples will be collected per soil location at each of two different times, if there were 15 locations per soil category, this would result in a total of 3 x 2 x 15 = 90 measurements per soil category, which should result in an acceptable limit on the width of the uncertainty bounds around the long-term average ABS air value for the soil category.

3.7.2 Estimating the Required Analytical Sensitivity for Outdoor Air

For the purposes of this effort, the analytical sensitivity that is needed for analysis of ABS air samples should be sufficient to ensure reliable detection and quantification if risks from outdoor ABS air approach or exceed a level of health concern. The choice of the level of concern is complicated by the fact that residents and workers in Libby may be exposed to asbestos by more than one pathway, and hence risk management decisions must consider the total (cumulative) risk from all pathways combined. With this in mind, the target level of concern for the outdoor ABS pathway alone is set at a cancer risk of 1E-05 (1 in 100,000) or a non-cancer HQ of 0.1. That is, the target sensitivity is selected such that, if the true concentration of LA in outdoor ABS air corresponds to a risk that could contribute risk 1/10 the total level of concern (1E-04), the concentrations in air would be readily detectable and quantifiable with good confidence. If the true concentration corresponds to a risk that is less than 1/10 the total level of concern, exact quantification of the pathway becomes less important.

The concentration of LA in outdoor ABS air that is associated with a risk level of 1E-05 is derived from the basic risk equations described above, simply by solving for the concentration that yields a risk of 1E-05:

$$1E-05 = C(air) \cdot TWF \cdot UR$$

 $C(air) = 1E-05 / (TWF \cdot UR)$

Note that the type of fibers included in this concentration is defined by the risk model. For example, the current EPA approach is based on phase contrast microscopy (PCM) fibers, which are defined as asbestos fibers longer than 5 micrometers (um), thicker than 0.25 um, and with an aspect ratio greater than 3:1. For convenience, the fibers used in a risk model are called "risk-based fibers".

In most cases, the risk-based fibers are only a sub-set of the total asbestos fibers present in air. The fraction of fibers that are risk-based is referred to as the "risk-based fraction" (RBF):

$$RBF = C(risk-based) / C(total)$$

At the Libby site, current analytical methods focus on measuring the concentration of total fibers, and sufficient data have accumulated to estimate the RBF with good accuracy. Thus, the concentration of risk fibers may be calculated from a measure of total fibers as follows:

$$C(risk=based) = C(total) \cdot RBF$$

This approach provides an estimate of the concentration of risk-based fibers that has lower statistical uncertainty than if only risk-based fibers were measured, and may be applied to any risk model that may be of interest.

Combining these two equations and rearranging to solve for the concentration of concern associated with a specified risk level (1E-05) for this exposure scenario yields the following:

Concentration of Concern (Total TEM s/cc) =
$$(1E-05)/(RBF \cdot TWF \cdot UR)$$

For planning purposes, it is conservatively assumed that the TWF for exposure to ABS air is 0.04. This value would correspond to an outdoor soil disturbance frequency of 8 hours per day (hrs/day), 60 days per year (days/yr) for 50 years (yrs). It is considered likely that most residents will have soil disturbance exposures that are considerably less than this assumption, although this value might be realistic for some types of tradespersons whose work regularly involves outdoor yard or soil disturbance activities.

Based on EPA's currently recommended cancer risk model (IRIS 2007), the unit risk factor for lifetime exposure is 0.23 per phase-contrast microscopy (equivalent) (PCME) f/cc. Based on particle size data from the Libby Site, the fraction of total LA fibers in air that are PCME fibers is about 0.45. Thus, the concentration of concern for total LA in outdoor ABS air would be about:

Concentration of cancer concern (1E-05 risk level) = $(1E-05) / (0.04 \cdot 0.45 \cdot 0.23) = 0.0024$ s/cc

As noted previously, this concentration of concern may be revised in the future as methods and data for asbestos cancer risk evaluation are improved. In order to at least partially account for potential future changes, the target analytical sensitivity for evaluating cancer risk is set to a somewhat lower value of 0.001 cc⁻¹.

For non-cancer effects, the basic risk equation is:

$$HQ = C \cdot (ET/24 \cdot EF/365 \cdot ED) / RfC$$

where:

HQ = hazard quotient (dimensionless)

C = long-term average concentration of asbestos in air (f/cc), expressed in the same units as used in the reference concentration (RfC)

ET = exposure time (hrs/day)

EF = exposure frequency (days/yr)

ED = exposure duration (yrs)

RfC = reference concentration (f/cc-yrs)


EPA toxicologists are currently working to develop an RfC for asbestos based on available data on LA and other forms of asbestos, but at present, no value has been finalized or approved for use. Therefore, it is not yet possible to compute an analogous level of concern for this endpoint. In the absence of data, it is tentatively assumed that the target analytical sensitivity that is adequate for evaluating cancer risk will also be sufficient for evaluating non-cancer risks. This assumption will be re-visited when an RfC is approved for use.

Assuming that most ABS samples will be collected in the field on filters that are 385 square millimeters (mm²) and that the collection volume is about 1,200 liters (L) [120 minutes x 10 liters per minute (L/min)], the number of grid openings (GOs) that will require analysis in order to achieve a target analytical sensitivity of 0.001 cc⁻¹ is about 30. However, if the soil disturbance results in high dust levels in air, the filter may be overloaded, requiring an indirect preparation. In this case, the number of GOs needed to achieve the target sensitivity may be 3 to 100 fold higher. In the event that the number of grid openings requiring analysis becomes time- or cost-prohibitive, it is generally better to increase the analytical sensitivity somewhat (e.g., 0.002 or 0.003 cc⁻¹), rather than decrease the number of samples collected and analyzed (EPA 2007).

3.7.3 Refinements to the Design as Data are Collected

In accord with EPA's DQO process, it is expected that the ABS program described in this document may be modified periodically as data are obtained. For example, if data suggest that there is little variability as a function of season, then EPA may decrease the number of sampling events over time. Alternatively, if data suggest that the variability in concentrations is higher than expected, then additional samples may be added to better limit the uncertainty in the values. Similarly, the target analytical sensitivity may be either increased or decreased, depending on the detection frequency, mean values, and sample variability observed in initial samples results, and on the RfC value when it becomes available. Finally, the design may be revised if new methods for evaluating cancer or non-cancer effects are developed and approved for used by EPA.

FIGURE 3-1 EXAMPLE UNCERTAINTY IN THE MEAN OF A LOGNORMAL DATA SET WITH σ = 2.0



Notes: UCL - upper confidence limit

4.0 SAMPLING PROGRAM

The following sections summarize field activities that CDM will perform during the outdoor ABS investigation. All activities will be performed in accordance with this SAP. Field personnel will refer to the SWQAPP (CDM 2007a) sections listed below for details regarding requirements referenced in this SAP:

SWQAPP Section Number	Section Title	
3.1	Sample Collection	
3.2.1	Drafting and Approval of Governing Documents	
3.2.2	Field Planning Meetings	
3.2.3	Field Team Training Requirements	
3.2.4	Field Logbooks	
3.2.5	Field Sample Data Sheets (FSDSs)	
3.2.6	Investigation Specific Field Forms	
3.2.7	Photographic Documentation	
3.2.8	Global Positioning System (GPS) Point Collection	
3.2.9	Field Equipment Maintenance	
3.2.10	Handling Investigation Derived Waste (IDW)	
3.2.11	Field Sample Custody and Documentation	
3.2.12	Sample Packaging and Shipping	
3.2.13	Modification Forms	
3.2.14.1	Field Surveillances	
3.2.14.2	Field Audits	

The SOPs and site-specific procedures to be utilized during this sampling event are listed below and included in Appendix A:

- Sample Custody (Modified SOP 1-2)
- Packaging and Shipping of Environmental Samples (Modified SOP 2-1)
- Guide to Handling of Investigation-Derived Waste (Modified SOP 2-2)
- Field Logbook Content and Control (Modified SOP 4-1)

- Photographic Documentation of Field Activities (Modified SOP 4-2)
- Field Equipment Decontamination at Nonradioactive Sites (Modified SOP 4-5)
- Control of Measurement and Test Equipment (SOP 5-1)
- Sampling of Asbestos Fibers in Air (EPA-LIBBY-01)
- Site-Specific SOP for Soil Sample Collection (CDM-LIBBY-05, Revision 2)
- Site-Specific SOP for Semi-Quantitative Visual Estimation of Vermiculite in Soil (CDM-LIBBY-06, Revision 1) with modifications
- Site-Specific SOP for GPS Coordinate Collection and Handling (CDM-LIBBY-09, Revision 0)
- Activity-Based Air Sampling for Asbestos (EPA Emergency Response Team [ERT] #2084) with modifications

4.1 Pre-Sampling Activities

Prior to beginning field activities, sampling locations will be selected, community coordination will be conducted (owners will be contacted to determine their willingness to participate in the program), a field planning meeting will be conducted, any required trainings will be conducted, and an inventory and procurement of supplies will be performed.

4.1.1 Selection of Sampling Locations

As discussed in Section 3.3, it is important that the locations selected for ABS be representative of the types and levels of residual sources that may remain at post-cleanup locations. The five soil categories that may exist at a property are:

Soil	Residual Source		
Category	PLM-VE Analysis for LA	Visual Presence of Vermiculite	
1	None (clean fill)		
2	ND (Bin A)	No	
3	ND (Bill A)	Yes	
4	Bin B1	Either Yes or No	
5	Bin B2	Either Yes or No	

Notes: PLM-VE - polarized light microscopy-visual area estimation; LA - Libby Amphibole asbestos; ND - non-detect

The target number of homes in each category is 15 (75 total). To the extent possible, the 15 locations in each soil category will be selected to provide a reasonable spatial representation in OU4. In order to achieve this objective, the list of all post-cleanup properties in OU4 will first

be stratified according to the presence of the five soil categories above, and then into three different sub-areas (north, central, and south), as shown in Figure 4-1. CDM's Community Involvement Coordination (CIC) staff will then contact the residents at the properties in each category in each sub-area to determine if they are willing to participate in this investigation. The objective is to obtain about equal number of locations from residents in each sub-area for each soil category. Also, to the extent possible, the number of locations for Soil categories 4 and 5 will be divided approximately evenly between the presence and absence of visible vermiculite.

When outdoor ABS activities are conducted at a property where indoor ABS is also planned, the indoor activities will be completed on a different day than the outdoor activities, with a preference for the indoor to occur before the outdoor activities whenever possible.

4.1.2 Community Coordination

A CDM CIC will contact each resident to describe the program and the potential impact to the resident (e.g., requirements for temporary relocation and the expected duration of the program). The property owner will be advised of the study's duration, sampling frequency, and will be informed of the importance of obtaining samples consistently over that extended time period. The property owner will have the opportunity to accept or decline their participation in this investigation before sampling is started on their property under this SAP. Upon acceptance, the property owner will receive an access agreement to sign. Access agreements will be obtained prior to the start of sample collection. Property-specific background information will also be collected by the CIC on the ABS Property Background and Sampling Form included in Appendix B. If information collected on the ABS investigation form is inconsistent with data collected during previous investigations, the current override system of updating property information in the project database (Libby2) will be used.

4.1.3 Field Planning Meeting

A field planning meeting will be conducted in accordance with the procedures detailed in Section 3.2.2 of the SWQAPP (CDM 2007a).

4.1.4 Training Requirements

Training requirements described in Section 3.2.3 of the SWQAPP (CDM 2007a) will apply to personnel conducting sample collection activities described in this SAP.

4.1.5 Inventory and Procurement of Equipment and Supplies

The following equipment are needed for sampling activities, and any required equipment not already contained in the field equipment supply inventory will be procured prior to initiation of

sampling activities:

- · Field logbooks
- Indelible ink pens
- · Digital camera
- Video camera
- Sample cassettes: 0.8 um pore, 25 millimeter (mm) diameter, mixed cellulose ester (MCE) filter cassettes
- Sample paperwork and sample tags/labels
- Custody seals
- Zipper-top baggies
- Air sampling pumps
- Tygon tubing
- Rotameters
- Personal protective equipment (PPE) as required by the site Health and Safety Plan (HASP)
- DataRAM
- Portable MET Station

4.2 Sample Collection

As noted above, the goal is to collect ABS samples for three different disturbance activities at two different time points for 15 different locations for five different soil categories (total = 450 disturbance activities). The following sections describe the sample collection procedure for each sampling event.

4.2.1 Outdoor Air Sampling

Sampling will occur over a 6-hour time interval, divided into three sub-periods of 2-hours each with air samples collected separately for each 2-hour sub-period. The activities to be conducted will occur in the following order:

- Period 1 raking
- Period 2 child play
- Period 3 lawn-mowing

Each of the activities will be conducted in accordance with EPA ERT SOP #2084, Activity-Based Air Sampling for Asbestos, with project-specific modifications (Appendix A). At properties where multiple soil categories are present (e.g., subparts of yard with clean fill as well

as subparts of yard with visual vermiculite that were sampled ND by PLM) the activity area with the lowest anticipated contamination will be tested first.

Personal Air Samples

Personal air samples will be collected from the breathing zones of the event participants in accordance with EPA-LIBBY-01, provided in Appendix A. The breathing zone can be visualized as a hemisphere approximately 6 to 9 inches around an individual's face. Personal air samples will be collected at two flow rates using two different types of pumps during each two-hour event, with a new sample started at the beginning of each new period. The flow rates for sample collection should be 10 and 3.5 L/min resulting in target volumes of 1,200 and 420 L, respectively. These flow rates were chosen for this sampling event in order to maximize the volume of air collected which in turn helps achieve the analytical sensitivities required for risk assessment evaluations. For all asbestos sampling, an asbestos sampling train consisting of 0.8 um, 25 mm MCE filter connected to a sampling pump will be used. The top cover from the cowl extension on the sampling cassette shall be removed ("open-face") and the cassette oriented face down.

Both the high volume and low volume samples will be submitted to the laboratory for analysis. If the higher volume sample is not readable by TEM after a direct preparation method, either the lower flow sample may be evaluated for analysis by direct preparation, or the higher flow sample may be used by applying an indirect sample preparation technique. The laboratory must consult with EPA in order to select which is the most appropriate approach to follow.

If it is necessary to relieve a participant from an activity, a relief (backup) participant will be properly suited in time to make the exchange. When the relief participant is ready, the activity participant will stop, remove the backpack or belt, pass it to the relief participant, and assist the relief participant with donning and adjusting the backpack or belt. The exchange is anticipated to take less than 60 seconds, so the sampling pumps and event time clock will not be halted during the exchange. If the exchange requires more than 60 seconds, the pump and event clock will be stopped until activity is re-initiated.

Pump Fault and Flow-Rate Error Procedures

Pump flow rates will be verified at 30 minute intervals or when participants are relieved from an activity by a backup participant, whichever occurs sooner. If at any time the observed flow rates are $\pm 10\%$ of the target rate, the sampling pump should be re-calibrated. If at any time an air sampling pump is found to have faulted or the observed flow rates are 30% below or 50% above the target rate, Figure 4-2 should be consulted to determine the appropriate action. The time elapsed from the start of the activity until the fault/flow observation will be used to determine the appropriate action according to Figure 4-2.

To calculate the percentage of an observed flow to the target flow, the following formula is used:

$$X\% = \frac{Observed \ Flow \ Rate (L/min)}{Target \ Flow \ Rate (L/min)} \cdot 100$$

Figure 4-3 illustrates the number of grid openings that will require analysis to achieve the target sensitivity (0.001 cc⁻¹) when there is a pump fault and the collection time is less than target (2 hours).

MET Station Data

A portable MET station will be deployed to record parameters representative each sampling location. The following parameters will be recorded every 30 seconds during each event: wind speed, wind direction, relative humidity, temperature, and barometric pressure. The meteorological station should be placed close enough to the activities so the observations of the MET station reflect the conditions of the activity area.

In addition, during days when ABS activities are occurring, MET will be downloaded from the local NOAA station, LBBM8. The following parameters are recorded hourly at this station:

- temperature (degrees Fahrenheit [°F])
- dew point (°F)
- relative humidity (%)
- wind speed (miles per hour [mph])
- wind gust (mph)
- wind direction
- solar radiation (watts per square meter per hour [watts/m² per hour])
- precipitation (inches)

Copies of all MET station data will be provided to EPA and Syracuse Research Corporation (SRC) within one week after collection. Electronic copies have been determined to be suitable and will be placed in the project e-room.

RAM Data

One DataRAM 4TM or equivalent will be place immediately next to each ABS activity area in the dominant downwind direction. The DataRAM will be programmed to log the observed

concentration of particulates 0.1 um and larger every 5 seconds. Data will be downloaded daily and copies of all DataRAM data will be provided to EPA and SRC within one week after collection. Electronic copies have been determined to be suitable and will be placed in the project e-room.

4.2.2 Outdoor Soil Sampling

The area where ABS activities are performed will be delineated with stakes, pin flags, or equivalent visual markers. At each ABS sampling location included in this effort, one 30-point composite soil sample will be collected from each activity area. The soil samples will be collected so that the entire ABS area is represented by the sample. Soil samples will be collected and homogenized in accordance with the Site-Specific SOP for Soil Sample Collection (CDM-LIBBY-05, Revision 2) provided in Appendix A, with the exception that the soil will not be wetted with water before collection.

In order to ensure that sufficient sample is available for potential future investigations, the mass of the composite sample must be no less than 2.0 kilograms (kg).

A sketch of the outdoor yard will also be prepared to indicate the approximate locations and size of the ABS activity area. The sketch should indicate the soil condition at the ABS location, including the extent of vegetative cover and any other important visual features. The sketch should also indicate the approximate location and level of any visible vermiculite in the yard, and the approximate boundary of the area selected for the ABS area(s). This should be done in accordance with the Site-Specific SOP for Semi-Quantitative Visual Estimation of Vermiculite in Soil (CDM-LIBBY-06, Revision 1) with the following modifications:

- All areas of the property will be divided into zones and inspected for visual vermiculite regardless of previous excavations or presence of LA
- Interior surfaces (e.g., crawlspace, shed floor) will not be inspected for visual vermiculite
- Semi-quantitative estimates of vermiculite observed during sample collection will be recorded on FSDS and not on the Visual Vermiculite Estimation Form.

Outdoor soil sampling and observations shall occur close to the time that the outdoor air samples are collected. If these cannot be carried out in sequence (within the same 24-hour period), the field team should note this in the field logbook.

Soil moisture will be estimated for each ABS activity area by the hand appearance method that provides results in percent of field capacity. This is performed by firmly squeezing a handful of

soil and comparing the results to the table below. For each ABS area soil used for this evaluation should be collected from the center of the area and be from 0 to 2 inches below ground surface. ABS activities will not be performed if the soil moisture deficiency is less than 50%.

Field Test for Moisture Content – Interpretation Table				
% Soil Moisture Deficiency	Moderately coarse texture	Medium texture	Fine and very fine texture	
0 (field capacity)	Upon squeezing, no free water appears on soil but wet outline of ball is left on hand.			
0 to 25	Forms weak ball, breaks	Forms ball, very pliable,	Easily ribbons out	
	easily when bounced in	slicks readily.*	between thumb and	
	hand.*	-	forefinger.*	
25 to 50	Will form ball, but falls apart when bounced in hand.*	Forms ball, slicks under pressure.*	Forms ball, will ribbon out between thumb and forefinger.*	
50 to 75	Appears dry, will not form ball with pressure.*	Crumbly, holds together from pressure.*	Somewhat pliable, will ball under pressure.*	
75 to 100	Dry, loose, flows through fingers.	Powdery, crumbles easily.	Hard, difficult to break into powder.	
*Squeeze a handfi	il of soil firmly to make bal	I test.		

In addition to estimating soil moisture content in the field, 10% of soil samples submitted for asbestos analysis will also be analyzed for moisture content using American Society for Testing and Materials (ASTM) Method D2216-05: Standard Test Methods for Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass.

In addition, soil texture will be determined as prescribed by United States Department of Agriculture, Natural Resources Conservation Service techniques (see modification to ERT SOP #2084 in Appendix A). The result will be recorded on the ABS Property Background and Sampling Form.

4.3 General Processes

4.3.1 Equipment Decontamination

Decontamination of air sampling pumps and soil sampling equipment will be conducted as described in Sections 3.1.1.2 and 3.1.3.2 of the SWQAPP (CDM 2007a). Equipment used

during activities will be decontaminated after each use as described in ERT SOP #2084 with project-specific modification.

4.3.2 Sample Labeling and Identification

Sample index identification numbers will identify the samples collected during this study by having the following format:

EX-#####

Where:

EX = Exterior Activity Based Sampling

= a sequential five digit number

4.3.3 Videotape Documentation

A videotape will be prepared to document a representative example of each activity including any special conditions or circumstances that arose during the activity. File names will be in the format:

last name of property owner_address_EABS_date , where:

EABS = Exterior Activity Based Sampling

 $Date = MM_DD_YY$

4.3.4 Field Logbooks

Field logbooks will be completed and managed as described in Section 3.2.4 of the SWQAPP (CDM 2007a). CDM SOP 4-1, Field Logbook Content and Control including project-specific modification is provided in Appendix A. Copies of all logbook entries will be provided to EPA and SRC within one week of collection. Electronic copies are suitable and will be placed in the project e-room within one week after the completion of each sampling event.

4.3.5 FSDSs

FSDSs will be completed and managed as described in Section 3.2.5 of the SWQAPP (CDM 2007a). Appendix C contains copies of the specific FSDSs that will be used to record information for samples collected during the activities described in this SAP. Copies of FSDSs will be provided to EPA and SRC within one week of collection. Electronic copies are suitable and will be placed in the project e-room within one week after the completion of each sampling

event.

4.3.6 Photographic Documentation

Photographs will be collected, documented, and managed as described in Section 3.2.7 of the SWQAPP (CDM 2007a). CDM SOP 4-2, Photographic Documentation of Field Activities including project-specific modification is provided in Appendix A. Photographs will be used to document areas where outdoor activities are conducted. File names will be in the format:

last name of property owner_address_EABS_date, where:

EABS = Exterior Activity Based Sampling

Date = $MM DD_YY$

4.3.7 GPS Point Collection

GPS location coordinates will be collected as described in Section 3.2.8 of the SWQAPP (CDM 2007a) and in accordance with CDM-LIBBY-09, provided in Appendix A. As related to the activities described in the SAP, one set of coordinates will be collected from the center of each activity area. These coordinates will also represent the GPS coordinates associated with soil samples collected from the area. GPS coordinates will also be collected for the MET station.

4.3.8 Field Equipment Maintenance

Air sampling pump calibrations will be conducted and documented as described in Section 3.1.1.2 of the SWQAPP (CDM 2007a). Field equipment maintenance will be conducted and documented as described in Section 3.2.9 of the SWQAPP (CDM 2007). CDM SOP 5-1, Control of Measurement and Test Equipment, is provided in Appendix A.

4.3.9 Handling IDW

IDW will be managed as described in Section 3.2.10 of the SWQAPP (CDM 2007a). CDM SOP 2-2, Guide to Handling of IDW, including a project-specific modification is provided in Appendix A.

4.3.10 Field Sample Custody and Documentation

Field Sample Custody and documentation will follow the requirements described in Section 3.2.11 of the SWQAPP (CDM 2007a). CDM SOP 1-2, Sample Custody, including a project-

specific modification is provided in Appendix A. Copies of all chain-of-custody (COCs) forms will be provided to EPA and SRC within one week of collection. Electronic copies are suitable and will be placed in the project e-room within one week after the completion of each sampling event.

4.3.11 Sample Packaging and Shipping

Sample packaging and shipping will follow the requirements described in Section 3.2.12 of the SWQAPP (CDM 2007a). CDM SOP 2-1, Packaging and Shipping of Environmental Samples, including a project-specific modification is provided in Appendix A.

4.3.12 Modification Forms

All deviations will be documented and recording according the requirements described in Section 3.2.13 of the SWQAPP (CDM 2007a). A copy of the modification form is provided in Appendix D.

4.3.13 Field Surveillances and Audits

Field surveillances and audits will be conducted according to the requirements described in Section 3.2.14 of the SWQAPP (CDM 2007a).

4.4 Quality Assurance/Quality Control (QA/QC) Activities

The QA/QC actions required for each process described in this SAP will follow the requirements described in the SWQAPP (CDM 2007a).

Collection of QA/QC Field Samples

QA/QC samples will be collected according to the procedures described in the SWQAPP (CDM 2007a). All QA/QC field samples will be collected at the frequencies described in the SWQAPP with the exception of the frequency of drying blanks, co-located samples, and field blanks for air samples. It is expected that drying air sample cassettes will not be required for this activity. One field blank will be collected at each property where activities are conducted. Co-located samples will not be collected as one high volume sample and one low volume sample will be collected simultaneously. Table 4-1 summarizes the QA/QC sample collection and analysis frequencies for the outdoor ABS investigation.





FIGURE 4-2
PROCEDURES FOR PUMP FAULT AND FLOW-RATE ERRORS



Notes: < - less than; > - greater than; \le - less than or equal to; % - percent; DQOs - data quality objectives

FIGURE 4-3
EFFECT OF PUMP TIME ON GRID OPENINGS REQUIRED




Table 4-1 Summary of Field QC Samples by Media

Media	Sample Type	Minimum Collection Frequency	Minimum Analysis Frequency	Acceptance Criteria	Acceptance Criteria Failure Action
	Lot Blank	1 per 500 cassettes	1 per 500 cassettes	ND for all asbestos	Rejection of all cassettes in lot
Air	Field Blank 1 per property per day		10% of total collected per week	ND for all asbestos fibers	Analysis of additional field blanks to determine source of potential cross-contamination, qualification of sample results, evaluation of field sample handling procedures
	Co-located	Not Required	0%	NA	Evaluation of sample collection techniques
Soil	Field Duplicate	1 per 20 samples	100%	>90% RPD	Evaluation of sample collection techniques

Notes: QC - quality control; ND - nondetect; RPD - relative percent difference; COC - chain of custody; NA - not applicable

5.0 LABORATORY ANALYSIS AND REQUIREMENTS

All laboratories that analyze samples collected as part of this project must participate in and have satisfied the certification requirements in the last two proficiency examinations from the National Institute of Standards and Technology/National Voluntary Laboratory Accreditation Program (NVLAP). The laboratory must also analyze performance evaluation samples when requested. These analyses must be performed to confirm laboratory capabilities before any samples are submitted to the laboratory and may be subsequently submitted at regular intervals. In addition, the laboratory must participate in the laboratory training program developed by the Libby laboratory team.

5.1 Analytical Methods

5.1.1 Air

All outdoor air samples will be submitted to a subcontracted laboratory for analysis using the International Organization for Standardization (ISO) TEM method 10312, also known as ISO 10312:1995(E) (CDM 2003), with all applicable project specific modifications, including LB-000016, LB-000019, LB-000028, LB-000029, LB-000029a, LB-000030, LB-000053, and LB-000066a (CDM 2003b). All asbestos structures (including not only Libby amphibole but all other asbestos types as well) that have appropriate diffraction patterns and EDS spectra, and having length greater than or equal to 0.5 um and an aspect ratio \geq 3:1, will be recorded on the Libby site-specific laboratory data sheets and electronic deliverables.

The target analytical sensitivity for all ABS air samples is 0.001 cc⁻¹. All air field blanks collected as part of this program will be analyzed by counting a number of grid opens that is approximately equal to the number of rid openings that are analyzed for field samples. It is expected that this will be about 30 grid openings.

As described in the latest version of laboratory modification LB-000029, the frequency for laboratory-based QC samples for TEM analysis is:

Lab blank = 4%

Recount same = 1%

Recount different = 2.5%

Re-preparation = 1%

Verified analysis = 1%

Inter-laboratory = 0.5%

5.1.2 Soil

All soil samples collected as part of this effort will be analyzed for asbestos by PLM-VE in accord with SOPs SRC-LIBBY-01, Revision 2 and SRC-LIBBY-03, (Revision 2.

A random subset of about 10% of all soil samples collected as part of this outdoor ABS effort will be analyzed for soil moisture content in accord with ASTM D2216-05: Standard Test Methods for Laboratory Determination of Water (Moisture) Content of Soil.

5.1.3 Sample Archival

All air samples will be distributed to a project laboratory for analysis. Both the high volume and low volume samples will be sent to the same laboratory. Once analyzed, all samples will be stored (archived) at the laboratory under COC until further notice.

Aliquots of soil samples not sent for immediate analysis will be archived at the Soil Preparation Laboratory in accord with standard practice, as detailed in the latest version of the Close Support Facility Soil Preparation Plan.

5.2 Analytical Sensitivity for TEM Analyses

As discussed in Section 3.7 (above), the target analytical sensitivity for outdoor ABS air samples is 0.001 s/cc. In the event of sample loading or other issues where an analytical sensitivity of 0.001 s/cc can not be achieved, the laboratory may report a sample result with a higher (poorer) sensitivity only after consultation with EPA project personnel and preparation of a temporary modification form.

5.3 Holding Times

No preservation requirements or holding times are established for air or soil samples collected for asbestos analysis.

5.4 Laboratory Custody Procedures and Documentation

Laboratory custody procedures and documentation will be completed as required by the specifications detailed in Section 4.5 of the SWQAPP (CDM 2007a).

5.5 Documentation and Records

Laboratory documentation and records will be completed as required by the specifications detailed in Section 4.7 of the SWQAPP (CDM 2007a).

5.6 Data Management

Sample results data will be delivered to the Volpe Center and CDM's Cambridge office both in hard copy and as an electronic data deliverable (EDD) in the most recent project-specific format. Electronic copies of all project deliverables, including graphics, will be filed by project number. Electronic files will be routinely backed up and archived according to individual laboratory processes.

All results, field data sheet information, and survey forms will be maintained in the Libby project database managed by the Volpe Center under the oversight of the Volpe Center database management team.

6.0 ASSESSMENT AND OVERSIGHT

Assessments and oversight reports to management are necessary to ensure that procedures are followed as required and that deviations from procedures are documented. These reports also serve to keep management current on field activities. Assessment, oversight reports, and response actions are discussed below.

6.1 Assessments

Performance assessments are quantitative checks on the quality of a measurement system and are appropriate to analytical work. Performance assessments for the laboratories may be accomplished by submitting reference material as blind reference (or performance evaluation) samples. These assessment samples have known concentrations of LA that are submitted to the laboratories without informing the laboratories that they are performance evaluation samples. Laboratory audits may be conducted upon request from the EPA Team Leader (TL) or Volpe Center Project Manager (PM).

System assessments are qualitative reviews of different aspects of project work to check on the use of appropriate QC measures and the functioning of the QA system. Project assessments will be performed under the direction of the QA managers, who report directly to the CDM president. Quality Procedure 6.2, as defined in the CDM QA Manual (CDM 2007b), defines CDM 's corporate assessments, procedures, and requirements. Due to the amount of sampling and the duration of the Libby project, both a field audit and an office audit are scheduled for the Site annually.

6.2 Response Actions

Response actions will be implemented on a case-by-case basis to correct quality problems. Minor response actions taken in the field to immediately correct a quality problem will be documented in the applicable field logbook and a verbal report will be provided to the CDM PM. For verbal reports, the CDM PM will complete a communication log to document the response actions were relayed to him/her. Major response actions taken in the field will be approved by the CDM PM, the EPA TL, and Volpe PM prior to implementation of the change. Major response actions are those that may affect the quality or objective of the investigation. Quality problems that cannot be corrected quickly through routine procedures may require implementation of a corrective action request (CAR) form.

All formal response actions will be submitted to either CDM 's QA manager and/or project QA coordinator for review and issuance. CDM 's PM or local QA coordinator will notify the QA manager when quality problems arise that may require a formal response action. CAR forms will be completed according to Quality Procedure 8.1 of the CDM QA Manual (CDM 2007b).

In addition, when modifications to this specific SAP are required, either for field or laboratory activities, a Libby Asbestos Project Record of Modification Form (Appendix D) must be completed.

6.3 Reports to Management

QA reports will be provided to management whenever quality problems are encountered. Field staff will note any quality problems on field data sheets, or in field logbooks. CDM's PM will inform the project QA coordinator upon encountering quality issues that cannot be immediately corrected. Weekly reports and change request forms are not required for this work assignment. Monthly QA reports will be submitted to CDM 's QA manager by the project QA coordinator.

Topics to be summarized regularly may include but not be limited to:

- Document technical and QA reviews that have been conducted
- Activities and general program status
- Project meetings
- Corrective action activities
- Any unresolved problem
- Any significant QA/QC problems not included above

7.0 DATA VALIDATION AND USABILITY

Laboratory results will be reviewed for compliance with project objectives. Data validation and evaluation are discussed in Sections 7.1 and 7.2, respectively.

7.1 Data Review, Validation, and Verification Requirements

Data review, validation, and verification will be performed for important investigative samples as described in the SWQAPP (CDM 2007a). Data validation, review, and verifications must be performed on sample results before distribution to the public for review. Requirements for the frequency of data review are initially set at 10%. This initial rate may be revised as initial samples are analyzed and results evaluated.

Data validation consists of examining the sample data package(s) against pre-determined standardized requirements. The validator may examine, as appropriate, the reported results, QC summaries, case narratives, COC information, raw data, initial and continuing instrument calibration, and other reported information to determine the accuracy and completeness of the data package. During this process, the validator will verify that the analytical methodologies were followed and QC requirements were met. The validator may recalculate selected analytical results to verify the accuracy of the reported information. Analytical results will then be qualified as necessary.

Data verification includes checking that results have been transferred correctly from laboratory data printouts to the laboratory report and to the EDD. Data verification for this project is primarily performed as a function of built-in quality control checks in the Libby project database when data is uploaded. However, the sample coordinator will notify the laboratories and the project database manager (Mr. Mark Raney, Volpe Center) of any discrepancies found during data usage.

7.2 Reconciliation with Data Quality Objectives

Once data has been generated, CDM evaluates data to determine if DQOs were achieved. This achievement will be discussed in the measurement report, including the data and any deviations to this SAP. Sample data will be maintained in the project database (Libby2). Laboratory QC sample data will be stored in hard copy (in the project files) and in Libby2.

8.0 PROJECT SCHEDULE

It is anticipated that initial outdoor assessments to determine locations for outdoor ABS sample collection will begin in May 2007. The first event of outdoor ABS sampling is currently planned to be conducted from July 2007 to August 2007. It is anticipated that results from this round of sampling will be available for tabulation and release for public review in October 2007.

9.0 REFERENCES

Amandus HE, Wheeler R. 1987. The Morbidity and Mortality of Vermiculite Miners and Millers Exposed to Tremolite-Actinolite: Part II. Mortality. Am. J. Ind. Med. 11:15-26.

CDM. 2003a. Libby Asbestos Project, Analytical Guidance Documents, Volume 1, Section 3. August. International Organization for Standardization (ISO), Ambient air – Determination of asbestos fibers – Direct-transfer transmission electron microscopy method, ISO 10312:1995(E).

CDM. 2003b. Libby Asbestos Project, Modification to Laboratory Activities with ongoing updates. June.

CDM. 2007a. Site-Wide Quality Assurance Project Plan. Final date pending TAU review.

CDM. 2007b. CDM Federal Programs (CDM) Quality Assurance Manual, Revision 11. March

EPA. 1992. Supplemental Guidance to RAGS: Calculating the Concentration Term, 9285.7-081.

EPA. 2001. EPA Requirements for Quality Assurance Project Plans. EPA QA/R-5. U.S. Environmental Protection Agency, Office of Environmental Information. EPA/240/B-01/003. March 2001.

EPA. 2003. Libby Asbestos Site, Residential/Commercial Cleanup Action Level And Clearance Criteria Technical Memorandum. Draft Final. U.S. Environmental Protection Agency Region 8. December 15, 2003.

EPA. 2005. Supplemental Remedial Investigation Quality Assurance Project Plan For Libby, Montana. Final. Report prepared by USEPA Region 8 with technical assistance from Syracuse Research Corporation, Denver, CO. June 24, 2005.

EPA. 2006. Guidance on Systematic Planning Using the Data Quality Objectives Process – EPA QA/G4. U.S. Environmental Protection Agency, Office of Environmental Information. EPA/240/B-06/001. February 2006.

EPA. 2007. Sampling and Analysis Plan for Indoor Air, OU4, Libby, Montana, Superfund Site. April 1, 2007.

Haas CN, Rose JB, Gerba CP. 1999. Quantitative Microbial Risk Assessment. John Wiley and Sons, New York.

IRIS. 2007. Integrated Risk Information System. On-line database of toxicity data maintained by the U.S Environmental Protection Agency. http://www.epa.gov/iriswebp/iris/index.html

McDonald JC, McDonald AD, Armstrong B, Sebastien P. 1986. Cohort study of mortality of vermiculite miners exposed to tremolite. Brit. J. Ind. Med. 43:436-444.

McDonald JC, Harris J, Armstrong B. 2004. Mortality in a cohort of vermiculite miners exposed to fibrous Amphibole in Libby, Montana. Occup. Environ. Med. 61:363-366.

Peipins LA, Lewin M, Campolucci S, Lybarger JA, Miller A, Middleton D, et al. 2003. Radiographic abnormalities and exposure to asbestos-contaminated vermiculite in the community of Libby, Montana, USA. Environ. Health Perspect. 111:1753-1759.

APPENDIX A STANDARD OPERATING PROCEDURES

SOP No.: 1-2

OP Title: Sample Custody

roject: Libby Asbestos Remedial Investigation (RI)

Project No.: 3282-137

lient: U.S. Environmental Protection Agency

roject Manager:

Date: 5/2/63

Technical Reviewer:

Date: 5/10/3

Date: 5/19/03

Date: 5/19/03

NOTE: Each media (soil/dust) must be submitted on separate COC forms.

he sample coordinator assistant will use the FSDS to complete an electronic chain of custody (eCOC). The sample coordinator will check the data entered to create the eCOC against the FSDSs. Three paper copies of the eCOC will then be enerated. One copy will be filed in the CDM Libby office and the other two will be sent with the samples. The sample coordinator will then check the eCOC versus the sample containers and sample shipment. The sample coordinator will e responsible for shipment of samples. If any errors are found on an eCOC after shipment, the paper copy of the COC will be corrected by the sample coordinator with a single strikeout initial and date. The corrected copy will be faxed to Volpe and the laboratory. The fax to Volpe will be used to update the Libby project database.

Reason for and duration of modification: Sample custody procedures for the Libby asbestos project vary slightly from SOP 1-2. These modifications are ecessary for the entire duration of the project.

Via: Hand delivery or shipped. Hand delivery refers to samples delivered by hand to the onsite laboratory; shipped refers to samples sent to the laboratory by delivery service (i.e., Federal Express). To be completed by the sample coordinator.

Project: All samples collected in accordance with this sampling and analysis plan (SAP) are part of the CSS. Circle CSS. To be completed by the field team.

Sample Placed in Cooler/Bag: Refers to visual confirmation of the sample in the shipping container. To be completed by the sample coordinator.

Index ID: Unique index identification number used to identify sample, in the form CSS-####. To be completed by the field team.

Sample Date: The date each sample was collected, in the form MM/DD/YY. To be completed by the field team.

Sample Time: The time each sample was collected, in military time. To be completed by the field team.

Sample Matrix: The matrix of each sample collected, specific to the CSS; S = soil and W = water. To be completed by the field team.

Sample Type: Sample type of each sample collected; G = grab, C = composite. To be completed by the field team.

Volume: Specific to air and dust samples. Does not pertain to the CSS. "NA" should be placed in this field. To be completed by the field team.

Analysis Request: Analysis of each sample collected. All soil samples will be analyzed by IR. IR will be written in the analysis request portion of the COC form by the field team. The sample coordinator and/or laboratory coordinator may request SEM analysis based on Table 5-2 of the SAP. The sample coordinator and/or laboratory coordinator will designate IR for the appropriate samples.

Comments: Any pertinent information regarding the sample (i.e., vermiculite visible) will be entered by either the field team or the sample coordinator.

Sample Received by Lab: To be checked by the sample custodian at the laboratory upon receipt of the samples to confirm presence of each sample on the COC record.

btal Number of Samples: Total number of samples on the COC form. To be completed by the field team.

Idditional Comments: Any additional comments that relate to samples on the COC form (i.e., turn around times). To be completed by the field team or sample ordinator.

Relinquished by: (1) Signed by field team member that relinquishes samples to ample coordinator and company of person relinquishing samples to sample coordinator (i.e., CDM). Date of relinquish shall be in the form MM/DD/YY and time shall be in military time. (2) Additional relinquished by lines to be impleted following standard sample custody procedures.

Received by: (1) Signed by sample coordinator that receives samples from the ampling team and company of person accepting samples from the field teams (i.e., CDM). Date and time of acceptance should be the same as date and time of elinquish. (2) Additional received by lines to be completed following standard ample custody procedures.

ample Condition upon Receipt: Will reflect the condition of samples at the slinquish time (i.e., accept ok or not acceptable with an explanation). To be completed by the person receiving samples.

Lage ___ of ___: Sequential page number of the entire COC set sent to the laboratory. To be completed by the sample coordinator.

SOP 1-2

Revision: 4

Date: March 1, 2004

Page 1 of 7

Prepared: David O. Johnson

Technical Review: Shelley Thibeault

QA Review: Laura Splichal

Approved: _

enature/Date

Issued:

Signature/Date

1.0 Objective

Due to the evidentiary nature of samples collected during environmental investigations, possession must be traceable from the time the samples are collected until their derived data are introduced as evidence in legal proceedings. To maintain and document sample possession, sample custody procedures are followed. All paperwork associated with the sample custody procedures will be retained in CDM Federal Programs Corporation (CDM) files unless the client requests that it be transferred to them for use in legal proceedings or at the completion of the contract.

Note: Sample custody documentation requirements vary with the specific EPA region or client. This SOP is intended to present basic sample custody requirements, along with common options. Specific sample custody requirements should be presented in the project-specific quality assurance (QA) project plan or project-specific modification or clarification form (see Section U-1).

2.0 Background

2.1 Definitions

Sample – A sample is material to be analyzed that is contained in single or multiple containers representing a unique sample identification number.

Sample Custody - A sample is under custody if:

- 1. It is in your possession
- 2. It is in your view, after being in your possession
- 3. It was in your possession and you locked it up
- 4. It is in a designated secure area

Chain-of-Custody Record - A chain-of-custody record is a form used to document the transfer of custody of samples from one individual to another.

Custody Seal - A custody seal is a tape-like seal that is part of the chain-of-custody process and is used to detect tampering with samples after they have been packed for shipping.

Sample Label – A sample label is an adhesive label placed on sample containers to designate a sample identification number and other sampling information.

Sample Tag - A sample tag is attached with string to a sample container to designate a sample identification number and other sampling information. Tags may be used when it is difficult to physically place adhesive labels on the container (e.g., in the case of small air sampling tubes).

SOP 1-2 Revision: 4

Date: March 1, 2004

Page 2 of 7

3.0 Responsibilities

Sampler - The sampler is personally responsible for the care and custody of the samples collected until they are properly transferred or dispatched.

Field Team Leader – The field team leader (FTL) is responsible for ensuring that strict chain-of-custody procedures are maintained during all sampling events. The FTL is also responsible for coordinating with the subcontractor laboratory to ensure that adequate information is recorded on custody records. The FTL determines whether proper custody procedures were followed during the fieldwork and decides if additional samples are required.

Field Sample Custodian – The field sample custodian, when designated by the FTL, is responsible for accepting custody of samples from the sampler(s) and properly packing and shipping the samples to the laboratory assigned to do the analyses. A field sample custodian is typically designated only for large and complex field efforts.

4.0 Required Supplies

- Chain-of-custody records (applicable client or CDM forms)
- Sample labels or tags

- Custody seals
- Clear tape

5.0 Procedures

5.1 Chain-of-Custody Record

This procedure establishes a method for maintaining custody of samples through use of a chain-of-custody record. This procedure will be followed for all samples collected or split samples accepted.

Field Custody

- 1. Collect only the number of samples needed to represent the media being sampled. To the extent possible, determine the quantity and types of samples and sample locations prior to the actual fieldwork. As few people as possible should handle samples.
- 2. Complete sample labels or tags for each sample using waterproof ink.
- 3. Maintain personal custody of the samples (in your possession) at all times until custody is transferred for sample shipment or directly to the analytical laboratory.

Transfer of Custody and Shipment

- 1. Complete a chain-of-custody record for all samples (see Figure 1 for an example of a chain-of-custody record. Similar forms may be used when requested by the client). When transferring the possession of samples, the individuals relinquishing and receiving will sign, date, and note the time on the record. This record documents sample custody transfer from the sampler, often through another person, to the sample custodian in the appropriate laboratory.
 - The date/time will be the same for both signatures when custody is transferred directly to another person. When samples are shipped via common carrier (e.g., Federal Express), the

SOP 1-2 Revision: 4

Date: March 1, 2004

Page 3 of 7

date/time will not be the same for both signatures. Common carriers are not required to sign the chain-of-custody record.

- In all cases, it must be readily apparent that the person who received custody is the same person who relinquished custody to the next custodian.
- If samples are left unattended or a person refuses to sign, this must be documented and explained on the chain-of-custody record.

Note: If a field sample custodian has been designated, he/she may initiate the chain-of-custody record, sign, and date as the relinquisher. The individual sampler(s) must sign in the appropriate block, but does (do) not need to sign and date as a relinquisher (refer to Figure 1).

- Package samples properly for shipment and dispatch to the appropriate laboratory for analysis.
 Each shipment must be accompanied by a separate chain-of-custody record. If a shipment consists of multiple coolers, samples in the coolers may be recorded on a single chain-of-custody record.
- 3. The original record will accompany the shipment, and the copies will be retained by the FTL and, if applicable, distributed to the appropriate sample coordinators. Freight bills will also be retained by the FTL as part of the permanent documentation. The shipping number from the freight bill shall be recorded on the applicable chain-of-custody record.

Procedure for Completing CDM Example Chain-of-Custody Record

The following procedure is to be used to fill out the CDM chain-of-custody record. The record provided herein (Figure 1) is an example chain-of-custody record. If another type of custody record (i.e., provided by the EPA contract laboratory program or a subcontract laboratory) is used to track the custody of samples, the custody record should be filled out in its entirety.

- 1. Record project number.
- 2. Record FTL for the project (if a field sample custodian has been designated, also record this name in the "Remarks" box).
- 3. Record the name and address of the laboratory to which samples are being shipped.
- 4. Enter the project name/location or code number.
- 5. Record overnight courier's airbill number.
- 6. Record sample location number.
- 7. Record sample number.
- 8. Note preservatives added to the sample.
- 9. Note media type (matrix) of the sample.
- 10. Note sample type (grab or composite).
- 11. Enter date of sample collection.
- 12. Enter time of sample collection in military time.

SOP 1-2 Revision: 4

Date: March 1, 2004

Page 4 of 7

Figure 1 Example CDM Chain-of-Custody Record

CDM

125 Maiden Lane, 5th Floor New York, NY 10038 (212) 785-9123 Fax: (212) 785-6114

CHAIN OF CUSTODY RECORD

PROJECT ID. FIELD TEAM LEADER					LABORATORY								DATE	PED		
PROJECT NAME/LOX	CATION					7	ID ADDRES B CONTRAI							AIRBIL	L NC),
MEDIA TYPE 1. Surface Water 2. Groundwater 3. Leachate 4. Field QC 5. Soil/Sediment 6. OI 7. Waste 8. Other	1. HCl, pH <2 G < 2. HNO3. pH <2 C : 3. NaON, pH >12 4. H2SO4. pH <2 5. Zinc Acetato, pH >9 6. Ice Only 7. Not Preserved					Gra	Posite	ANALYSES (List no. of conteners submitted)							•	
SAMPLE LOCATION NO.	LABORJ SAM NUM	PLE .	PRESER- VATIVES ADDED	MEDIA TYPE			TIME SAMPLED	1 -								EMARKS H NS/MSD
1.																
2.														\perp		
3.									 			↓				
4,								L								
5 .							_	<u> </u>	Ш			ـــــ	<u> </u>			
4.								<u> </u>				_	<u> </u>			
7.]								
8.																
9.							Ī									
10.												1	1		٠,	
SAMPLER SIGNATURES:										*****		`				
RELINQUISHED BY:	DATETIME	DATE/THE RECEIV					REUNOUSHED BY		DATE/TIME		(\$04)				DATE/TIME	
(MGH)		CHORN CH				ISBN DATE/TIME REUNOLISHE PRINT				DATE/TIME						l r
RELINCUISHED BY:	DATE/TIME				DATECT											
UNIONÓ		queon:			(3/04)						134044					
COMMENTS:					-						-					

DISTRECTION: White and years copies accompany sample shipment to laboratory; yellow copy retained by laboratory. Pink copy retained by samplers.

1/98

Note: If requested by the client, different chain-of-custody records may be used. Copies of the template for this record may be obtained from the Chantilly Graphics Department.

SOP 1-2 Revision: 4

Date: March 1, 2004

Page 5 of 7

- 13. When required by the client, enter the names or initials of the samplers next to the sample location number of the sample they collected.
- 14. List parameters for analysis and the number of containers submitted for each analysis.
- 15. Enter matrix spike/matrix spike duplicate (MS/MSD) if sample is for **laboratory** quality control or other remarks (e.g., sample depth).
- 16. Sign the chain-of-custody record(s) in the space provided. All samplers must sign each record.
- 17. If sample tags are used, record the sample tag number in the "Remarks" column.
- 18. The originator checks information entered in Items 1 through 16 and then signs the top left "Relinquished by" box, prints his/her name, and enters the current date and time (military).
- 19. Send the top two copies (usually white and yellow) with the samples to the laboratory; retain the third copy (usually pink) for the project files. Retain additional copies for the project file or distribute as required to the appropriate sample coordinators.
- 20. The laboratory sample custodian receiving the sample shipment checks the sample label information against the chain-of-custody record. Sample condition is checked and anything unusual is noted under "Remarks" on the chain-of-custody record. The laboratory custodian receiving custody signs in the adjacent "Received by" box and keeps the copy. The white copy is returned to CDM.

5.2 Sample Labels and Tags

Unless the client directs otherwise, sample labels or tags will be used for all samples collected or accepted for CDM projects.


- 1. Complete one label or tag with the information required by the client for each sample container collected. A typical label or tag would be completed as follows (see Figure 2 for example of sample tag; labels are completed with the equivalent information):
 - Record the project code (i.e., project or task number).
 - Enter the station number (sample number) if applicable.
 - Record the date to indicate the month, day, and year of sample collection.
 - Enter the time (military) of sample collection.
 - Place a check to indicate composite or grab sample.
 - Record the station (sample) location.
 - Sign in the space provided.
 - Place a check next to "yes" or "no" to indicate if a preservative was added.
 - Place a check under "Analyses" next to the parameters for which the sample is to be analyzed. If the desired analysis is not listed, write it in the empty slot. Note: Do not write in the box for "laboratory sample number."
 - Place or write additional relevant information under "Remarks."
- 2. Place adhesive labels directly on the sample containers. Place clear tape over the label to protect from moisture.
- 3. Securely attach sample tags to the sample bottle. On 2.27 liter (80 oz.) amber bottles, the tag string may be looped through the ring style handle and tied. On all other containers, it is

SOP 1-2 Revision: 4

Date: March 1, 2004

Page 6 of 7

Figure 2
Example Sample Tag



Note: Equivalent sample labels or tags may be used.

SOP 1-2 Revision: 4

Date: March 1, 2004

Page 7 of 7

recommended that the string be looped around the neck of the bottle, then twisted and relooped around the neck until the slack in the string is removed.

4. Double-check that the information recorded on the sample tag is consistent with the information recorded on the chain-of-custody record.

5.3 Custody Seals

Two custody seals must be placed on opposite corners of all shipping containers (e.g., cooler) prior to shipment. The seals should be signed and dated by the shipper.

Custody seals may also be placed on individual sample bottles. Check with the client or refer to EPA regional guidelines for direction.

5.4 Sample Shipping

The CDM standard operating procedure listed below defines the requirements for packaging and shipping environmental samples.

CDM Federal SOP 2-1, Packaging and Shipping Environmental Samples

6.0 Restrictions/Limitations

Check with the EPA region or client for specific guidelines. If no specific guidelines are identified, this procedure should be followed.

For EPA Contract Laboratory Program (CLP) sampling events, combined chain-of-custody/traffic report forms or other EPA-specific records may be used. Refer to regional guidelines for completing these forms.

The EPA FORMS II LiteTM software may be used to customize sample labels and custody records when directed by the client or the CDM project manager.

7.0 References

U.S. Environmental Protection Agency, EPA Guidance for Quality Assurance Project Plans, EPA QA/G-5, EPA/600/R-98/018, February 1998, Section B3.

U.S. Environmental Protection Agency, National Enforcement Investigations Center, Multi-Media Investigation Manual, EPA-330/9-89-003-R, Revised March 1992, p.85.

U.S. Environmental Protection Agency, Contract Laboratory Program (CLP), Guidance for Field Samplers, EPA-540-R-00-003, Draft Final, June 2001, Section 3.2.

U.S. Environmental Protection Agency, FORMS II Lite™ User's Guide, March 2001.

U.S. Environmental Protection Agency, Region IV, Environmental Investigations Standard Operating Procedures and Quality Assurance Manual, May 1996, Section 3.3.

U.S. Army Corps of Engineers, Requirements for the Preparation of Sampling and Analysis Plan, EM 200-1-3, February 2001, Appendix F.

SOP No.: 2-1

P Title: Packaging and Shipping of Environmental Samples

roject: Libby Asbestos Remedial Investigation (RI)

Project No.: 3282-137

lient: U.S. Environmental Protection Agency

roject Manager:

Date: 5/7/03

echnical Reviewer Sne Sne

Date: 57703

A Reviewer:

Date: 5/12/03

PA Approval:

Date: 5/19/03

Reason for and duration of modification: Procedures for shipping environmental imples for the Libby asbestos project vary slightly from CDM Technical SOP 2-1. These modifications are necessary for the entire duration of the project.

amples collected during this investigation will be packaged and shipped in accordance with CDM Technical SOP 2-1, with the following modifications:

ection 1.4, Required Equipment - Vermiculite (or other absorbent material), bubble wrap, or ice will not be used for packaging or shipping samples.

ection 1.5, Procedures - No vermiculite or other absorbent material will be used to pack are samples. No ice will be used.

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 1 of 21

Prepared: Krista Lippoldt

Technical Review: Chuck Myers

QA Review: Douglas J. Updike

Approved:

ignature/Date

Issued:

Signature/Date

1.0 Packaging and Shipping of All Samples

This standard operating procedure (SOP) applies to the packaging and shipping of all environmental samples. If the sample is preserved or radioactive, the following sections may also be applicable.

Section 2.0 - Packaging and Shipping Samples Preserved with Methanol

Section 3.0 - Packaging and Shipping Samples Preserved with Sodium Hydroxide

Section 4.0 - Packaging and Shipping Samples Preserved with Hydrochloric Acid

Section 5.0 - Packaging and Shipping Samples Preserved with Nitric Acid

Section 6.0 - Packaging and Shipping Samples Preserved with Sulfuric Acid

Section 7.0 - Packaging and Shipping Limited-Quantity Radioactive Samples

1.1 Objective

The objective of this SOP is to outline the requirements for the packaging and shipment of environmental samples. Additionally, Sections 2.0 through 7.0 outline requirements for the packaging and shipping of regulated environmental samples under the Department of Transportation (DOT) Hazardous Materials Regulations, the International Air Transportation Association (IATA), and International Civil Aviation Organization (ICAO) Dangerous Goods Regulations for shipment by air and applies only to domestic shipments. This SOP does not cover the requirements for packaging and shipment of equipment (including data loggers and self-contained breathing apparatus [SCBAs] or bulk chemicals that are regulated under the DOT, IATA, and ICAO.

1.2 Background

1.2.1 Definitions

Environmental Sample - An aliquot of air, water, plant material, sediment, or soil that represents the contaminant levels on a site. Samples of potential contaminant sources, like tanks, lagoons, or non-aqueous phase liquids are normally not "environmental" for this purpose. This procedure applies only to environmental samples that contain less than reportable quantities for any foreseeable hazardous constituents according to DOT regulations promulgated in 49 CFR - Part 172.101 Appendix A.

Custody Seal – A custody seal is a narrow adhesive-backed seal that is applied to individual sample containers and/or the container (i.e., cooler) before offsite shipment. Custody seals are used to demonstrate that sample integrity has not been compromised during transportation from the field to the analytical laboratory.

Inside Container – The container, normally made of glass or plastic, that actually contacts the shipped material. Its purpose is to keep the sample from mixing with the ambient environment.

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 2 of 21

Outside Container – The container, normally made of metal or plastic, that the transporter contacts. Its purpose is to protect the inside container.

Secondary Containment – The outside container provides secondary containment if the inside container breaks (i.e., plastic overpackaging if liquid sample is collected in glass).

Excepted Quantity – Excepted quantities are limits to the mass or volume of a hazardous material in the inside and outside containers below which DOT, IATA, ICAO regulations do not apply. The excepted quantity limits are very low. Most regulated shipments will be made under limited quantity.

Limited Quantity – Limited quantity is the maximum amount of a hazardous material below which there are specific labeling or packaging exceptions.

Performance Testing - Performance testing is the required testing of outer packaging. These tests include drop and stacking tests.

Qualified Shipper – A qualified shipper is a person who has been adequately trained to perform the functions of shipping hazardous materials.

1.2.2 Discussion

Proper packaging and shipping is necessary to ensure the protection of the integrity of environmental samples shipped for analysis. These shipments are potentially subject to regulations published by DOT, IATA, or ICAO. Failure to abide by these rules places both CDM and the individual employee at risk of serious fines. The analytical holding times for the samples must not be exceeded. The samples should be packed in time to be shipped for overnight delivery. Make arrangements with the laboratory before sending samples for weekend delivery.

1.2.3 Associated Procedure

CDM Federal SOP 1-2, Sample Custody

1.3 Required Equipment

- Coolers with return address of the appropriate CDM office
- Heavy-duty plastic garbage bags
- Plastic zip-type bags, small and large
- Clear tape
- Nylon reinforced strapping tape
- Duct tape
- Vermiculite (or an equivalent nonflammable material that is inert and absorbent)*
- Bubble wrap (optional)
- Ice
- Custody seals
- Completed chain-of-custody record or contract laboratory program (CLP) custody records, if applicable
- Completed bill of lading
- "This End Up" and directional arrow labels

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 3 of 21

 Check for any client-specific or laboratory requirements related to the use of absorbent packaging materials.

1.4 Packaging Environmental Samples

The following steps must be followed when packing sample bottles and jars for shipment:

- Verify the samples undergoing shipment meet the definition of "environmental sample" and are not a hazardous material as defined by DOT. Professional judgment and/or consultation with qualified persons such as the appropriate health and safety coordinator or the health and safety manager should be observed.
- 2. Select a sturdy cooler in good repair. Tape any interior opening in the cooler (drain plug) from the inside to ensure control of interior contents. Also, tape the drain plug from the outside of the cooler. Line the cooler with a large heavy-duty plastic garbage bag.
- 3. Be sure the caps on all bottles are tight (will not leak); check to see that labels and chain-of-custody records are completed properly (SOP 1-2, Sample Custody).
- 4. Place all bottles in separate and appropriately sized plastic zip-top bags and close the bags. Up to three VOA vials may be packed in one bag. Binding the vials together with a rubber band on the outside of the bag, or separating them so that they do not contact each other, will reduce the risk of breakage. Bottles may be wrapped in bubble wrap. Optionally, place three to six VOA vials in a quart metal can and then fill the can with vermiculite or equivalent. Note: Trip blanks must be included in coolers containing VOA samples.
- 5. Place 2 to 4 inches of vermiculite (or equivalent) into a cooler that has been lined with a garbage bag, and then place the bottles and cans in the bag with sufficient space to allow for the addition of packing material between the bottles and cans. It is preferable to place glass sample bottles and jars into the cooler vertically. Glass containers are less likely to break when packed vertically rather than horizontally.
- 6. While placing sample containers into the cooler, conduct an inventory of the contents of the shipping cooler against the chain-of-custody record. The chain-of-custody with the cooler should reflect only those samples within the cooler.
- 7. Put ice in large plastic zip-top bags (double bagging the zip-tops is preferred) and properly seal. Place the ice bags on top of and/or between the samples. Several bags of ice are required (dependant on outdoor temperature, staging time, etc.) to maintain the cooler temperature at approximately 4° Celsius (C) if the analytical method requires cooling. Fill all remaining space between the bottles or cans with packing material. Securely fasten the top of the large garbage bag with fiber or duct tape.
- 8. Place the completed chain-of-custody record or the CLP traffic report form (if applicable) for the laboratory into a plastic zip-top bag, seal the bag, tape the bag to the inner side of the cooler lid and close the cooler.



SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 4 of 21

- 9. The cooler lid shall be secured with nylon reinforced strapping tape by wrapping each end of the cooler a minimum of two times. Attach a completed chain-of-custody seal across the opening of the cooler on opposite sides. The custody seals should be affixed to the cooler with half of the seal on the strapping tape so that the cooler cannot be opened without breaking the seal. Complete two more wraps around with fiber tape and place clear tape over the custody seals.
- 10. The shipping container lid must be marked "THIS END UP" and arrow labels that indicate the proper upward position of the container should be affixed to the cooler. A label containing the name and address of the shipper (CDM) shall be placed on the outside of the container. Labels used in the shipment of hazardous materials (such as Cargo Only Air Craft, Flammable Solids, etc.) are not permitted on the outside of containers used to transport environmental samples and shall not be used. The name and address of the laboratory shall be placed on the container, or when shipping by common courier, the bill of lading shall be completed and attached to the lid of the shipping container.

2.0 Packaging and Shipping Samples Preserved with Methanol 2.1 Containers

- The maximum volume of methanol in a sample container is limited to 30 ml.
- The sample container must not be full of methanol.

2.2 Responsibility

It is the responsibility of the qualified shipper to:

- Ensure that the samples undergoing shipment contain no other contaminant that meets the definition of "hazardous material" as defined by DOT
- Determine the amount of preservative in each sample so that accurate determination of quantities can be made

2.3 Additional Required Equipment

The following equipment is needed in addition to the required equipment listed in Section 1.3:

- Inner packing may consist of glass or plastic jars
- Outer packaging (for limited quantities) insulated cooler that has passed the ICAO drop test
- Survey documentation (if shipping from Department of Energy [DOE] or radiological sites)
- Class 3 flammable liquid labels
- Orientation labels
- Consignor/consignee labels

2.4 Packaging Samples Preserved with Methanol

The following steps are to be followed when packaging limited-quantity sample shipments.

- Tape any interior opening in the cooler (drain plug) from the inside to ensure control of interior contents. Also, tape the drain plug from the outside of the cooler.
- All sample containers will be properly labeled and the label protected with waterproof tape prior to sampling.

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 5 of 21

- At a minimum the label must contain:
 - Project name
 - Project number
 - Date and time of sample collection
 - Sample location
 - Sample identification number
 - Collector's initials
 - Preservative (note amount of preservative used in miscellaneous section of the chain-of-custody form)
- Wrap each container (40-ml VOA vials) in bubble wrap (secure with waterproof tape) to prevent breakage.
- Place the bubble-wrapped container into a 2.7-mil zip-type bag, removing trapped air.
- Place wrapped containers inside a polyethylene bottle filled with vermiculite; seal the bottle.
 (Maximum of 4 VOA vials will fit inside a 500-ml wide-mouth polyethylene bottle.)
- Total volume of methanol per shipping container must not exceed 500 ml.
- Place sufficient amount of vermiculite in the bottom of the cooler to absorb any leakage that may occur.
- Place a garbage bag in the cooler.
- Pack the samples appropriately inside the garbage bag (bottles placed upright) to prevent movement during shipment.
- Place a sufficient amount of double-bagged ice around the samples to maintain the required temperature during shipment.
- Seal the garbage bag by tieing or taping.
- The maximum weight of the cooler shall not exceed 30 kg (66 lbs) for any limited-quantity shipment of dangerous goods.
- Secure the chain-of-custody form (placed inside a zip-type bag) to the interior of the cooler lid.
- If the shipment is from a DOE or other facility, place the results of the radiation screen and cooler/sample survey with the chain-of-custody.
- Wrap strapping tape or duct tape around both ends of the cooler and around the cooler lid.
- Affix custody seals to opposite sides of the cooler lid. Cover the custody seals with clear waterproof tape.
- Mark the outside of the cooler with the proper shipping name of the contents, corresponding UN number, and LTD. QTY. (as shown below).

Methanol Mixture UN1230 LTD. QTY.

- Place a label on the front of the cooler with the company name, contact name, phone number, full street address, and state with zip code for both shipper and recipient.
- Affix a Flammable Liquid label to the outside of the cooler.
- Affix package orientation labels on two opposite sides of the cooler.
- Secure the marking and labels to the surface of the cooler with clear waterproof tape to prevent accidental removal during shipment.
- An example of cooler labeling/marking locations is shown in Figure 1.

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 6 of 21

Note: No marking or labeling can be obscured by strapping or duct tape.

Note: The inner packaging of dangerous goods must be placed into the designated cooler for shipment. Other non-regulated environmental samples may be added to the cooler for shipment.

- When shipping from a DOE facility, the cooler will be surveyed by a qualified radiation control technician to ensure that radiation flux on exterior surfaces does not exceed 0.5 mrem/h on all sides. This survey will be documented and the results reviewed by the qualified shipper.
- Complete the Dangerous Goods and Hazardous Materials Inspection Checklist for Shipping Limited-Quantity (Appendix A).
- Complete a Dangerous Goods Airbill.

Figure 1 - Example of Cooler Label/Marking Locations

Strapping Tabe

To:
From:
Methanol Mixture
UN1230
LTD. QTY:

Proper Shipping Name and UN Number

Hazard Class Label

3.0 Packaging and Shipping Samples Preserved with Sodium Hydroxide 3.1 Containers

The inner packaging container (and amount of preservative) that may be used for these shipments includes:

Excepted Quantities of Sodium Hydroxide Preservatives

Preserv	ative	Desired Sai	i in Final	100	Quantity of Preservative (ml) for						
		рΗ	Conc.	40 ml	125 ml	250 ml	500 ml	1 L			
NaOH	30%	>12	0.08%		.25	0.5	1	2			

5 drops = 1 ml

3.2 Responsibility

It is the responsibility of the qualified shipper to determine the amount of preservative in each sample so that accurate determination of quantities can be made.

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 7 of 21

3.3 Additional Required Equipment

The following equipment is needed in addition to the required equipment listed in Section 1.3:

- Outer packaging (for limited quantities) insulated cooler that has passed the ICAO drop test
- Inner packings may consist of glass or plastic jars no larger than 1 pint
- Survey documentation (if shipping from DOE or radiological sites)
- Class 8 corrosive labels
- Orientation labels
- Consignor/consignee labels

3.4 Packaging Samples Preserved with Sodium Hydroxide

Samples containing NaOH as a preservative that exceed the excepted concentration of 0.08 percent (2 ml of a 30 percent NaOH solution per liter) may be shipped as a limited quantity per packing instruction Y819 of the IATA/ICAO Dangerous Goods Regulations.

The following steps are to be followed when packaging limited-quantity samples shipments.

- Tape any interior opening in the cooler (drain plug) from the inside to ensure control of interior contents. Also, tape the drain plug from the outside of the cooler.
- All sample containers will be properly labeled and the label protected with waterproof tape prior to sampling.
- At a minimum the label must contain:
 - Project name
 - Project number
 - Date and time of sample collection
 - Sample location
 - Sample identification number
 - Collector's initials
 - Preservative (note amount of preservative used in miscellaneous section of the chain-of-custody form)
- This step is optional; wrap each container in bubble wrap (secure with waterproof tape) to prevent breakage.
- Place the bubble-wrapped container into a 2.7-mil zip-type bag, removing trapped air.
- Place glass containers inside a polyethylene bottle filled with vermiculite; seal the bottle.
- The total volume of sample in each cooler must not exceed 1 liter.
- Place sufficient amount of vermiculite in the bottom of the cooler to absorb any leakage that may occur.
- Place a garbage bag in the cooler.
- Pack the samples appropriately inside the garbage bag (bottles placed upright) to prevent movement during shipment.
- Place a sufficient amount of double-bagged ice around the samples to maintain the required temperature during shipment.
- Seal the garbage bag by tieing or taping.
- The maximum weight of the cooler shall not exceed 30 kg (66 lbs) for any limited-quantity shipment of dangerous goods.



SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 8 of 21

- Secure the chain-of-custody form (placed inside a zip-type bag) to the interior of the cooler lid.
- If the shipment is from a DOE or other facility, place the results of the radiation screen and cooler/sample survey with the chain-of-custody.
- Wrap strapping tape or duct tape around both ends of the cooler and around the cooler lid.
- Affix custody seals to opposite sides of the cooler lid. Cover the custody seals with clear waterproof tape.
- Mark the outside of the cooler with the proper shipping name of the contents, corresponding UN number, and LTD. QTY. (as shown below).

Sodium Hydroxide Solution UN1824 LTD. QTY.

- Place a label on the front of the cooler with the company name, contact name, phone number, full street address, and state with zip code for both shipper and recipient.
- Affix a Corrosive label to the outside of the cooler.
- Affix package orientation labels on two opposite sides of the cooler.
- Secure the marking and labels to the surface of the cooler with clear waterproof tape to prevent accidental removal during shipment.
- An example of cooler labeling/marking locations is shown in Figure 1.

Note: Samples meeting the exception concentration of 0.08 percent NaOH by weight may be shipped as non-regulated or non-hazardous following the procedure in Section 1.4.

Note: No marking or labeling can be obscured by strapping or duct tape.

Note: The inner packaging of dangerous goods must be placed into the designated cooler for shipment. Other non-regulated environmental samples may be added to the cooler for shipment.

- When shipping from a DOE facility, the cooler will be surveyed by a qualified radiation control technician to ensure that radiation flux on exterior surfaces does not exceed 0.5 mrem/h on all sides. This survey will be documented and the results reviewed by the qualified shipper.
- Complete the Dangerous Goods and Hazardous Materials Inspection Checklist for Shipping Limited-Quantity (Appendix A).
- Complete a Dangerous Goods Airbill.

4.0 Packaging and Shipping Samples Preserved with Hydrochloric Acid 4.1 Containers

The inner packaging container (and amount of preservative) that may be used for these shipments includes:

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 9 of 21

Excepted Quantities of Hydrochloric Acid Preservatives

Preser	vative		d In Final mpie	Quantity of Preservative (ml) for Specified Container					
		pH	Conc.	40 ml	125 ml	250 ml			
HCI	2N	<1.96	0.04%	.2	.5	1			

5 drops = 1 ml

4.2 Responsibility

It is the responsibility of the qualified shipper to:

- Determine the samples undergoing shipment contain no other contaminant that meets the definition of hazardous material as defined by DOT
- Determine the amount of preservative in each sample so that accurate determination of quantities can be made

4.3 Additional Required Equipment

The following equipment is needed in addition to the required equipment listed in Section 1.3.

- Inner packing may consist of glass or plastic jars no larger than 1 pint.
- Outer packaging (for limited quantities) insulated cooler that has passed the ICAO drop test.
- Survey documentation (if shipping from DOE or radiological sites)
- Class 8 corrosive labels
- Orientation labels
- Consignor/consignee labels

4.4 Packaging Samples Preserved with Hydrochloric Acid

The following steps are to be followed when packaging limited-quantity sample shipments.

- Tape any interior opening in the cooler (drain plug) from the inside to ensure control of interior contents. Also, tape the drain plug from the outside of the cooler.
- All sample containers will be properly labeled and the label protected with waterproof tape prior to sampling.
- At a minimum the label must contain:
 - Project name
 - Project number
 - Date and time of sample collection
 - Sample location
 - Sample identification number
 - Collector's initials
 - Preservative (note amount of preservative used in miscellaneous section of the chain-of-custody form)
- Wrap each container (40-ml VOA vials) in bubble wrap (secure with waterproof tape) to prevent breakage.
- Place the bubble-wrapped container into a 2.7-mil zip-type bag, removing trapped air.
- Place wrapped containers inside a polyethylene bottle filled with vermiculite; seal the bottle.
 (No more than 4 VOA vials will fit inside a 500-ml wide-mouth polyethylene bottle.)

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 10 of 21

- Total volume of sample inside each cooler must not exceed 1 liter.
- Place sufficient amount of vermiculite in the bottom of the cooler to absorb any leakage that may occur.
- Place a garbage bag in the cooler.
- Pack the samples appropriately inside the garbage bag (bottles placed upright) to prevent movement during shipment.
- Place a sufficient amount of double-bagged ice around the samples to maintain the required temperature during shipment.
- Seal the garbage bag by tieing or taping.
- The maximum weight of the cooler shall not exceed 30 kg (66 lbs) for any limited-quantity shipment of dangerous goods.
- Secure the chain-of-custody form (placed inside a zip-type bag) to the interior of the cooler lid.
- If the shipment is from a DOE or other facility, place the results of the radiation screen and cooler/sample survey with the chain-of-custody.
- Wrap strapping tape or duct tape around both ends of the cooler and around the cooler lid.
- Affix custody seals to opposite sides of the cooler lid. Cover the custody seals with clear waterproof tape.
- Mark the outside of the cooler with the proper shipping name of the contents, corresponding UN number, and LTD. QTY. (as shown below).

Hydrochloric Acid Solution UN1789 LTD. QTY.

- Place a label on the front of the cooler with the company name, contact name, phone number, full street address, and state with zip code for both shipper and recipient.
- Affix a Corrosive label to the outside of the cooler.
- Affix package orientation labels on two opposite sides of the cooler.
- Secure the marking and labels to the surface of the cooler with clear waterproof tape to prevent accidental removal during shipment.
- An example of cooler labeling/marking locations is shown in Figure 1.

Note: Samples containing less than the exception concentration of 0.04 percent HCl by

weight will be shipped as non-regulated or non-hazardous following the

procedure in Section 1.4.

Note: No marking or labeling can be obscured by strapping or duct tape.

Note: The inner packaging of dangerous goods must be placed into the designated

cooler for shipment. Other non-regulated environmental samples may be added

to the cooler for shipment.

When shipping from a DOE facility, the cooler will be surveyed by a qualified radiation control technician to ensure that radiation flux on exterior surfaces does not exceed 0.5 mrem/h on all sides. This survey will be documented and the results reviewed by the qualified shipper.

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 11 of 21

- Complete the Dangerous Goods and Hazardous Materials Inspection Checklist for Shipping Limited-Quantity (Appendix A).
- Complete a Dangerous Goods Airbill.

5.0 Packaging and Shipping Samples Preserved with Nitric Acid

5.1 Containers

The inner packaging container (and amount of preservative) that may be used for these shipments includes:

Excepted Quantities of Nitric Acid Preservatives

क्षेत्रक ८० : Preservative			l In Final nple				f Preservative (mi) for cified Container		
		pН	Conc.	40 ml	125 ml	250 mi	500 ml	1 L	
HNO ₃	6N	<1.62	0.15%		2	4	5	8	

5 drops = 1 ml

5.2 Responsibility

It is the responsibility of the qualified shipper to:

- Determine the samples undergoing shipment contain no other contaminant that meets the definition of hazardous material as defined by DOT
- Determine the amount of preservative in each sample so that accurate determination of quantities can be made

5.3 Additional Required Equipment

The following equipment is needed in addition to the required equipment listed in Section 1.3.

- Inner packings may consist of glass or plastic jars no larger than 100 ml.
- Outer packaging (for limited quantities) insulated cooler that has passed the ICAO drop test.
- Survey documentation (if shipping from DOE or radiological sites)
- Class 8 corrosive labels
- Orientation labels
- Consignor/consignee labels

5.4 Packaging Samples Preserved with Nitric Acid

Samples containing HNO₃ as a preservative that exceed the excepted concentration of 0.15 percent HNO₃ will be shipped as a limited quantity per packing instruction Y807 of the IATA/ICAO Dangerous Goods Regulations.

The following steps are to be followed when packaging limited-quantity sample shipments.

- Tape any interior opening in the cooler (drain plug) from the inside to ensure control of interior contents. Also, tape the drain plug from the outside of the cooler.
- All sample containers will be properly labeled and the label protected with waterproof tape prior to sampling.
- At a minimum the label must contain:
 - Project name



SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 12 of 21

- Project number
- Date and time of sample collection
- Sample location
- Sample identification number
- Collector's initials
- Preservative (note amount of preservative used in miscellaneous section of the chain-of-custody)
- This step is optional; wrap each container in bubble wrap (secure with waterproof tape) to prevent breakage.
- Place the bubble-wrapped container into a 2.7-mil zip-type bag, removing trapped air.
- Place glass containers inside a polyethylene bottle filled with vermiculite; seal the bottle.
- Place sufficient amount of vermiculite in the bottom of the cooler to absorb any leakage that may occur.
- Place a garbage bag in the cooler.
- Pack the samples appropriately inside the garbage bag (bottles placed upright) to prevent movement during shipment.
- Place a sufficient amount of double-bagged ice around the samples to maintain the required temperature during shipment.
- Seal the garbage bag by tieing or taping.
- The maximum volume of preserved solution in the cooler must not exceed 500 ml.
- The maximum weight of the cooler shall not exceed 30 kg (66 lbs) for any limited-quantity shipment of dangerous goods.
- Secure the chain-of-custody form (placed inside a zip-type bag) to the interior of the cooler lid.
- If the shipment is from a DOE or other facility, place the results of the radiation screen and cooler/sample survey with the chain-of-custody.
- Wrap strapping tape or duct tape around both ends of the cooler and around the cooler lid.
- Affix custody seals to opposite sides of the cooler lid. Cover the custody seals with clear waterproof tape.
- Mark the outside of the cooler with the proper shipping name of the contents, corresponding UN number, and LTD. QTY. (as shown below).

Nitric Acid Solution (with less than 20 percent) UN2031 Ltd. Qty.

- Place a label on the front of the cooler with the company name, contact name, phone number, full street address, and state with zip code for both shipper and recipient.
- Affix a Corrosive label to the outside of the cooler.
- Affix package orientation labels on two opposite sides of the cooler.
- Secure the marking and labels to the surface of the cooler with clear waterproof tape to prevent accidental removal during shipment.
- An example of cooler labeling/marking locations is shown in Figure 1.

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 13 of 21

Note:

Samples meeting the exception concentration of 0.15 percent HNO₃ by weight

will be shipped as non-regulated or non-hazardous following the procedure in

Section 1.4.

Note:

No marking or labeling can be obscured by strapping or duct tape.

Note:

The inner packaging of dangerous goods must be placed into the designated cooler for shipment. Other non-regulated environmental samples may be added

to the cooler for shipment.

• When shipping from a DOE facility, the cooler will be surveyed by a qualified radiation control technician to ensure that radiation flux on exterior surfaces does not exceed 0.5 mrem/h on all sides. This survey will be documented and the results reviewed by the qualified shipper.

 Complete the Dangerous Goods and Hazardous Materials Inspection Checklist for Shipping Limited-Quantity (Appendix A).

Complete a Dangerous Goods Airbill.

6.0 Packaging and Shipping Samples Preserved with Sulfuric Acid 6.1 Containers

The inner packaging container (and amount of preservative) that may be used for these shipments includes:

Excepted Quantities of Sulfuric Acid Preservatives

Preservative			Desired in Final Sample		Quantity of Preservative (ml) for Specified Container				
		рH	Conc.	40 mi	125 ml	250 ml	500 ml	1 L	
H₂SO₄	37N	<1.15	0.35%	.1_	.25	0.5	1	2	

5 drops = 1 ml

6.2 Responsibility

It is the responsibility of the qualified shipper to:

- Determine the samples undergoing shipment contain no other contaminant that meets the definition of hazardous material as defined by DOT
- Determine the amount of preservative in each sample so that accurate determination of quantities can be made

6.3 Additional Required Equipment

The following equipment is needed in addition to the required equipment listed in Section 1.3.

- Inner packings may consist of glass or plastic jars no larger than 100 ml.
- Outer packaging (for limited quantities) insulated cooler that has passed the ICAO drop test.
- Survey documentation (if shipping from DOE or radiological sites)
- Class 8 corrosive labels
- Orientation labels
- Consignor/consignee labels

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 14 of 21

6.4 Packaging of Samples Preserved with Sulfuric Acid

Samples containing H₂SO₄ as a preservative that exceed the excepted concentration of 0.35 percent will be shipped as a limited quantity per packing instruction Y809 of the IATA/ICAO Dangerous Goods Regulations.

The following steps are to be followed when packaging limited-quantity samples shipments.

- Tape any interior opening in the cooler (drain plug) from the inside to ensure control of interior contents. Also, tape the drain plug from the outside of the cooler.
- All sample containers will be properly labeled and the label protected with waterproof tape prior to sampling.
- At a minimum the label must contain:
 - Project name
 - Project number
 - Date and time of sample collection
 - Sample location
 - Sample identification number
 - Collector's initials
 - Preservative (note amount of preservative used in miscellaneous section of the chain-of-custody form)
- Wrap each glass container in bubble wrap (secure with waterproof tape) to prevent breakage.
- Place the bubble-wrapped container into a 2.7-mil zip-type bag, removing trapped air.
- Place glass containers inside a polyethylene bottle filled with vermiculite; seal the bottle.
- Place sufficient amount of vermiculite in the bottom of the cooler to absorb any leakage that may occur.
- Place a garbage bag in the cooler.
- Pack the samples appropriately inside the garbage bag (bottles placed upright) to prevent movement during shipment.
- Place a sufficient amount of double-bagged ice around the samples to maintain the required temperature during shipment.
- Seal the garbage bag by tieing or taping.
- The maximum volume of preserved solution in the cooler must not exceed 500 ml.
- The maximum weight of the cooler shall not exceed 30 kg (66 lbs) for any limited-quantity shipment of dangerous goods.
- Secure the chain-of-custody form (placed inside a zip-type bag) to the interior of the cooler lid.
- If the shipment is from a DOE or other facility, place the results of the radiation screen and cooler/sample survey with the chain-of-custody.
- Wrap strapping tape or duct tape around both ends of the cooler and around the cooler lid.
- Affix custody seals to opposite sides of the cooler lid. Cover the custody seals with clear waterproof tape.
- Mark the outside of the cooler with the proper shipping name of the contents, corresponding UN number, and LTD. QTY. (as shown below).

Sulfuric Acid Solution UN2796 LTD. QTY.



SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 15 of 21

Place a label on the front of the cooler with the company name, contact name, phone number, full street address, and state with zip code for both shipper and recipient.

Affix a Corrosive label to the outside of the cooler.

Affix package orientation labels on two opposite sides of the cooler.

 Secure the marking and labels to the surface of the cooler with clear waterproof tape to prevent accidental removal during shipment.

An example of cooler labeling/marking locations is shown in Figure 1.

Note: Samples containing less than the exception concentration of 0.35 percent H₂SO₄

by weight will be shipped as non-regulated or non-hazardous in accordance

with the procedure described in Section 1.4.

Note: No marking or labeling can be obscured by strapping or duct tape.

Note: The inner packaging of dangerous goods must be placed into the designated

cooler for shipment. Other non-regulated environmental samples may be added

to the cooler for shipment.

When shipping from a DOE facility, the cooler will be surveyed by a qualified radiation control technician to ensure that radiation flux on exterior surfaces does not exceed 0.5 mrem/h on all sides. This survey will be documented and the results reviewed by the qualified shipper.

Complete the Dangerous Goods and Hazardous Materials Inspection Checklist for Shipping

Limited-Quantity (Appendix A).

Complete a Dangerous Goods Airbill.

7.0 Packaging and Shipping Limited-Quantity Radioactive Samples 7.1 Containers

The inner packaging containers that may be used for these shipments include:

Any size sample container

7.2 Description/Responsibilities

- The qualified shipper will determine that the samples undergoing shipment contain no other contaminant that meets the definition of hazardous material as defined by DOT.
- The qualified shipper will ship all samples that meet the Class 7 definition of radioactive materials and meet the activity requirements specified in Table 7 of 49 CFR 173.425, as Radioactive Materials in Limited Quantity. The qualified shipper will verify that all packages and their contents meet the requirements of 49 CFR 173.421, Limited Quantities of Radioactive Materials.
- The packaging used for shipping will meet the general requirements for packaging and packages specified in 49 CFR 173.24 and the general design requirements provided in 173.410. These standards state that a package must be capable of withstanding the effects of any acceleration, vibration, or vibration resonance that may arise under normal condition of transport without any deterioration in the effectiveness of the closing devices on the various

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 16 of 21

receptacles or in the integrity of the package as a whole and without loosening or unintentionally releasing the nuts, bolts, or other securing devices even after repeated use.

- If the shipment is from a DOE facility, radiological screenings will be completed on all samples taken. The qualified shipper will review the results of each screening (alpha, beta, and gamma speciation). Samples will not be shipped offsite until the radiological screening has been performed.
- The total activity for each package will not exceed the relevant limits listed in Table 7 of 49 CFR 173.425. The A₂ value of the material will be calculated based on all radionuclides found during previous investigations (if any) in the area from which the samples are derived. The A₂ values to be used will be the most restrictive of all potential radionuclides as listed in 49 CFR 173.435.
- The radiation level at any point on the external surface of the package bearing the sample(s) will not exceed 0.005 mSv/hour (0.5 mrem/hour). These will be verified by dose and activity monitoring prior to shipment of the package.
- The removable radioactive surface contamination on the external surface of the package will not exceed the limits specified in 49 CFR 173.443(a). CDM will apply the DOE-established free release criteria for removable surface contamination of less than 20 dpm/100 cm² (alpha) and 1,000 dpm/100 cm² (beta/gamma). It should be noted that these values are more conservative than the DOT requirements for removable surface contamination.
- The qualified shipper will verify that the outside of the inner packaging is marked "Radioactive."
- The qualified shipper will verify that the excepted packages prepared for shipment under the provisions of 49 CFR 173.421 have a notice enclosed, or shown on the outside of the package, that reads, "This package conforms to the conditions and limitations specified in 49 CFR 173.421 for radioactive material, excepted package-limited quantity of material, UN2910."

7.3 Additional Required Equipment

The following equipment is needed in addition to the required equipment listed in Section 1.3.

- Survey documentation/radiation screening results (if shipping from DOE or radiological sites)
- Orientation labels
- Excepted quantities label
- Consignor/consignee labels

7.4 Packaging of Limited-Quantity Radioactive Samples

The following steps are to be followed when packaging limited-quantity sample shipments.

- The cooler is to be surveyed by a qualified radiation control technician to ensure that radiation flux on exterior surfaces does not exceed 0.5 mrem/h on all sides. This survey will be documented and the results reviewed by the qualified shipper.
- Tape any interior opening in the cooler (drain plug) from the inside to ensure control of interior contents. Also, tape the drain plug from the outside of the cooler.
- All sample containers will be properly labeled and the label protected with waterproof tape prior to sampling.
- At a minimum the label must contain:
 - Project name
 - Project number

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 17 of 21

- Date and time of sample collection
- Sample location
- Sample identification number
- Collector's initials
- This step is optional; wrap each container in bubble wrap (secure with waterproof tape) to prevent breakage.
- Place sufficient amount of vermiculite, or approved packaging material, in the bottom of the cooler to absorb any leakage that may occur.
- Place a garbage bag in the cooler.
- Pack the samples appropriately inside the garbage bag (bottles placed upright) to prevent movement during shipment.
- If required, place a sufficient amount of double-bagged ice around the samples to maintain the required temperature during shipment.
- Seal the garbage bag by tieing or taping.
- Place a label marked Radioactive on the outside of the sealed bag.
- Enclose a notice that includes the name of the consignor or consignee and the following statement: "This package conforms to the conditions and limitations specified in 49 CFR 173.421 for radioactive material, excepted package-limited quantity of material, UN2910."
- Note that both DOT and IATA apply different limits to the quantity in the inside packing and in the outside packing.
- The maximum weight of the package shall not exceed 30 kg (66 lbs) for any limited-quantity shipment of dangerous goods.
- Secure the chain-of-custody form (placed inside a zip-type bag) to the interior of the cooler lid.
- If the shipment is from a DOE or other facility, place the results of the radiation screen and cooler/sample survey with the chain-of-custody.
- If a cooler is used, wrap strapping tape or duct tape around both ends of the cooler and around the cooler lid.
- Affix custody seals to opposite sides of the cooler lid. Cover the custody seals with clear waterproof tape.
- Place a label on the front of the cooler with the company name, contact name, phone number, full street address, and state with zip code for both shipper and recipient.
- Affix package orientation labels on two opposite sides of the cooler/package.
- Affix a completed Excepted Quantities label to the side of the cooler/package.
- Secure any marking and labels to the surface of the cooler with clear waterproof tape to prevent accidental removal during shipment.
- An example of the cooler labeling/marking is shown in Figure 2.

Note: No marking or labeling can be obscured by strapping or duct tape.

- Complete the Shipment Quality Assurance Checklist (Appendix B).
 - Note: Except as provided in 49 CFR 173.426, the package will not contain more than 15

grams of 235U.


Note: A declaration of dangerous goods is not required.

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 18 of 21

Figure 2 - Radioactive Material - Limited-Quantity Cooler Marking Example



8.0 References

U.S. Environmental Protection Agency, Sampler's Guide to the Contract Laboratory Program, EPA/540/P-90/006, December 1990.

U.S. Environmental Protection Agency, Region IV, Standard Operating Procedures and Quality Assurance Manual, February 1991.

U.S. Environmental Protection Agency Rule, 40 CFR 136.

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 19 of 21

Appendix A

Dangerous Goods and Hazardous Materials Inspection Checklist for Shipping Limited-Quantity

Samp	le Paci	kaging	
Yes	No	N/A	The VOA vials are wrapped in bubble wrap and placed inside a zip-type bag. The VOA vials are placed into a polyethylene bottle, filled with vermiculite, and tightly sealed.
0 0	0	0	The drain plug is taped inside and outside to ensure control of interior contents. The samples have been placed inside garbage bags with sufficient bags of ice to preserve samples at 4°C.
00	0	0	The cooler weighs less than the 66-pound limit for limited-quantity shipment. The garbage bag has been sealed with tape (or tied) to prevent movement during shipment.
000	0	000	The chain-of-custody has been secured to the interior of the cooler lid. The cooler lid and sides have been taped to ensure a seal. The custody seals have been placed on both the front and back hinges of the cooler, using waterproof tape.
Air W	aybill	Completi	on
Yes	No	N/A	Section 1 has the shipper's name, company, and address; the account number, date, internal billing reference number; and the telephone number where the shipper can be reached.
a	ū	0	Section 2 has the recipient's name and company along with a telephone number where they can be reached.
0000	0000	0000	Section 3 has the Bill Sender box checked. Section 4 has the Standard Overnight box checked. Section 5 has the Deliver Weekday box checked. Section 6 has the number of packages and their weights filled out. Was the total of
0	۵	0	all packages and their weights figured up and added at the bottom of Section 6? Under the Transport Details box, the Cargo Aircraft Only box is obliterated, leaving only the Passenger and Cargo Aircraft box.
0			Under the Shipment Type, the Radioactive box is obliterated, leaving only the Non-Radioactive box.
a			Under the Nature and Quantity of Dangerous Goods box, the Proper Shipping Name, Class or Division, UN or ID No., Packing Group, Subsidiary Risk, Quantity and Type of Packing, Packing Instructions, and Authorization have been filled out for the type of chemical being sent.
ū			The Name, Place and Date, Signature, and Emergency Telephone Number appears at the bottom of the FedEx Airbill.
ū			The statement "In accordance with IATA/ICAO" appears in the Additional Handling Information box.
۵	0		The Emergency Contact Information at the bottom of the FedEx Airbill is truly someone who can respond any time of the day or night.

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 20 of 21

Proper Shipping Name	Class or Division	UN or ID No.	Packing Group	Sub Risk	Quantity	Packing Instruction	Authorizațion
Hydrochloric Acid Solution	8	UN1789	II		1 plastic box × 0.5 L	Y809	Ltd. Qty.
Nitric Acid Solution (with less than 20%)	8	UN2031	11		1 plastic box × 0.5 L	Y807	Ltd. Qty.
Sodium Hydroxide Solution	8	UN1824	li		1 plastic box × 0.5 L	Y809	Ltd. Qty.
Sulfuric Acid Solution	8	UN2796	II		1 plastic box × 0.5 L	Y809	Ltd. Qty.
Methanol	3	UN1230	II		1 plastic box × 1 L	Y305	Ltd. Qty.

Sample Cooler Labeling

Yes	No	N/A	•
ū		o i	The proper shipping name, UN number, and Ltd. Qty. appears on the shipping container.
O.		Q	The corresponding hazard labels are affixed on the shipping container; the labels are not obscured by tape.
C)			The name and address of the shipper and receiver appear on the top and side of the shipping container.
Q			The air waybill is attached to the top of the shipping container.
Q.			Up Arrows have been attached to opposite sides of the shipping container.
Q.		ū	Packaging tape does not obscure markings or labeling.

SOP: 2-1 Revision: 2

Date: March 1, 2004

Page 21 of 21

Appendix B Shipment Quality Assurance Checklist

Date:			Shipper: Destination:
Item(s) I	Descri	ptio	n:
Radionu	ıclide(s): _	
Radiolog	gical S	urv	ey Results: surfacemrem/hr 1 meter
Instrume	ent Us	sed:	Mfgr: Model:
S/N:			Cal Date:
			Limited-Quantity or Instrument and Article
Yes	No		
		1.	Strong tight package (package that will not leak material during conditions normally incidental to transportation).
		2.	Radiation levels at any point on the external surface of package less than or equal to
		3.	0.5 mrem/hr. Removable surface contamination less than 20 dpm/100 cm ² (alpha) and 1,000
			dpm/100 cm ² (beta/gamma). Outside inner package bears the marking "Radioactive."
			Package contains less than 15 grams of ²³⁵ U (check yes if ²³⁵ U not present).
			Notice enclosed in or on the package that includes the consignor or consignee and the statement, "This package conforms to the conditions and limitations specified in 49 CFR 173.421 for radioactive material, excepted package-limited quantity of material, UN2910."
		7.	Activity less than that specified in 49 CFR 173.425. Permissible package limit:
-		8.	Package Quantity: On all air shipments, the statement Radioactive Material, excepted package- limited quantity of material shall be noted on the air waybill.
Qualifie	d Ship	per	Signature:

Project Specific Modification

SOP No.: 2-2

SOP Title: Guide to Handling Investigation-Derived Waste

Project: Libby Asbestos Remedial Investigation (RI)

Project No.: 3282-137

Client: U.S. Environmental Protection Agency

Project Manager: Date: 5/7/03

Technical Reviewer: Date: 5)7/03

Reason for and duration of modification: Site-specific procedures for disposing of Libby amphibole asbestos contaminated IDW are different than CDM Technical SOP 2-2. These modifications are necessary for the entire duration of the project.

All IDW will be handled in accordance with CDM Technical SOP 2-2, Guide to Handling Investigation-Derived Waste, with the following modifications:

Section 5.2, Off Site Disposal - All IDW (not including excess soil volume) will be collected in transparent garbage bags and marked "IDW" with an indelible marker. These bags will be deposited into the asbestos contaminated waste stream for deposal at the mine.

SOP: 2-2 Revision: 4

Date: March 1, 2004

Page 1 of 7

Prepared:	Tim Eggert	Technical Review:	Sharon Budney	Z
•		, ,		

OA Review: Jeniffer Oxford

proved: Mulac C Mal

Signature/

Issued:

Signature/Date

1.0 Objective

This standard operating procedure (SOP) presents guidance for the management of investigation-derived waste (IDW). The primary objectives for managing IDW during field activities include:

- Leaving the site in no worse condition than existed prior to field activities
- Remove wastes that pose an immediate threat to human health or the environment
- Proper handling of onsite wastes that do not require offsite disposal or extended above-ground containerization
- Complying with federal, state, and facility applicable or relevant and appropriate requirements (ARARs)
- Careful planning and coordination of IDW management options
- Minimizing the quantity of IDW

2.0 Background

2.1 Definitions

Hazardous Waste – Discarded material that is regulated listed waste, or waste that exhibits ignitability, corrosivity, reactivity, or toxicity as defined in 40 CFR 261.3 or state regulations.

Investigation-Derived Wastes (IDWs) - Discarded materials resulting from field activities such as sampling, surveying, drilling, excavations, and decontamination processes that, in present form, possess no inherent value or additional usefulness without treatment. Wastes may be solid, liquid, or gaseous, or multiphase materials that may be classified as hazardous or non-hazardous.

Mixed-Waste - Any material that has been classified as hazardous and radioactive.

Radioactive Wastes – Discarded materials that are contaminated with radioactive constituents with specific activities in concentrations greater than the latest regulatory criteria (i.e., 10 CFR 20).

Treatment, Storage, and Disposal Facility (TSDF) - Permitted facilities that accept hazardous waste shipments for further treatment, storage, and/or disposal. These facilities must be permitted by the U.S. Environmental Protection Agency (EPA) and appropriate state agencies.

2.2 Discussion

Field investigation activities result in the generation of waste materials that may be characterized as hazardous or radioactive waste. IDWs may include drilling muds, cuttings, and purge water from test pit and well installation; purge water, soil, and other materials from collection of samples; residues from testing of treatment technologies and pump and treat systems; personal protective equipment (PPE); solutions (aqueous or otherwise) used to decontaminate non-disposable protective clothing and

SOP: 2-2 Revision: 4

Date: March 1, 2004

Page 2 of 7

equipment; and other wastes or supplies used in sampling and testing potentially hazardous or radiologically contaminated material.

Note: The client's representatives may not be aware of all potential contaminants. The management of IDW must comply with applicable regulatory requirements.

3.0 Responsibilities

Site Manager - The site manager is responsible for ensuring that all IDW procedures are conducted in accordance with this SOP. The site manager is also responsible for ensuring that handling of IDW is in accordance with site-specific requirements.

Project Manager - The project manager is responsible for identifying site-specific requirements for the disposal of IDW in accordance with federal, state, and/or facility requirements.

Field Crew Members - Field crew members are responsible for implementing this SOP and communicating any unusual or unplanned condition to the project manager's attention.

4.0 Required Equipment

Equipment required for IDW containment will vary according to site-specific/client requirements. Management decisions concerning the necessary equipment required should consider: containment method, sampling, labeling, maneuvering, and storage (if applicable). Equipment must be onsite and inspected before commencing work.

4.1 IDW Containment Devices

The appropriate containment device (drums, tanks, etc.) will depend on site- or client-specific requirements and the ultimate disposition of the IDW. Typical IDW containment devices can include:

- Plastic sheeting (polyethylene) with a minimum thickness of 20 millimeters
- Department of Transportation (DOT) approved steel containers
- Bulk storage tanks comprised of polyethylene or steel

Containment of IDW should be segregated by waste type (i.e., solid or liquid, corrosive or flammable, etc.) and source location. Volume of the appropriate containment device should be site-specific.

4.2 IDW Container Labeling

A "Waste Container" or "IDW Container" label or indelible marking should be applied to each container. Labeling or marking requirements for onsite IDW not expected to be transported offsite are:

- Labels and markings that contain the following information: project name, generation date, location of waste origin, container identification number, sample number (if applicable), and contents (drill cuttings, purge water, PPE, etc.).
- Each label or marking will be applied to the upper one-third of the container at least twice, on opposite sides.
- Containers that are 5 gallons or less may only require one label or set of markings.
- Labels or markings will be positioned on a smooth part of the container. The label must not be affixed across container bungs, seams, ridges, or dents.

SOP: 2-2 Revision: 4

Date: March 1, 2004

Page 3 of 7

Labels must be constructed of a weather-resistive material with markings made with a
permanent marker or paint pen and capable of enduring the expected weather conditions. If
markings are used, the color must be easily distinguishable from the drum color.

Labels will be secured in a manner to ensure the label remains affixed to the container.

Labeling or marking requirements for IDW expected to be transported offsite must be in accordance with the requirements of 49 CFR 172.

4.3 IDW Container Movement

Staging areas for IDW containers should be predetermined and in accordance with site-specific and/or client requirements. Arrangements should be made prior to field mobilization as to the methods and personnel required to safely transport IDW containers to the staging area. Transportation offsite onto a public roadway is prohibited unless 49 CFR 172 requirements are met.

4.4 IDW Container Storage

Containerized IDW should be staged pending chemical analysis or further onsite treatment. Staging areas and bulk storage procedures are to be determined according to site-specific requirements. Containers are to be stored in such a fashion that the labels can be easily read. A secondary/spill container must be provided as appropriate.

5.0 Procedures

The three general options for managing IDW are (1) collection and onsite disposal, (2) collection for offsite disposal, and (3) collection and interim management. Attachment 1 summarizes media-specific information on generation processes and management options. The option selected should take into account the following factors:

- Type (soil, sludge, liquid, debris), quantity, and source of IDW
- Risk posed by managing the IDW onsite
- Compliance with regulatory requirements
- IDW minimization and consistency with the IDW remedy and the site remedy

In all cases the client should approve the plans for IDW. Formal plans for the management of IDW must be prepared as part of a work plan or separate document.

5.1 Onsite Disposal

5.1.1 Soil/Sludge/Sediment

The options for handling soil/sludge/sediment IDW are as follows:

- 1. Return to boring, pit, or source immediately after generation as long as returning the media to these areas will not increase site risks (e.g., the contaminated soil will not be replaced at a greater depth than where it was originally so that it will not contaminate "clean" areas).
- 2. Spread around boring, pit, or source within the area of contamination (AOC) as long as returning the media to these areas will not increase site risks (e.g., direct contact with surficial contamination).

SOP: 2-2 Revision: 4

Date: March 1, 2004

Page 4 of 7

- 3. Consolidate in a pit within the AOC as long as returning the media to these areas will not increase site risks (e.g., the contaminated soil will not be replaced at a greater depth than where it was originally so that it will not contaminate "clean" areas).
- 4. Send to onsite TSDF may require analytical analysis prior to treatment/disposal.

Note: These options may require client and/or regulatory approval.

5.1.2 Aqueous Liquids

The options for handling aqueous liquid IDW are as follows:

- 1. Discharge to surface water, only when IDW is not contaminated.
- 2. Discharge to ground surface close to the well, only if soil contaminants will not be mobilized in the process and the action will not contaminate clean areas. If IDW from the sampling of background upgradient wells is not a community concern or associated with soil contamination, this presumably uncontaminated IDW may be released on the ground around the well.
- 3. Discharge to sanitary sewer.
- 4. Send to onsite TSDF may require analysis prior to treatment/disposal.

Note: These options may require analytical results to obtain client and/or regulatory approval.

5.1.3 Disposable PPE

The options for handling disposable PPE are as follows:

- 1. Double-bag contents in non-transparent trash bags and place in onsite industrial dumpster, only if PPE is not contaminated.
- 2. Containerize, label, and send to onsite TSDF may require analysis prior to treatment/disposal.

5.2 Offsite Disposal

Before sending to an offsite TSDF, analysis may be required. Also, manifests are required. Arrangements must be made with the client responsible for the site; it is CDM's policy not to sign manifests. The TSDF and transporter must be permitted for the respective wastes.

5.2.1 Soil/Sludge/Sediment

When the final site remedy requires offsite treatment and disposal, the IDW may be stored (e.g., drummed, covered in a waste pile) or returned to its source until final disposal. The management option selected should take into account the potential for increased risks, applicable regulations, and other relevant site-specific factors (e.g., weather, storage space, and public concern/perceptions).

5.2.2 Aqueous Liquids

When the final site remedy requires offsite treatment and disposal, the IDW may be stored (e.g., mobile tanks or drums) until final disposal. The management option selected should take into account the

SOP: 2-2 Revision: 4

Date: March 1, 2004

Page 5 of 7

potential for increased risks, applicable regulations, and other relevant site-specific factors (e.g., weather, storage space, and public concern/perceptions).

5.2.3 Disposable PPE

When the final site remedy requires offsite treatment disposal, the IDW may be containerized and stored. The management option selected should take into account potential for increased risks, applicable regulations, and other relevant site-specific factors (e.g., weather, storage space, and public concern/perceptions).

5.3 Interim Measures

All interim measures must be approved by the client and regulatory agencies.

- 1. Storing IDW onsite until the final action may be practical in the following situations:
 - A. Returning wastes (especially sludges and soils) to their onsite source area would require reexcavation for disposal in the final remediation alternative.
 - B. Interim storage in containers may be necessary to provide adequate protection to human health and the environment.
 - C. Offsite disposal options may trigger land disposal regulations under the Resource Conservation and Recovery Act (RCRA). Storing IDW until the final disposal of all wastes from the site will eliminate the need to address this issue more than once.
 - D. Interim storage may be necessary to provide time for sampling and analysis.
- 2. Segregate and containerize all waste for future treatment and/or disposal.
 - A. Containment options for soil/sludge/sediment may include drums or covered waste piles in AOC.
 - B. Containment options for aqueous liquids may include mobile tanks or drums.
 - C. Containment options for PPE may include drums or roll-off boxes.

6.0 Restrictions/Limitations

Site Managers Should Determine the Most Appropriate Disposal Option for Aqueous Liquids on a Site-Specific Basis. Parameters to consider, especially when determining the level of protection, include the volume of IDW, the contaminants present in the groundwater, the presence of contaminants in the soil at the site, whether the groundwater or surface water is a drinking water supply, and whether the groundwater plume is contained or moving. Special disposal/handling may be needed for drilling fluids because they may contain significant solid components.

Disposable sampling materials, disposable PPE, decontamination fluids, etc. will always be managed on a site-specific basis. Under No Circumstances Should These Types of Materials Be Brought Back to the Office or Warehouse.



SOP: 2-2 Revision: 4

Date: March 1, 2004

Page 6 of 7

7.0 References

Environmental Resource Center. 1992. Hazardous Waste Management Compliance Handbook, Van Nostrand Reinhold.

Institute of Hazardous Materials Management. 1992. Handbook on Hazardous Materials Management, 4th Ed.

- U. S. Environmental Protection Agency. 1987. A Compendium of Superfund Field Operations Methods, EPA/540/P-87/001.1.
- U. S. Environmental Protection Agency. August 1990. Low-Level Mixed Waste: A RCRA Perspective for NRC Licensees, EPA/530-SW-90-057.
- U. S. Environmental Protection Agency. May 1991. Management of Investigation-Derived Wastes During Site Inspections, EPA/540/G-91/009.
- U. S. Environmental Protection Agency. January 1992. Guide to Management of Investigation-Derived Wastes, 9345.3-03FS.
- U. S. Environmental Protection Agency, Region IV. May 1996 and 1997. Environmental Investigations Standard Operating Procedures and Quality Assurance Manual, revisions.

SOP: 2-2 Revision: 4

Date: March 1, 2004

Page 7 of 7

		chment 1
7	IDVV Mana Generation Processes	gement Options Management Options
Type of IDW:	Well/Test pit installations Borehole drilling Soil sampling	Management Options Onsite Disposal Return to boring, pit, or source immediately after generation Spread around boring, pit, or source within the AOC Consolidate in a pit (within the AOC) Send to onsite TSDF Offsite Disposal Client to send to offsite TSDF Interim Management Store for future treatment and/or disposal
Sludge/Sediment	 Sludge pit/sediment sampling 	Onsite Disposal Return to boring, pit, or source immediately after generation Send to onsite TSDF Offsite Disposal Client to send to offsite TSDF Interim Management Store for future treatment and/or disposal
Aqueous Liquids (groundwater, surface water, drilling fluids, wastewaters)	 Well installation/development Well purging during sampling Groundwater discharge during pump tests Surface water sampling Wastewater sampling 	Onsite Disposal Pour onto ground close to well (nonhazardous waste) Discharge to sewer Send to onsite TSDF Offsite Disposal Client to send to offsite commercial treatment unit Client to send to publicly owned treatment works (POTW Interim Management Store for future treatment and/or disposal
Decontamination Fluids	Decontamination of PPE and equipment	Onsite Disposal Send to onsite TSDF Evaporate (for small amounts of low contamination organic fluids) Discharge to ground surface Offsite Disposal Client to send to offsite TSDF Discharge to sewer Interim Management Store for future treatment and/or disposal
Disposable PPE and Sampling Equipment	Sampling procedures or other onsite activities	Onsite Disposal Place in onsite industrial dumpster Send to onsite TSDF Offsite Disposal Client to send to offsite TSDF Interim Management Store for future treatment and/or disposal

January 1992.

Project-Specific Modification

SOP No.: 4-1

SOP Title: Field Logbook Content and Control

Project: Libby Asbestos Remedial Investigation (RI)

Project No.: 3282-137

Client: U.S. Environmental Protection Agency

Project Manager: Date: 5/7/03

Technical Reviewer: Date: 5703

QA Reviewer: Date: 5/12/03

EPA Approval: Date: 5/19/03

Reason for and duration of modification: Site-specific procedures field logbook completions are different than CDM Technical SOP 4-1. These modifications are necessary for the entire duration of the project.

All content and control of will logbooks will be done accordance with CDM Technical SOP 4-1, Field Logbook Content and Control, with the following modifications:

Section 5.2, Operation – A new page will be completed for each property where information is collected for RI activities. The header information will include the address, the name of the property owner, and the building identification number of structures on the property.

When following the line-out and signature procedures to close a logbook page, the author must also print their name under the signature.

Libby Asbestos Project Logbook Requirements

Updated March 2007

Header Information

- Name of contract/project: Volpe/Libby Asbestos Project
- Address of property
- Property owner's name
- Logbook number

Individual Pages

- Date and time (time always in military units)
- Author (please print your name)
- Personnel onsite, description of activities being performed, and title(s) of governing documents

Examples:

- John Doe (CDM Oversight) and Jack Black (ER Foreman) on site inspecting ground floor containment in accordance with the RAWP (11/03)
- John Doe (CDM Air Tech) setting up kneewall clearance samples in accordance with the RAWP (11/03)
- Weather conditions
- Level of personal protection being used
- Equipment being used (e.g., Horiba U22 water quality meter; QuickTake 30 air sampling pump)
- Required calibration information

Other Requirements

- For corrections, line out once, initial, and date the change
- Define less commonly used acronyms/abbreviations
- Do not write over the page number in the logbook
- Describe any deviations to procedures or processes, including names of personnel directing the change and implications of the change
- Note periods of down-time, delays, or other problems
- Keep the Table of Contents up-to-date
- Once completing the logbook, make sure the table of contents is complete and unused pages are lined out before turning in to admin staff

For your reference, CDM SOP 4-1 Revision 5 is attached.

SOP 4-1

Revision: 5 Date: March 1, 2004

Page 1 of 4

Prepared: Del Baird

Technical Review: Sharon Budney

OA Review: Douglas J. Updike

1.0 Objective

The objective of this standard operating procedure (SOP) is to set CDM Federal (CDM) criteria for content entry and form of field logbooks. Field logbooks are an essential tool to document field activities for historical and legal purposes.

2.0 Background

2.1 Definitions

Biota - The flora and fauna of a region.

Magnetic Declination Corrections - Compass adjustments to correct for the angle between magnetic north and geographical meridians.

2.2 Discussion

Information recorded in field logbooks includes field team names, observations, data, calculations, date/time, weather, and description of the data collection activity, methods, instruments, and results. Additionally, the logbook may contain deviations from plans and descriptions of wastes, biota, geologic material, and site features including sketches, maps, or drawings as appropriate.

3.0 Responsibilities

Field Team Leader (FTL) - The FTL is responsible for ensuring that the format and content of data entries are in accordance with this procedure.

Site Personnel - All CDM employees who make entries in field logbooks during onsite activities are required to read this procedure prior to engaging in this activity. The FTL will assign field logbooks to site personnel who will be responsible for their care and maintenance. Site personnel will return field logbooks to the records file at the end of the assignment.

4.0 Required Equipment

- Site-specific plans
- Field notebook
- Indelible black or blue ink pen
- Ruler or similar scale

SOP 4-1 Revision: 5

Date: March 1, 2004

Page 2 of 4

5.0 Procedures

5.1 Preparation

In addition to this SOP, site personnel responsible for maintaining logbooks must be familiar with all procedures applicable to the field activity being performed. These procedures should be consulted as necessary to obtain specific information about equipment and supplies, health and safety, sample collection, packaging, decontamination, and documentation. These procedures should be located at the field office.

Field logbooks shall be bound with lined, consecutively numbered pages. All pages must be numbered prior to initial use of the logbook. Prior to use in the field, each logbook will be marked with a specific document control number issued by the document control administrator, if required by the contract quality implementation plan (QIP). Not all contracts require document control numbers. The following information shall be recorded on the cover of the logbook:

- Field logbook document control number.
- Activity (if the logbook is to be activity-specific) and location.
- Name of CDM contact and phone number(s).
- Start date.
- In specific cases, special logbooks may be required (e.g., waterproof paper for stormwater monitoring).

The first few (approximately five) pages of the logbook will be reserved for a table of contents (TOC). Mark the first page with the heading and enter the following:

Table of Contents

Date/Description (Start Date)/Reserved for TOC Page 1-5

The remaining pages of the table of contents will be designated as such with "TOC" written on the top center of each page.

5.2 Operation

Requirements that must be followed when using a logbook:

- Record work, observations, quantities of materials, calculations, drawings, and related information directly in the logbook. If data collection forms are specified by an activity-specific plan, this information need not be duplicated in the logbook. However, any forms used to record site information must be referenced in the logbook.
- Do not start a new page until the previous one is full or has been marked with a single diagonal line so that additional entries cannot be made. Use both sides of each page.
- Do not erase or blot out any entry at any time. Indicate any deletion by a single line through
 the material to be deleted. Initial and date each deletion. Take care to not obliterate what was
 written previously.
- Do not remove any pages from the book.

SOP 4-1

Revision: 5

Date: March 1, 2004

Page 3 of 4

Specific requirements for field logbook entries include:

- Initial and date each page.
- Sign and date the final page of entries for each day.
- Initial and date all changes.
- Multiple authors must sign out the logbook by inserting the following: Above notes authored by:
 - (Sign name)
 - (Print name)
 - (Date)
- A new author must sign and print his/her name before additional entries are made.
- Draw a diagonal line through the remainder of the final page at the end of the day.
- Record the following information on a daily basis:
 - Date and time
 - Name of individual making entry
 - Names of field team and other persons onsite
 - Description of activity being conducted including station or location (i.e., well, boring, sampling location number) if appropriate
 - Weather conditions (i.e., temperature, cloud cover, precipitation, wind direction, and speed) and other pertinent data
 - Level of personal protection to be used
 - Serial numbers of instruments
 - Required calibration information
 - Serial/tracking numbers on documentation (e.g., carrier air bills)

Entries into the field logbook shall be preceded with the time (written in military units) of the observation. The time should be recorded frequently and at the point of events or measurements that are critical to the activity being logged. All measurements made and samples collected must be recorded unless they are documented by automatic methods (e.g., data logger) or on a separate form required by an operating procedure. In these cases, the logbook must reference the automatic data record or form.

At each station where a sample is collected or an observation or measurement made, a detailed description of the location of the station is required. Use a compass (include a reference to magnetic declination corrections), scale, or nearby survey markers, as appropriate. A sketch of station location may be warranted. All maps or sketches made in the logbook should have descriptions of the features shown and a direction indicator. It is preferred that maps and sketches be oriented so that north is toward the top of the page. Maps, sketches, figures, or data that will not fit on a logbook page should be referenced and attached to the logbook to prevent separation.

Other events and observations that should be recorded include:

- Changes in weather that impact field activities.
- Deviations from procedures outlined in any governing documents. Also record the reason for any noted deviation.
- Problems, downtime, or delays.
- Upgrade or downgrade of personal protection equipment.



SOP 4-1 Revision: 5

Date: March 1, 2004

Page 4 of 4

5.3 Post-Operation

To guard against loss of data due to damage or disappearance of logbooks, completed pages shall be periodically photocopied (weekly, at a minimum) and forwarded to the field or project office. Other field records shall be photocopied and submitted regularly and as promptly as possible to the office. When possible, electronic media such as disks and tapes should be copied and forwarded to the project office.

At the conclusion of each activity or phase of site work, the individual responsible for the logbook will ensure that all entries have been appropriately signed and dated, and that corrections were made properly (single lines drawn through incorrect information, then initialed and dated). The completed logbook shall be submitted to the records file.

6.0 Restrictions/Limitations

Field logbooks constitute the official record of onsite technical work, investigations, and data collection activities. Their use, control, and ownership are restricted to activities pertaining to specific field operations carried out by CDM personnel and their subcontractors. They are documents that may be used in court to indicate dates, personnel, procedures, and techniques employed during site activities. Entries made in these logbooks should be factual, clear, precise, and non-subjective. Field logbooks, and entries within, are not to be used for personal use.

7.0 References

Sandia National Laboratories, *Procedure for Preparing Sampling and Analysis Plan, Site-Specific Sampling Plan, and Field Operating Procedures*, QA-02-03, Albuquerque Environmental Program Department 3220, Albuquerque, New Mexico, 1991.

Sandia National Laboratories, Division 7723, Field Operation Procedure for Field Logbook Content and Control, Environmental Restoration Department, Albuquerque, New Mexico, 1992.

Project-Specific Modification

SOP No.: 4-2

SOP Title: Photographic Documentation of Field Activities

Project: Libby Asbestos Remedial Investigation (RI)

Project No.: 3282-137

Client: U.S. Environmental Protection Agency

Project Manager. Date: 5/7/03

Technical Reviewer: Date: 5 7 03

QA Reviewer: Date: 5/12/03

EPA Approval: Date: 5/19/07

Reason for and duration of modification: <u>Site-specific procedures for photographs</u> taken by digital cameras are different than the current SOP.

All photographs will be recorded in accordance with CDM Technical SOP 4-2, Photographic Documentation of Field Activities, with the following modifications:

Section 5.2.2. General Guidelines for Still Photography - A slate is not required for each new roll of film. The information for the slate will be recorded in the field logbook. The numbers assigned by the digital camera will be used instead of the photographer assigning the number. The caption information will either be on the back of the photograph or the photograph will be numbered or labeled and the caption information listed next to the number or label in the photograph log. On the digital photos, a caption will be included in the picture stating property address/location, date, and name of feature. All team members, as stated in the logbook, will be photographers and witnesses at the property. Slates are not required for close-up photographs. Instead the required information can be listed in the logbook or photograph log. A color strip is not required for close-up or feature photographs.

<u>Section 5.2.4, Photographic Documentation</u> - The name of the laboratory, time and date of drop-off, and receipt of film is not required to be recorded for this project.

CDM Standard Operating Procedure

Project-Specific Modification

<u>Section 5.3.2</u>, <u>Archive Procedures</u> - Digital photographs will be archived on compact discs. These discs will be assigned a document control dumber written on the disc case as well as well as the disc.

SOP 4-2 Revision: 6

Date: March 1, 2004

Page 1 of 6

Prepared: David O. Johnson

Technical Review: Jo Nell Mullins

QA Review: Laura Splichal

Approved: \\

Signature Date

Signature/Date

1.0 Objective

The purpose of this standard operating procedure (SOP) is to provide standard guidelines and methods for photographic documentation, which include still and digital photography and videotape recordings of field activities and site features (geologic formations, core sections, lithologic samples, water samples, general site layout, etc.). This document shall provide guidelines designed for use by a professional or amateur photographer. This SOP is intended for circumstances when formal photographic documentation is required. Based on project requirements, it may not be applicable for all photographic activities.

2.0 Background

2.1 Definitions

Photographer - A photographer is the camera operator (professional or amateur) of still photography, including digital photography, or videotape recording whose primary function with regard to this SOP is to produce documentary or data-oriented visual media.

Identifier Component - Identifier components are visual components used within a photograph such as visual slates, reference markers, and pointers.

Standard Reference Marker - A standard reference marker is a reference marker that is used to indicate a feature size in the photograph and is a standard length of measure, such as a ruler, meter stick, etc. In limited instances, if a ruled marker is not available or its use is not feasible, it can be a common object of known size placed within the visual field and used for scale.

Slates - Slates are blank white index cards or paper used to present information pertaining to the subject/procedure being photographed. Letters and numbers on the slate will be bold and written with black, indelible marking pens.

Arrows and Pointers - Arrows and pointers are markers/pointers used to indicate and/or draw attention to a special feature within the photograph.

Contrasting Backgrounds - Contrasting backgrounds are backdrops used to lay soil samples, cores, or other objects on for clearer viewing and to delineate features.

Data Recording Camera Back - A data recording camera back is a camera attachment or built-in feature that will record, at the very least, frame numbers and dates directly on the film.

2.2 Discussion

Photographs and videotape recordings made during field investigations are used as an aid in documenting and describing site features, sample collection activities, equipment used, and possible

SOP 4-2 Revision: 6

Date: March 1, 2004

Page 2 of 6

lithologic interpretation. This SOP is designed to illustrate the format and desired placement of identifier components, such as visual slates, standard reference markers, and pointers. These items shall become an integral part of the "visual media" that, for the purpose of this document, shall encompass still photographs, digital photographs, and videotape recordings (or video footage). The use of a photographic logbook and standardized entry procedures are also outlined. These procedures and guidelines will minimize potential ambiguities that may arise when viewing the visual media and ensure the representative nature of the photographic documentation.

2.3 Associated Procedures

CDM Federal SOP 4-1, Field Logbook Content and Control

3.0 Responsibilities

Field Team Leader (FTL) – The FTL is responsible for ensuring that the format and content of photographic documentation are in accordance with this procedure. The FTL is responsible for directing the photographer to specific situations, site features, or operations that the photographer will be responsible for documenting.

Photographer – The photographer shall seek direction from the FTL and regularly discuss the visual documentation requirements and schedule. The photographer is responsible for maintaining a logbook per Sections 5.1, 5.2.4, and 5.3.1 of this SOP.

4.0 Required Equipment

The following is a general list of equipment that may be used:

- 35mm camera or disposable single use camera (35mm or panoramic use)
- Digital camera
- Extra batteries for 35mm camera
- Video camera
- Logbook
- Indelible black or blue ink pen
- Standard reference markers
- Slates
- Arrows or pointers
- Contrasting backgrounds
- Medium speed, or multi purpose fine-grain, color, 35 mm negative film or slide film (project dependent)
- Data recording camera back (if available)
- Storage medium for digital camera

5.0 Procedures

5.1 Documentation

A commercially available, bound logbook will be used to log and document photographic activities. Review the CDM Federal SOP 4-1, Field Logbook Content and Control and prepare all supplies needed for logbook entries.

Note: A separate photographic logbook is not required. A portion of the field logbook may be designated as the photographic log and documentation section.



SOP 4-2 Revision: 6

Date: March 1, 2004

Page 3 of 6

5.1.1 Field - Health and Safety Considerations

There are no hazards that an individual will be exposed to specific to photographic documentation. However, site-specific hazards may arise depending on location or operation. Personal protective equipment used in this operation will be site-specific and dictated through requirements set by the site safety officer, site health and safety plan, and/or prescribed by the CDM Federal Corporate Health and Safety Program. The photographer should contact the site safety officer for health and safety orientation prior to commencing field activities. The site health and safety plan must be read prior to entry to the site, and all individuals must sign the appropriate acknowledgement that this has been done.

The photographer should be aware of any potential physical hazards while photographing the subject (e.g., traffic, low overhead hazard, edge of excavation).

5.2 Operation

5.2.1 General Photographic Activities in the Field

The following sections provide general guidelines that should be followed to visually document field activities and site features using still/digital cameras and video equipment. Listed below are general suggestions that the photographer should consider when performing activities under this SOP:

- The photographer should be prepared to make a variety of shots, from close-up to wide-angle. Many shots will be repetitive in nature or format especially close-up site feature photographs. Consideration should therefore be given to designing a system or technique that will provide a reliable repetition of performance.
- All still film photographs should be made using a medium speed, or multi purpose fine-grain, color negative film in the 35 mm format unless otherwise directed by the FTL.
- It is suggested that Kodak brand "Ektapress Gold Deluxe" film or equivalent be used as the standard film for the still photography requirements of the field activities. This film is stable at room temperature after exposure and will better survive the time lag between exposure and processing. It is suggested that film speed ASA 100 should be used for outdoor photographs in bright sunlight, ASA 200 film should be used in cloudy conditions, and ASA 400 film should be used indoors or for very low-light outdoor photographs.
- No preference of videotape brand or digital storage medium is specified and is left to the discretion of the photographer.
- The lighting for sample and feature photography should be oriented toward a flat condition with little or no shadow. If the ambient lighting conditions are inadequate, the photographer should be prepared to augment the light (perhaps with reflectors or electronic flash) to maintain the desired visual effect.
- Digital cameras have multiple photographic quality settings. A camera that obtains a higher resolution (quality) has a higher number of pixels and will store a fewer number of photographs per digital storage medium.

5.2.2 General Guidelines for Still Photography

Slate Information

When directed by the FTL, each new roll of film or digital storage medium shall contain on the first usable frame (for film) a slate with consecutively assigned control numbers (a consecutive, unique number that is assigned by the photographer as in sample numbers).



SOP 4-2 Revision: 6

Date: March 1, 2004

Page 4 of 6

Caption Information

All still photographs will have a full caption permanently attached to the back or permanently attached to a photo log sheet. The caption should contain the following information (digital photographs should have a caption added after the photographs are downloaded):

- Film roll control number (if required) and photograph sequence number
- Date and time
- Description of activity/item shown (e.g., name of facility/site, specific project name, project no.)
- Direction (if applicable)
- Photographer

When directed by the FTL, a standard reference marker should be used in all documentary visual media. While the standard reference marker will be predominantly used in close-up feature documentation, inclusion in all scenes should be considered.

Digital media should be downloaded at least once each day.

Close-Up and Feature Photography

When directed by the FTL, close-up photographs should include a standard reference marker of appropriate size as an indication of the feature size and contain a slate marked with the site name and any identifying label, such as a well number or core depth, that clearly communicates to the viewer the specific feature being photographed.

Feature samples, core pieces, and other lithologic media should be photographed as soon as possible after they have been removed from their in situ locations. This enables a more accurate record of their initial condition and color. When directed by the FTL, include a standard reference color strip (color chart such as Munsell Soil Color Chart or that available from Eastman Kodak Co.) within the scene. This is to be included for the benefit of the viewer of the photographic document and serves as a reference aid to the viewer for formal lithologic observations and interpretations.

Site Photography

Site photography, in general, will consist predominantly of medium and wide-angle shots. A standard reference marker should be placed adjacent to the feature or, when this is not possible, within the same focal plane.

While it is encouraged that a standard reference marker and caption/slate be included in the scene, it is understood that situations will arise that preclude their inclusion within the scene. This will be especially true of wide-angle shots. In such a case, the film/tape control number shall be entered in the photographic logbook along with the frame number and all other information pertinent to the scene.

Panoramic

In situations where a wide-angle lens does not provide sufficient subject detail, a single-use disposable panoramic camera is recommended. If this type of camera is not available, a panoramic series of two or three photos would be appropriate. Panoramas can provide greater detail while covering a wide subject, such as an overall shot of a site.



SOP 4-2 Revision: 6

Date: March 1, 2004

Page 5 of 6

To shoot a panoramic series using a standard 35 mm or digital camera, the following procedure is recommended.

- Use a stable surface or tripod to support the camera
- Allow a 20 to 30 percent overlap while maintaining a uniform horizon
- Complete two to three photos per series

5.2.3 General Photographic Documentation Using Video Cameras

As a reminder, it is not within the scope of this document to set appropriate guidelines for presentation or "show" videotape recording. The following guidelines are set for documentary videotape recordings only and should be implemented at the discretion of the FTL.

Documentary videotape recordings of field activities may include an audio slate for all scenes. At the beginning of each video session, an announcer will recite the following information: date, time (in military units), photographer, site ID number, and site location. This oral account may include any additional information clarifying the subject matter being recorded.

A standard reference marker may be used when taking close-up shots of site features with a video camera. The scene may also include a caption/slate. It should be placed adjacent and parallel to the feature being photographed.

It is recommended that a standard reference marker and caption/slate be included in all scenes. The caption information is vital to the value of the documentary visual media and should be included. If it is not included within the scene, it should be placed before the scene.

Original videotape recordings will not be edited. This will maintain the integrity of the information contained on the videotape. If editing is desired, a working copy of the original videotape recording can be made.

A label should be placed on the videotape with the appropriate identifying information (i.e., project name, project number, date, location, etc.).

5.2.4 Photographic Documentation

Photographic activities must be documented in a photographic logbook or in a section of the field logbook. The photographer will be responsible for making proper entries.

In addition to following the technical standards for logbook entry as referenced in CDM Federal SOP 4-1, the following information should be maintained in the appropriate logbook:

- Photographer name.
- If required, an entry shall be made for each new roll/tape control number assigned.
- Sequential tracking number for each photograph taken (for digital cameras, the cameragenerated number may be used).
- Date and time (military time).
- Location.
- A description of the activity/item photographed.

SOP 4-2 Revision: 6

Date: March 1, 2004

Page 6 of 6

• If needed, a description of the general setup, including approximate distance between the camera and the subject, may be recorded in the logbook.

 Record as much other information as possible to assist in the identification of the photographic document.

5.3 Post Operation

All film will be sent for development and printing to a photographic laboratory (to be determined by the photographer). The photographer will be responsible for arranging transport of the film from the field to the photographic laboratory. The photographer shall also be responsible for arranging delivery of the negatives and photographs, digital storage medium, or videotape to the project management representative.

5.3.1 Documentation

At the end of each day's photographic session, the photographer(s) will ensure that the appropriate logbook has been completely filled out and maintained as outlined in CDM Federal SOP 4-1.

5.3.2 Archive Procedures

- 1. Photographs and the associated set of uncut negatives, digital media, and original unedited documentary videotape recordings will be submitted to the project files and handled according to contract records requirements. The FTL will ensure their proper distribution.
- 2. Completed pages of the appropriate logbook will be copied weekly and submitted to the project files.

6.0 Restrictions/Limitations

This document is designed to provide a set of guidelines for the field amateur or professional photographer to ensure that an effective and standardized program of visual documentation is maintained.

It is not within the scope of this document to provide instruction in photographic procedures, nor is it within the scope of this document to set guidelines for presentation or "show" photography.

The procedures outlined herein are general by nature. The FTL is responsible for specific operational activity or procedure. Questions concerning specific procedures or requirements should be directed to the FTL.

Note: Some sites do not permit photographic documentation. Check with the site contact for any restrictions.

7.0 References

U.S. Army Corps of Engineers, Requirements for the Preparation of Sampling and Analysis Plans, EM 200-1-3, February 2001, Appendix F.

U.S. Environmental Protection Agency, Region IV, Environmental Investigations Standard Operating Procedures and Quality Assurance Manual, Athens, Georgia, November 2001.

U.S. Environmental Protection Agency, National Enforcement Investigations Center, Multi-Media Investigation Manual, EPA-330/9-89-003-R, Revised March 1992, p. 85.



Project-Specific Modification

SOP No.: 4-5

SOP Title: Field Equipment Decontamination at Nonradioactive Sites

Project: Libby Asbestos Remedial Investigation (RI)

Project No.: 3282-137

Client: U.S. Environmental Protection Agency

Project Manager: Date: 5/7/63

Technical Reviewer: Date: 517/03

QA Reviewer: Date: 5/12/03

EPA Approval: Date: 5/19/03

Reason for and duration of modification: Site-specific procedures for decontamination of Libby amphibole asbestos contaminated field equipment are different than CDM Technical SOP 4-5. These modifications are necessary for the entire duration of the project.

All equipment used to collect, handle, or measure soil samples will be decontaminated in accordance with CDM Technical SOP 4-5, Field Equipment Decontamination at Nonradioactive Sites, with the following modifications:

Section 4.0, Required Equipment - Plastic sheeting will not be used during decontamination procedures. American Society for Testing and Materials (ASTM) Type II water will not be used. Rather, locally available deionized (DI) water will be used.

<u>Section 5.0, Procedures</u> - Decontamination water will not be captured and will be discharged to the ground at the property.

Section 5.6, Waste Disposal - Decontamination water will not be captured and will not be packaged, labeled, or stored as investigation-derived waste (IDW).

Prepared: Steven Fundingsland Technical Review: QA Review: Doug Updike Approved:

Signature/Date

1.0 Objective

issued:

The objective of this standard operating procedure (SOP) is to describe the general procedures required for decontamination of field equipment at nonradioactive sites. This SOP serves as a guide and is applicable at most sites; however, it should be noted that site-specific conditions (i.e., type of contamination, type of media sampled) and the governing agency (i.e., EPA, DOE, USACE) may require modifications to the decontamination procedures provided in this SOP.

S/gnature/Date

2.0 Background

2.1 Definitions

Acid Rinse - A solution of 10 percent nitric or hydrochloric acid made from reagent grade acid and analyte-free water.

Analyte-Free Water - Tap water that has been treated so that the water contains no detectable heavy metals or other inorganic compounds. Analyte-free water should be stored only in clean glass, stainless steel, or plastic containers that can be closed when not in use.

Clean - Free of visible contamination and when decontamination has been completed in accordance with this SOP.

Cross Contamination - The transfer of contaminants through equipment or personnel from the contamination source to less contaminated or noncontaminated samples or areas.

Decontamination - The process of rinsing or otherwise cleaning the surfaces of equipment to rid them of contaminants and to minimize the potential for cross contamination of samples or exposure of personnel.

Organic-Free/Analyte-Free Water - Tap water that has been treated so that the water meets the analyte-free water criteria and contains no detectable organic compounds. Organic-free/analyte-free water should be stored only in clean glass, Teflon™, or stainless steel containers that can be closed when not in use.

Potable Water - Tap water may be obtained from any municipal system. Chemical analysis of the water source may be required before it is used.

Soap - Low-sudsing, nonphosphate detergent such as Liquinox™.

Solvent Rinse - Pesticide grade, or better, isopropanol, acetone, or methanol.

2.2 Discussion

Decontamination of field equipment is necessary to ensure acceptable quality of samples by preventing cross contamination. Further, decontamination reduces health hazards and prevents the spread of contaminants offsite.

3.0 Responsibilities

Field Team Leader - The field team leader (FTL) ensures that field personnel are trained in the performance of this procedure and that decontamination is conducted in accordance with this procedure. The FTL may also be required to collect and document rinsate samples to provide quantitative verification that these procedures have been correctly implemented.

4.0 Required Equipment

- Stiff-bristle scrub brushes
- Plastic buckets and troughs
- Soar
- Nalgene or Teflon sprayers or wash bottles or 2- to 5-gallon, manual-pump sprayer (pump sprayer material must be compatible with the solution used)
- Plastic sheeting
- Disposable wipes, rags, or paper towels
- Potable water*
- Analyte-free water
- Organic-free/analyte-free water
- Gloves, safety glasses, and other protective clothing as specified in the site-specific health and safety plan
- High-pressure pump with soap dispenser or steam-spray unit (for large equipment only)
- Appropriate decontamination solutions pesticide grade or better and traceable to a source (e.g., 10 percent and/or 1 percent nitric acid [HNO₃], acetone, methanol, isopropanol, hexane)
- Tools for equipment assembly and disassembly (as required)
- 55-gallon drums or tanks (as required)
- Pallets for drums or tanks holding decontamination water (as required)
- * Potable water may be required to be tested for contaminants before use. Check field plan for requirements.

5.0 Procedures

All reusable equipment (nondedicated) used to collect, handle, or measure samples will be decontaminated before coming into contact with any sample. Decontamination of equipment will occur either at a central decontamination station or at portable decontamination stations set up at the sampling location, drill site, or monitoring well location. The centrally located decontamination station will include an appropriately sized bermed and lined area on which equipment decontamination will occur and shall be equipped with a collection system and storage vessels. In certain circumstances, berming is not required when small quantities of water are being generated and for some short duration field activities (i.e., pre-remedial sampling). Equipment should be transported to the decontamination station in a manner to prevent cross contamination of equipment and/or area. Precautions taken may include enclosing augers in plastic wrap while being transported on a flatbed truck.

The decontamination area will be constructed so that contaminated water is either collected directly into appropriate containers (5-gallon buckets or steel wash tubs) or within the berms of the decontamination area that then drains into a collection system. Water from the collection system will be transferred into 55-gallon drums or portable tanks for storage. Typically, decontamination water will be staged until sampling results or waste characterization results are obtained and evaluated and the proper disposition of the waste is determined. The exact procedure for decontamination waste disposal should be discussed in the field plan. Also, solvent and acid rinse fluids may need to be segregated from other investigation-derived wastes.

All items that will come into contact with potentially contaminated media will be decontaminated before use and between sampling and/or drilling locations. If decontaminated items are not immediately used, they will be covered either with clean plastic or aluminum foil depending on the size of the item. All decontamination procedures for the equipment being used are as follows:

General Guidelines

■ Potable, analyte-free, and organic-free/analyte-free water should be free of all contaminants of concern. Following the field plan, analytical data from the water source may be required.

- Sampling equipment that has come into contact with oil and grease will be cleaned with methanol or other approved
 alternative to remove the oily material. This may be followed by a hexane rinse and then another methanol rinse.
 Regulatory or client requirements regarding solvent use will be stated in the field plan.
- All solvents and acids will be pesticide grade or better and traceable to a source. The corresponding tot numbers will be recorded in the appropriate logbook. Solvents and acids are potentially hazardous materials and must be handled, stored, and transported accordingly. Solvents should never be used in a closed building. See the site-specific health and safety plan and/or the chemical's Material Safety Data Sheet (MSDS) for specific information regarding the safe use of the chemical.
- Decontaminated equipment will be allowed to air dry before being used.
- Documentation for all cleaning will be recorded in the appropriate logbook.
- Gloves, boots, safety glasses, and any other personnel protective clothing and equipment will be used as specified in the site-specific health and safety plan.

5.1 Heavy Equipment Decontamination

Heavy equipment includes drilling rigs and backhoes. Follow these steps when decontaminating this equipment:

- Establish a bermed decontamination area that is large enough to fully contain the equipment to be cleaned. If available, an existing wash pad or appropriate paved and bermed area may be used; otherwise, use one or more layers of heavy plastic sheeting to cover the ground surface and berms. All decontamination pads should be upwind of the area under investigation.
- With the rig in place, spray areas (rear of rig or backhoe) exposed to contaminated soils using a hot water high-pressure sprayer. Be sure to spray down all surfaces, including the undercarriage.
- Use brushes, soap, and potable water to remove dirt whenever necessary.
- Remove equipment from the decontamination pad and allow it to air dry before returning it to the work site.
- Record the equipment type, date, time, and method of decontamination in the appropriate logbook.
- After decontamination activities are completed, collect all contaminated wastewater, plastic sheeting, and disposable gloves, boots, and clothing in separate containers or receptacles. All receptacles containing contaminated items must be properly labeled for disposal as detailed in the field plan. Liquids and solids must be drummed separately.

5.2 Downhole Equipment Decontamination

Downhole equipment includes hollow-stem augers, drill pipes, rods, stems, etc. Follow these steps when decontaminating this equipment:

- Set up a centralized decontamination area, if possible. This area should be set up to collect contaminated rinse waters and to minimize the spread of airborne spray.
- Set up a "clean" area upwind of the decontamination area to receive cleaned equipment for air-drying. At a minimum, clean plastic sheeting must be used to cover the ground, tables, or other surfaces on which decontaminated equipment is to be placed. All decontamination pads should be upwind of any areas under investigation.
- Place the object to be cleaned on aluminum foil or plastic-covered wooden sawhorses or other supports. The objects to be cleaned should be at least 2 feet above the ground to avoid splashback when decontaminating.

- Using soap and potable water in the hot water high-pressure sprayer (or steam unit), spray the contaminated equipment. Aim downward to avoid spraying outside the decontamination area. Be sure to spray inside corners and gaps especially well. Use a brush, if necessary, to dislodge dirt.
- If using soapy water, rinse the equipment using clean, potable water. If using hot water, the rinse step is not necessary if the hot water does not contain a detergent. If the hot water contains a detergent, this final clean water rinse is required.
- Using a suitable sprayer, rinse the equipment thoroughly with analyte-free water.
- Remove the equipment from the decontamination area and place in a clean area upwind to air dry.
- Record equipment type, date, time, and method of decontamination in the appropriate logbook.
- After decontamination activities are completed, collect all contaminated wastewaters, plastic sheeting, and disposable gloves, boots, and clothing in separate containers or receptacles. All receptacles containing contaminated items must be properly labeled for disposal. Liquids and solids must be drummed separately.

5.3 Sampling Equipment Decontamination

Sampling equipment is defined as equipment that comes into direct contact with the sample media. Such equipment includes split spoon samplers, well casing and screens, and spatulas or bowls used to homogenize samples. Follow these steps when decontaminating this equipment:

- Set up a decontamination line on plastic sheeting. The decontamination line should progress from "dirty" to "clean." A clean area shall be established upwind of the decontamination wash/rinse activities to dry the equipment. At a minimum, clean plastic sheeting must be used to cover the ground, table, or other surfaces that the decontaminated equipment is placed for drying.
- Disassemble any items that may trap contaminants internally. Do not reassemble the items until decontamination and air drying are complete.
- Wash the items with potable water and soap using a stiff brush as necessary to remove particulate matter and surface films. The items may be steam cleaned using soap and hot water as an alternative to brushing. Note that polyvinyl chloride or plastic items should not be steam cleaned. Items that have come into contact with concentrated and/or oily contaminants may need to be rinsed with a solvent such as hexane and allowed to air dry prior to this washing step.
- Thoroughly rinse the items with potable water.
- If sampling for metals, thoroughly rinse the items with an acid solution (e.g., 10 percent nitric acid) followed by a rinse using analyte-free water. If sampling for organic compounds, thoroughly rinse the items with solvent (e.g., isopropanol) followed by a rinse using analyte-free water. The specific chemicals used for the acid rinse and solvent rinse phases should be specified in the work plan. The acid rinsate and solvent rinsate must each be containerized separately. Acids and solvents are potentially hazardous materials and care must be exercised when using these chemicals to prevent adverse health affects (e.g., skin burns, irritation to the eyes and respiratory system, etc.). Appropriate personal protective equipment must be worn when using these chemicals. These chemicals (including spent rinsate) must be managed and stored appropriately. Special measures such as proper labels, paperwork, notification, etc. may be required when transporting or shipping these chemicals.
- Rinse the items thoroughly using organic-free/analyte-free water.
- Allow the items to air dry completely.

- After drying, reassemble the parts as necessary and wrap the items in clean plastic wrap or in aluminum foil.
- Record equipment type, date, time, and method of decontamination in the appropriate logbook.
- After decontamination activities are completed, collect all contaminated waters, used solvents and acids, plastic sheeting, and disposable personal protective equipment. Place the contaminated items in properly labeled drums for disposal. Liquids and solids must be drummed separately. Refer to site-specific plans for labeling and waste management requirements.

5.4 Pump Decontamination

Follow the manufacturer's recommendation for specified pump decontamination procedures. At a minimum, follow these steps when decontaminating pumps:

- Set up the decontamination area and separate "clean" storage area using plastic sheeting to cover the ground, tables. and other surfaces. Set up four containers; the first container shall contain dilute (nonfoaming) soapy water, the second container shall contain potable water, the third container shall be empty to receive wastewater, and the fourth container shall contain analyte-free water.
- The pump should be set up in the same configuration as for sampling. Submerge the pump intake (or the pump, if submersible) and all downhole-wetted parts (tubing, piping, foot valve) in the soapy water of the first container. Place the discharge outlet in the wastewater container above the level of the wastewater. Pump soapy water through the pump assembly until it discharges to the waste container. Scrub the outside of the pump and other wetted parts with a metal brush.
- Move the pump assembly to the potable water container while leaving discharge outlet in the waste container. All downhole-wetted parts must be immersed in the potable water rinse. Pump potable water through the pump assembly until it runs clear.
- Move the pump intake to the analyte-free water container. Pump the water through the pump assembly. Pump the volume of water through the pump specified in the field plan. Usually, three pump-and-line-assembly volumes will be required.
- Decontaminate the discharge outlet by hand, following the steps outlined in Section 5.3.
- Remove the decontaminated pump assembly to the clean area and allow it to air dry upwind of the decontamination area. Intake and outlet orifices should be covered with aluminum foil to prevent the entry of airborne contaminants and particles.
- Record the equipment type, serial number, date, time, and method of decontamination in the appropriate logbook.

5.5 Instrument Probe Decontamination

Instrument probes used for field measurements such as pH meters, conductivity meters, etc. will be decontaminated between samples and after use with analyte-free, or better, water.

5.6 Waste Disposal

Refer to site-specific plans for waste disposal requirements. The following are guidelines for disposing of wastes:

- All wash water, rinse water, and decontamination solutions that have come in contact with contaminated equipment are to be handled, packaged, labeled, marked, stored, and disposed of as investigation-derived waste.
- Small quantities of decontamination solutions may be allowed to evaporate to dryness.

- If large quantities of used decontamination solutions will be generated, each type of waste should be contained in separate containers.
- Unless otherwise required, plastic sheeting and disposable protective clothing may be treated as solid, nonhazardous
- Waste liquids should be sampled, analyzed for contaminants of concern in accordance with disposal regulations, and disposed of accordingly.

6.0 Restrictions/Limitations

Nitric acid and polar solvent rinses are necessary only when sampling for metals or organics respectively. These steps should not be used, unless required, because of the potential for acid burns and ignitability hazards.

If the field equipment is not thoroughly rinsed and allowed to completely air dry before use, volatile organic residue, which interferes with the analysis, may be detected in the samples. The occurrence of residual organic solvents is often dependent on the time of year sampling is conducted. In the summer, volatilization is rapid, and in the winter, volatilization is slow. Check with your EPA region, state, and client for approved decontamination solvents.

7.0 References

American Society for Testing and Materials. 2002. Standard Practice for Decontamination of Field Equipment at Nonradioactive Waste Sites, ASTM D5088-02, January 10.

Department of Energy. Hazardous Waste Remedial Actions Program. 1996. Standard Operating Procedures for Site Characterization, DOE/HWP-100/R1. September. Hazardous Waste Remedial Actions Program. 1996. Quality Control Requirements for Field Methods, DOE/HWP-69/R2. September.

U. S. Environmental Protection Agency. 1987. A Compendium of Superfund Field Operations Methods, EPA/540/P-87/001.1.

. Region 2, 1989. CERCLA Quality Assurance Manual, Revision 1.

Region 4. 2001. Engineering Support Branch Standard Operating Procedures and Quality Assurance Manual. November.

Prepared:	Dave Johnson	Technical Re	eyiew:Mike Clark	
QA Review:		Approved:	Na 0 (10)00 44	2/21/04
Issued:	The att wheley		Signature/Da	
/	Signature/Date /			

1.0 Objective

The objective of this standard operating procedure (SOP) is to establish the baseline requirements, procedures, and responsibilities inherent to the control and use of all measurement and test equipment (M&TE). Contractual obligations may require more specific or stringent requirements that must also be implemented.

2.0 Background

2.1 Definitions

Traceability - The ability to trace the history, application, or location of an item and like items or activities by means of recorded identification.

2.2 Discussion

M&TE may be government furnished (GF), rented or leased from an outside vendor, or purchased. It is essential that measurements and tests resulting from the use of this equipment be of the highest accountability and integrity. To facilitate that, the equipment shall be used in full understanding and compliance with the instructions and specifications included in the manufacturer's operations and maintenance and calibration procedures and in accordance with any other related project-specific requirements.

2.3 Associated Procedures

- CDM Federal (CDM) Technical SOP 4-1
- CDM Quality Procedures (QPs) 2.1 and 2.3
- Manufacturer's operating and maintenance and calibration procedures

3.0 Responsibilities

All staff with responsibility for the direct control and/or use of M&TE are responsible for being knowledgeable of and understanding and implementing the requirements contained herein as well as any other related project-specific requirements.

The project manager (PM) or designee (equipment coordinator, quality assurance coordinator, field team leader, etc.) is responsible for initiating and tracking the requirements contained herein.

4.0 Required Equipment

- Determine and implement M&TE related project-specific requirements
- The maintenance and calibration procedures must be followed when using M&TE
- Obtain the maintenance and calibration procedures if they are missing or incomplete
- Attach or include the maintenance and calibration procedures with the M&TE
- Prepare and record maintenance and calibration in an Equipment Log or a Field Log as appropriate (Figure 1)
- Maintain M&TE records
- Label M&TE requiring routine or scheduled calibration (when required)
- Perform maintenance and calibration using the appropriate procedure and calibration standards
- Identify and take action on nonconforming M&TE

5.0 Procedures

5.1 Determine if Other Related Project-Specific Requirements Apply

For All M&TE:

The PM or designee shall determine if M&TE related project-specific requirements apply. If M&TE related project-specific requirements apply, obtain a copy of them and review and implement as appropriate.

5.2 Obtain the Operating and Maintenance and Calibration Documents

For GF M&TE that is to be procured:

Regulsitioner - Specify that the maintenance and calibration procedures be included.

For GF M&TE that is acquired as a result of a property transfer:

Receiver - Inspect the M&TE to determine whether maintenance and calibration procedures are included with the item. If missing or incomplete, order the appropriate documentation from the manufacturer.

For M&TE that is to be rented or leased from an outside vendor:

Requisitioner - Specify that the maintenance and calibration procedures, the latest calibration record, and the calibration standards certification be included. If this information is not delivered with the M&TE, ask Procurement to request it from the vendor.

5.3 Prepare and Record Maintenance and Calibration Records

For all M&TE:

PM or Designee - Record all maintenance and calibration events in a Field Log unless other project-specific requirements apply.

For GF M&TE only (does not apply to rented or leased M&TE):

If an Equipment Log is a project specific requirement, perform the following:

Receiver - Notify the PM or designee for the overall property control of the equipment of the receipt of an item of M&TE.

PM or Designee - Prepare a sequentially page numbered Equipment Log for the item using the maintenance and calibration form (or equivalent) from the CDM *Property Control Manual* (Figure 1).

PM or Designee and User - Record all maintenance and calibration events in an Equipment Log.

5.4 Label M&TE Requiring Calibration

For GF M&TE only (does not apply to rented or leased M&TE):

If calibration labeling is a project specific requirement, perform the following:

PM or Designee - Read the maintenance and calibration procedures to determine the frequency of calibration required.

PM or Designee - If an M&TE item requires calibration before use, affix a label to the item stating "Calibrate Before Use."

PM or Designee - If an M&TE item requires calibration at other scheduled intervals, e.g., monthly, annually, etc., affix a label listing the date of the last calibration, the date the item is next due for a calibration, the initials of the person who performed the calibration, and a space for the initials of the person who will perform the next calibration.

5.5 Operating, Maintaining or Calibrating an M&TE Item For all M&TE:

PM or Designee and User - Operate, maintain, and calibrate M&TE in accordance with the maintenance and calibration procedures. Record maintenance and calibration actions in the Equipment Log or Field Log.

CDM A subsidiary of Camp Dresser & McKee Inc.			Maintenance and
Date:	Time:	(AM/PM)	
Employee Name: Contract/Project:			Equipment ID No:
			Equipment ID No.:
Activity:			Equipment Serial No.:
Maintenance Performed:			
Comments:			
	 		
ignature:			Date:
			Date:Concentration of Standard:
alibration Standard:			
Calibration Standard: ot No. of Calibration Standard: Pre-Calibration Reading:			Concentration of Standard: Expiration Date of Calibration Standard: Post-Calibration Reading:
Calibration Standard: .ot No. of Calibration Standard: Pre-Calibration Reading: .dditional Readings:			Concentration of Standard: Expiration Date of Calibration Standard: Post-Calibration Reading: Additional Readings:
Calibration Standard: ot No. of Calibration Standard: Pre-Calibration Reading: Additional Readings:			Concentration of Standard: Expiration Date of Calibration Standard: Post-Calibration Reading: Additional Readings: Additional Readings:
Calibration Standard: Lot No. of Calibration Standard: Pre-Calibration Reading: Additional Readings: Additional Readings: Pre-Field Check Reading:			Concentration of Standard: Expiration Date of Calibration Standard: Post-Calibration Reading: Additional Readings:
Calibration Standard: Lot No. of Calibration Standard: Pre-Calibration Reading: Additional Readings: Additional Readings: Pre-Field Check Reading:			Concentration of Standard: Expiration Date of Calibration Standard: Post-Calibration Reading: Additional Readings: Additional Readings:
Calibration Standard: Lot No. of Calibration Standard: Pre-Calibration Reading: Additional Readings: Additional Readings: Pre-Field Check Reading: Adjustment(s):			Concentration of Standard: Expiration Date of Calibration Standard: Post-Calibration Reading: Additional Readings: Additional Readings:
Calibration Standard: Lot No. of Calibration Standard: Pre-Calibration Reading: Additional Readings: Additional Readings: Pre-Field Check Reading:			Concentration of Standard: Expiration Date of Calibration Standard Post-Calibration Reading: Additional Readings: Additional Readings:
Signature: Calibration Standard: Lot No. of Calibration Standard: Pre-Calibration Reading: Additional Readings: Additional Readings: Pre-Field Check Reading: Adjustment(s): Calibration: Passed Comments:			Concentration of Standard: Expiration Date of Calibration Standard: Post-Calibration Reading: Additional Readings: Additional Readings:

5.6 Shipment

For GF M&TE:

Shipper - Inspect the item to ensure that the maintenance and calibration procedures are attached to the shipping case, or included, and that a copy of the most recent Equipment Log entry page (if required) is included with the shipment. If the maintenance and calibration procedures and/or the current Equipment Log page (if required) is missing or incomplete, do not ship the item. Immediately contact the PM or designee and request a replacement.

For M&TE that is rented or leased from an outside vendor:

Shipper - Inspect the item to ensure that the maintenance and calibration procedures and latest calibration and standards certification records are included prior to shipment. If any documentation is missing or incomplete, do not ship the item. Immediately contact Procurement and request that they obtain the documentation from the vendor.

5.7 Records Maintenance

For GF M&TE:

PM or Designee - Create a file upon the initial receipt of an item of M&TE or calibration standard. Organize the files by contract origin and by M&TE item and calibration standard. Store all files in a cabinet, file drawer, or other appropriate storage media at the pertinent warehouse or office location.

PM or Designee - Maintain all original documents in the equipment file except for the packing slip and Field Log.

Receiver - Forward the original packing slip to Procurement and a photocopy to the PM or designee.

PM or Designee - File the photocopy of the packing slip in the M&TE file.

PM or Designee and User - Record all maintenance and calibration in an Equipment Log or Field Log (as appropriate.) File the completed Equipment Logs in the M&TE records, Forward completed Field Logs to the PM for inclusion in the project files.

For M&TE rented or leased from an outside vendor:

Receiver - Forward the packing slip to Procurement.

User - Forward the completed Field Log to the PM for inclusion in the project files.

User - Retain the most current maintenance and calibration record and calibration standards certifications with the M&TE item and forward previous versions to the PM for inclusion in the project files.

5.8 Traceability of Calibration Standards

For all items of M&TE:

PM or Designee and User - When ordering calibration standards, request nationally recognized standards as specified or required. Request commercially available standards when not otherwise specified or required. Or, request standards in accordance with other related project-specific requirements.

PM or Designee and User - Require certifications for standards that clearly state the traceability.

PM or Designee and User - Note standards that are perishable and consume or dispose of them on or before the expiration date.

PM or Designee - Require Material Safety Data Sheet to be provided with standards.

5.9 M&TE That Fails Calibration

For any M&TE item that cannot be calibrated or adjusted to perform accurately:

PM or Designee - Immediately discontinue use and segregate the item from other equipment. Notify the appropriate PM and take appropriate action in accordance with the CDM QP 2.3 for nonconforming items.

PM or Designee - Review the current and previous maintenance and calibration records to determine if the validity of current or previous measurement and test results could have been affected and notify the appropriate PM(s) of the results of the review.

6.0 Restrictions/Limitations

On an item-by-item basis, exemptions from the requirements of this SOP may be granted by the HDQ health and safety manager and/or HDQ quality assurance director. All exemptions shall be documented by the grantor and included in the equipment records as appropriate.

7.0 References

CDM Federal Programs Corporation Property Control Manual. 2002. March.



U.S. ENVIRONMENTAL PROTECTION AGENCY REGION 8

STANDARD OPERATING PROCEDURE (SOP) FOR THE SAMPLING OF ASBESTOS FIBERS IN AIR

Prepared by:	Will Dam for W. Brattin	Date: 3/8/0/
Reviewed by:	(Author)	Date: 3/8/01
zoviowa oy.	(Project Director)	-
	(Quality Assurance Coordinator)	Date: <u>38/01</u>
Approved by:	Offin for Paul Perenard	Date: 3/8/0/
	(Project Manager)	

SOP EPA-LIBBY-01 Revision # 1 Date: March 2001

REVISION LOG

Revision Date	Reason for Revision
02/28/01	щ
03/07/01	Further define pump calibration procedures.

PROCEDURAL SECTION

1.0 Scope and Applicability

This Standard Operating Procedure (SOP) provides a standardized method for sampling air to measure the concentration of asbestos fibers. This SOP is applicable to any type of asbestos fiber (amphibole, chrysotile) that may exist in air (either indoor or outdoor), and is applicable to both personal and ambient air (referred as stationary air throughout this SOP) sampling techniques. Filters collected in this way are suitable for examination by a variety of microscopic techniques, including TEM, PCM, and SEM.

2.0 Summary of Method

This SOP is based on air sampling techniques described in EPA SOP 2015, ISO 10312, OSHA Technical Manual, NIOSH 7400 and NIOSH 7402.

Air is drawn through a fine-pore filter in order to trap any suspended particulate matter in the air, including suspended asbestos fibers and other mineralogic materials. The filters are then examined using an appropriate microscopic technique to observe, characterize and quantify the number of asbestos fibers on the filter. The concentration of fibers in air is then calculated by dividing the total number of fibers on the filter by the volume of air drawn through the filter.

3.0 Health and Safety Warnings

Asbestos fibers are hazardous to human health when inhaled. Exposure to excessive levels may increase the risk of lung cancer, mesothelioma, and asbestosis. All personnel engaged in collection of air samples in areas where asbestos fibers may be present must have adequate health and safety training and must wear an appropriate level of personal protective equipment (PPE). Refer to the Health and Safety Plan for further details.

4.0 Cautions

None, refer to Section 3.0.

5.0 Interferences

High levels of dust or other suspended particulates may clog or overload the filter and reduce the ability to observe and characterize asbestos fibers on the filters. Precautions should be taken to avoid any unnecessary sources of dust emissions or use of aerosol sprays. Sampling conditions

(flow rate, sampling time) should be adjusted accordingly to avoid filter overload.

6.0 Personnel Qualifications

Field personnel engaged in collection of filter cassettes must be trained in the proper use and calibration of the air sampling equipment (as specified in this SOP), as well as proper methods for data recording and sample handling. Additionally, all field personnel must maintain appropriate and current training and/or certifications to meet all federal, state, and local regulations.

7.0 Apparatus and Equipment

Filter Cassettes

All samples will be collected on conductive filter holders consisting of 25-mm diameter, three piece filter cassettes having a 50-mm long electrically conductive extension cowl. The cassette shall be pre-loaded with a mixed cellulose ester (MCE) filter with pore size 0.8 um. Use of the 0.8 um pore size is recommended for all samples so that samples collected using a high volume pump are comparable to samples collected with a low volume pump. The 0.8 um pore size filters are used for samples collected with a low volume pump in order to decrease back-pressure and increase flow rate.

To reduce contamination and to hold the cassette tightly together, seal the crease between the cassette base and the cowl with a shrink band or adhesive tape. If particle deposition on the inside of the cowl is observed, it may be necessary to ground the cowl to reduce static charge. This is done by attaching one end of a length of flexible wire to the plastic cowl with a hose clamp and attaching the other end of the wire to a suitable ground (e.g., a cold water pipe).

Air Pumps

The sampling pump used shall provide a non-fluctuating airflow through the filter and shall maintain the initial flow rate within \pm 10% throughout the sampling period.

A variety of different types of air pump may be used, depending on the flow rates that are required to achieve the data quality objectives and desired analytical sensitivity of the project. In general, the pump should be selected to deliver a flow rate that is as high as possible without overloading the filter with dust or fibers. The minimum flow rate is 0.5 L/min, and rates up to 10 L/min may be appropriate in some cases.

For stationary air monitors, a high volume pump that operates on AC power is recommended. For personal air sampling, either a portable high volume AC powered sampler or a low volume

battery-operated pump are acceptable, depending on whether the activities of the individual are impaired by the tethering imposed by the power cord needed for the high volume pump.

Tripod

For stationary air monitors, a tripod or other similar device is required to hold the filter cassette at a specified elevation above the floor. As noted below, this will typically be a height that represents the breathing zone (1.5-2 meters).

Spring Clips

For personal air monitors, the filter cassette is held in place using spring clips or other similar devices.

Rotameter

A rotameter that has been calibrated to a primary calibration source is required to calibrate the air flow rate at the start and the end of each sampling period. Due to its dependency on changes in atmospheric pressure, the rotameter must be calibrated to a primary calibration source at the site location (e.g., City of Libby) prior to sampling and re-calibrated on-site every week. Record calibration and re-calibration to the primary standard in the field logbook.

Primary Calibration Source

A bubble buret or other primary calibration standard may be used to calibrate the rotameter.

Sample Labels

A pre-printed sheet of sample labels (2 identical labels per sample number) is required. One label should be attached to the filter cassette before the sample collection period begins, and the matching label should be attached to the field data sheet that records relevant data on the sample being collected.

Field Log Book

A field log book is required to record relevant information regarding the collection of samples (location, time, unusual conditions or problems, etc.)

Field Data Sheet

A personal air or stationary air monitoring field data sheet (as appropriate) is required to record the relevant sampling information. Refer to the Phase 2 QAPP (EPA, March 2001) for the form.

8.0 Instrument Calibration

External calibration devices such as a bubble burset or a rotometer that have been calibrated to a primary calibration source may be used to calibrate air flow rate prior to air sampling. The flow rate must also be measured by the same method at the end of the sampling period.

8.1 Calibrating a Rotameter with an Electronic Calibrator (DryCal)

- See manufacturer's manual for operational instructions.
- To set up the calibration train, attach one end of the tygon tubing to the outlet plug of the rotameter; attach the other end of the tubing to the inlet plug on the pump. Another piece of tubing is attached from the inlet plug of the rotameter to the outlet plug on the DryCal.
- Rest or firmly stabilize the rotameter so that it is vertical (± 6°).
- Attach an isolating load with a pressure drop of about 10 to 20 inches of water column in series with a stable pump (a filter cassette of same lot number as will be used for field samples works well for this).
- Turn the DryCal and sampling pump on.
- Turn the flow adjust screw (or knob) on the pump until the desired flow rate is attained.
- Record the DryCal flow rate reading and the corresponding rotameter reading in the field logbook. The rotameter should be able to work within the desired flow range.
- Perform the calibration three times until the desired flow rate of ± 5% is attained. Once at the sampling location, a secondary calibrator (e.g., rotameter) may be used to calibrate sampling pumps.

8.2 Calibrating an Air Pump with a Rotameter

A rotameter can be used provided it has been precalibrated to a primary calibration source at the site location (e.g., City of Libby). Three separate constant flow calibration readings should be obtained both before sampling and after sampling. The mean value of these flow rate measurements shall be used to calculate the total air volume sampled.

Turn on the sampling pump and run for 5 minutes before performing calibration.

- Remove the end plugs on the filter cassette. A cassette, representative of the lot planned for use in air sampling, must be used.
- To set up the calibration train, attach one end of the tygon tubing to the cassette base; attach the other end of the tubing to the inlet plug on the pump. Another piece of tubing is attached from the cassette cap to the rotameter.

- Rest or firmly stabilize the flow meter so that it is vertical $(\pm 6^{\circ})$.
- Turn the flow adjust screw (or knob) on the sampling pump until the center of the float ball on the rotameter meets the flow rate value specified in the project plan.

9.0 Sample Collection

Apply one of the pre-printed adhesive labels to the filter cassette and apply the other to the field data sheet for the sample.

Secure the filter cassette in the appropriate sampling location. For a fixed air monitor, this will generally be at a height that represents the breathing zone of the potentially exposed population (e.g., 1.5-2 meters above the floor). For personal air monitoring, the cassette will typically be placed on the lapel just below the face of the individual being monitored. For personal air sampling for Scenarios 2 and 3 [Refer to Phase 2 QAPP (EPA March 2001)], secure the cassette on the lapel of the dominant hand of the worker. The distance from the nose/mouth of the person to the cassette should be about 10 cm. Secure the cassette on the collar or lapel using spring clips or other similar devices. In all cases, orient the cassette so the open face of the cowel is pointing downward to avoid any particles entering the filter by precipitation. Remove the protective cap over the open face of the cowel and turn on the calibrated pump. Record the starting time, the initial flow rate, and all other relevant sample data on the field data sheet for the sample. Store covers and end plugs in a clean area (e.g., a closed bag or box) during the sampling period.

For sampling events lasting longer than 2 hours, in-field pump checks should be performed approximately every 2 hours. These periodic checks should include the following activities:

- Observe the sampling apparatus (filter cassette, pump, tripod, etc.) to determine whether it's been disturbed.
- Check the pump to ensure it is working properly and the flow rate is stable at the prescribed flow rate.
- Inspect the filter for overloading and particle deposition. Inspect the filter using a small flashlight. Look for particle adhesion or deposition on the side of the cassette and check the filter surface for accumulation of visible dust or smoke particles. If particle deposition on the inside of the cowl is observed, it may be necessary to ground the cowl to reduce static charge.

After the specified sampling period has elapsed, measure the ending flow rate and ending clock time on the data sheet. Turn off the pump and remove the cassette from the pump. Attach and secure a sample seal around each sample cassette in such a way as to assure that the end cap and

base plug cannot be removed without destroying the seal. Tape the ends of the seal together since the seal is not long enough to be wrapped end-to-end. Initial and date the seal.

10. Sample Handling and Preservation

Package the cassettes so they will not rattle during shipment nor be exposed to static electricity. Place custody seals, dated and marked with the packager's signature, onto the shipping container. Do not ship samples in polystyrene peanuts, vermiculite, paper shreds, or excelsior. Tape sample cassettes to sheet bubbles and place in a container that will cushion the samples in such a manner that they will not rattle. For additional shipping requirements, see the project plan.

Ship the sealed cassette to the analytical laboratory under proper chain of custody procedures. No preservation of the cassette is required.

QUALITY CONTROL and QUALITY ASSURANCE

Pre-Project Filter ("Lot") Blanks

Before samples are collected, two cassettes from each filter lot of 100 cassettes should be randomly selected and submitted for analysis. The lot blanks will be analyzed for asbestos fibers by the same method as will be used for field samples. The entire batch of cassettes should be rejected if any asbestos fiber is detected on any filter.

Field Blanks

Blank samples are used to determine if any contamination has occurred during sample handling. Prepare two blanks (from the sample lot used for field sampling) for the first 1 to 20 samples. For sets containing greater than 20 samples, prepare blanks as 10% of the samples. Filter blanks should be taken to a sampling location and prepared there. Remove the caps on the filter cassette and hold the cassette open for about 30 seconds. Close and seal the cassette as described in Section 9. Store blanks for shipment with the sample cassettes.

SOP EPA-LIBBY-01 Revision # 1 Date: March 2001

REFERENCES

NIOSH 7400

NIOSH 7402

ISO 10312

OSHA Technical Manual

EPA SOP 2015

Site-Specific Sampling Guidance Libby Superfund Site

Guidance No.: CDM-LIBBY-05, Revision 2

Guidance Title: Soil Sample Collection at Residential and Commercial Properties

Approved by:		71	
	- Jongs Sed		5/10/07
•	Technical Reviewer		Date
	Sechonell		5/10/02
	QA Reviewer		Date
	Mal C;	<i>l</i>	05/10/07
	Volpe Center Approval	4	/ / Date
	MIA		5/10/07
	ERA Approval		Date

Section 1

Purpose

The goal of this standard operating procedure (SOP) is to provide a consistent method for the collection of 30-point composite surface soil sampling to support all investigations conducted at the Libby Superfund Site and specified in governing guidance documents. This SOP describes the equipment and operations used for sampling surface soils in residential and commercial areas, which will be submitted for the analysis of Libby amphibole asbestos. Refer to each investigation-specific guidance documents or work plan for detailed modifications to this SOP, where applicable. The EPA Team Leader or their designate must approve deviations from the procedures outlined in this document prior to initiation of the sampling activity.

Section 2

Responsibilities

Successful execution of this SOP requires a clear hierarchy of assigned roles with different sets of responsibilities associated with each role. All staff with responsibility for the collection of soil samples is responsible for understanding and implementing the requirements contained herein as well as any other governing guidance documents.

Task Leader (TL) or Field Team Leader (FTL) - The TL or FTL is responsible for overseeing sample collection processes as described in EPA approved governing guidance documents (i.e., site-specific sampling and analysis plans [SAPs], quality assurance project plans [QAPPs], etc.). The TL or FTL is also responsible for checking all work performed and verifying that the work satisfies the specific tasks outlined by this SOP and all governing guidance documents. The TL or FTL will communicate with the field team members regarding the specific collection objectives and anticipated situations that require deviation from this SOP. It is also the responsibility of the TL or FTL to communicate the need for any deviations from the SOP with the appropriate EPA personnel (team leader or their designate), and document the deviations using a Field Modification Form provided in each SAP or QAPP.

<u>Field team members</u> - Field team members performing the sampling described in this SOP are responsible for adhering to the applicable tasks outlined in this procedure while collecting samples at properties associated with the Libby Superfund Site. The field team members should have limited discretion with regard to collection procedures but should exercise judgment regarding the exact location of sample points, within the boundaries outlined by the TL or FTL.



Section 3 Equipment

- Measuring tape or wheel Used to estimate the square footage of each land use area.
- Pin flags Used to identify composite points within each sampling area.
- <u>Trowel or push probe</u> For collecting surface soil samples.
- Shovel For collecting surface soil samples.
- Stainless steel mixing bowl Used to mix and homogenize composite soil samples
 after collection. Zip-top bags may also be used for homogenization if approved
 by the governing guidance documents.
- Gloves For personal protection and to prevent cross-contamination of samples (disposable, powderless plastic or latex).
- Sample container Gallon-sized zip-top plastic bags (2 per sample).
- <u>Field clothing and personal protective equipment (PPE)</u> As specified in the current version of the site health and safety plan (HASP).
- <u>Field sprayers</u> Used to suppress dust during sample collection and to decontaminate nondisposable sampling equipment between samples.
- <u>Deionized (DI) water</u>- Used in field sprayers to suppress dust and to clean and decontaminate sampling equipment.
- <u>Plastic bristle brush</u> Used to clean and decontaminate sampling equipment.
- Wipes Disposable, paper. Used to clean and decontaminate sampling equipment.
- Aluminum foil Used to wrap decontaminated sampling equipment in between uses to prevent contamination during transport.
- Alconox Used to clean and decontaminate sampling equipment weekly.
- 6-mil poly bag Used to store and dispose of investigation-derived waste (IDW).
- Trash bag Used to store and dispose of general trash.
- <u>Field logbook/PDA</u> Used to record progress of sampling effort and record any problems and field observations.



- <u>Visual Vermiculite Estimation Form (VVEF)</u> Used to record semi-quantitative estimates of visual vermiculite at each sub-sample location and point inspection (PI).
- Permanent marking pen Used to label sample containers.
- Sample ID Labels (Index IDs) Pre-printed stickers used to label sample containers.
- Cooler or other rigid container Used to store samples while in the field.
- <u>Custody Seals</u> For ensuring integrity of samples while in the field and during shipping.

Section 4

Sampling Approach

Upon arrival at each property, the field team will locate all parcels requiring sample collection depending on the investigation-specific objectives detailed in governing guidance documents. Parcels on a property will be sectioned into zones that share a similar land use. Zones established by land use areas may be subdivided based on site conditions (e.g., access, construction setup considerations, etc.). Use areas include:

- Specific Use Area (SUA): flowerbed, garden, flowerpot, stockpile, play area, dog pen, driveway (non-paved), parking lot (non-paved), road (non-paved), alley (non-paved)
- Common Use Area (CUA): yard, former garden, former flowerbed, walkway
- <u>Limited Use Area (LUA)</u>: pasture, maintained/mowed field, overgrown areas with trails/footpaths, overgrown areas in between SUAs/CUAs
- Interior Surface Area (ISA): soil floor of garage, pumphouse, shed, crawlspace, earthen basement
- Non-Use Areas(NUA): wooded lot, un-maintained field. NUAs will be identified but will not be sampled at this time because they are not presently considered a complete exposure pathway. However, to the extent that NUAs may become a complete exposure pathway in the future, EPA may revisit NUAs at a later date.

After areas have been designated as zones (i.e., SUA zones, CUA zones, LUA zones, NUA zones, ISA zones), the field team will measure the zones with a measuring wheel and label the zone type and approximate square footage on the field sketch and/or design drawings. There is not a minimum or maximum square footage restriction on any zone.

In establishing zones at the property, no area type may be combined with any other area type. For example, driveways and flowerbeds are both SUAs but will be



separated into unique zones for soil sampling. Similarly, large CUAs such as yards may be subdivided into front yard, side yard, and back yard zones dependent on site conditions. Sectioning properties into additional zones will be at the discretion of the FTL but consistent among the teams. Conversely, not all land use areas previously mentioned will be applicable at every property.

It is anticipated that SUAs and ISA zones will generally tend to be smaller parcels. Combining small, proximal SUAs into one zone will be at the discretion of the FTL but consistent among teams. With the exception of proximal SUAs, all other land use areas will be contiguous when establishing zones at each property.

Composite sampling requires soil collection from multiple (sub-sample) points. Composite samples will be collected from similar land use areas (i.e., SUA, CUA, etc.) and will not be combined with any other use area. One composite sample will be collected from each zone that does not contain visual vermiculite.

For SUAs (e.g., driveway, garden, dog pen, etc.), composite samples will be collected from the 0- to 6-inch depth interval. If a depth of 6 in. cannot be attained given the varying levels of compaction in driveways, roads, etc. the maximum depth attainable will be documented in the field logbook/PDA. For non-SUAs (e.g., yard, former flowerbed, crawlspace, etc.), composite samples will be collected from 0 to 3 inches. All composite soil samples will have 30 sub-samples (i.e., 30-point composite sample) of approximately equal size for a final sample volume between 2,000 and 2,500 grams. Table 1 lists the sample depth for each type of land use area.

Table 1 Sampling Area and Depth			
Land Use Area	Label	Sampling Depth (Inches)	
Special Use Area	SUA	0-6	
Common Use Areas	CUA	0-3	
Limited Use Area	LUA	0-3	
Non-Use Area	NUA	Not Sampled	
Interior Surface Zone	IS	0-3	

As each sub-sample is collected, the soil will be inspected for visual vermiculite (VV) and the location and semi-quantitative estimates of VV will be recorded as prescribed in the SOP for Semi-Quantitative Visual Estimation of Vermiculite in Soil, Revision 1 (CDM 2007a).

Areas of SUAs with VV will not be sampled. Instead, the location will be recorded in the field logbook/PDA and on the field sketch or design drawing. If the SUA is of substantial size (greater than 1000 square feet [ft²]), and the VV is localized, additional PIs will be collected to determine the extent of VV and a sample will be collected from the remainder of the zone that does not contain VV. If the SUA measures less than 1,000 ft² and VV is present, a sample will not be collected from that SUA. Proximal



SUAs will not be combined into a SUA zone if VV is present. If visible vermiculite is not observed, proceed with sample collection of the SUA zone

Section 5 Sample Collection

Don the appropriate PPE as specified in the governing HASP. A new pair of disposable gloves is to be worn for each sample collected. Segregate land use areas on the property into zones as described in Section 4. To reduce dust generation during sampling, use a sprayer with DI water to wet each sub-sample location prior to collection. Use the trowel to check beneath the surface soil layer, but do not advance more than 6 inches. If VV is observed, record the information on the field sketch or design drawing. If VV is observed within a large SUA, do not collect a sample from the area containing VV as described above.

Within each zone, select 30 sub-sample locations equidistant from each other. These 30 sub-sample locations will comprise the 30-point composite sample for that zone. All composite sub-samples will originate from the same land use area. For example, do not mix sub-samples from SUAs with sub-samples from LUAs.

Clean the sub-sample locations of twigs, leaves, and other vegetative material that can be easily removed by hand. Using the trowel or push probe, excavate a hole in the soil approximately 2 inches in diameter and 6 inches deep for SUAs, or 3 inches deep for non-SUAs, while placing the excavated material directly inside the gallon-sized zip-top plastic bag. Repeat this step for each subsequent sub-sample until the appropriate number of composite sub-samples has been collected. As each subsample is collected, inspect the location for VV as prescribed in the SOP for Semi-Quantitative Visual Estimation of Vermiculite in Soil, Revision 1 (CDM 2007a).

Samples collected from zones measuring greater than 3,000 ft² will require additional PIs to inspect the soil for VV, but no more than 30 sub-samples will be collected from a zone for each composite sample. Samples collected from zones measuring less than 3,000 ft² will have the same number of sub-samples as PIs unless additional PIs are required to identify the extent of localized VV.

Homogenize the sample as required by governing guidance documents. Once the sample is homogenized, fill the zip-top plastic bag to 1/3rd full (approximately 2000 grams). Affix the sample index ID label to the inside of the bag and write the index ID number on the outside of the bag, or affix an additional label using clear packing tape. Sample index ID numbers will be assigned based on the investigation-specific guidance document. Double bag the sample and repeat the labeling process for the outer bag. Decontaminate equipment between composite samples as described in Section 8.

Repeat steps outlined above until all samples from a property have been collected.



Soil field duplicate samples will be collected at the rate specified in governing guidance documents. Field duplicate samples will be collected as samples co-located in the same zone. The duplicate will be collected from the same number of subsamples as the parent sample, but the sub-sample locations of the duplicate sample will be randomly located in the zone. The inspection for VV at each sub-sample location will follow the same protocol as referenced above. These samples will be independently collected with separate sampling equipment or with the original sampling equipment after it has been properly decontaminated. For tracking purposes, the parent/duplicate sample relationship will be recorded in accordance with sample documentation requirements stated in the governing guidance document. These samples will be used to determine the variability of sample results in a given land use area. These samples will not be used to determine variability in sampling techniques.

Section 6 Site Cleanup

IDW will be managed as prescribed in Section 3.2.10 of the Site-wide QAPP [SWQAPP] (CDM 2007b) or other applicable governing guidance documents. In general, replace the soil plug with excess sample volume. The soil should be placed back into the hole and tamped down lightly. If sandy areas such as playgrounds are sampled, refilling the soil plug is not necessary.

Rinse water, the roots of vegetation removed during sampling, and any excess soil volume may be returned to the sampled area.

Section 7

Documentation

A field logbook/PDA will be maintained by each individual or team that is collecting samples as prescribed in Section 3.2.4 of the SWQAPP (CDM 2007b) or other applicable governing guidance documents. Guidance documents will detail conditions which require attention, but at a minimum the following information should be collected:

- Project name
- Title of governing documents
- Property address
- Date
- Time
- Team members



- Weather conditions
- PPE used
- Locations of any samples or sub-samples that could not be acquired
- Descriptions of any deviations to the SAP or SOP and the reason for the deviation
- Relinquishment of samples to project sample coordinator

Complete required documentation as detailed in applicable governing guidance documents.

Section 8

Quality Assurance/Quality Control

Quality control samples will include:

Field duplicates

Detailed information on QC sample collection and frequency is prescribed in Section 3.1.3.2 of the SWQAPP (CDM 2007b) or other applicable governing guidance documents.

Section 8

Decontamination

All sampling equipment must be decontaminated prior to reuse. Specific instructions on sample equipment decontamination are included in the applicable governing guidance documents. In general, the procedure to decontaminate all soil sampling equipment is outlined below:

- Remove all visible contamination with plastic brush
- Use DI water and plastic brush to wash each piece of equipment
- Remove excess water present on the equipment by shaking
- Use a paper towel to dry each piece of equipment
- Wrap dried equipment in aluminum foil

Once a week all soil sampling equipment will be cleaning using Alconox and DI water.

Spent wipes, gloves, aluminum foil, and PPE must be disposed of or stored properly as IDW, specified in Section 3.2.10 of the SWQAPP (CDM 2007b) or other applicable governing guidance documents.



Section 9

Sample Custody

Field sample custody and documentation will follow the requirements described in Section 3.2.11 of the SWQAPP (CDM 2007b) or other applicable governing guidance documents.

Section 10

Glossary

Governing guidance documents - The written document that spells out the detailed site-specific procedures to be followed by the project leader and the field personnel for completing specific investigations. These documents will clearly indicate specific requirements for the implementation of this SOP.

<u>Libby Superfund Site</u> - The Libby Superfund Site contains all buildings and land within the boundaries of each operable unit (OU) of the site and illustrated on the most recent version of the OU boundary map.

<u>Sub-sample</u> - The actual location at which the sample is taken. The dimension of a sample point is 2 inches across by 3 inches deep (6 inches for SUAs).

<u>Composite Sampling</u> - A sample program in which multiple sample points are compiled together and submitted for analysis as a single sample.

<u>Land Use Area</u> - A section of property segregated by how the property owner uses the area. The area can be classified as a SUA, LUA, CUA, ISA, or NUA.

Section 11 References

CDM. 2007a. Semi-Quantitative Visual Estimation of Vermiculite in Soils at Residential and Commercial Properties, Revision 1. CDM-LIBBY-06.

CDM. 2007b. Site-Wide Quality Assurance Project Plan. Draft in review.



Site-Specific Sampling Guidance Libby Superfund Site

SOP No.: CDM-LIBBY-06, Revision 1

SOP Title: Ser and Commerc	ni-Quantitative Visu ial Properties	al Estimation of	Vermiculite in S	Soils at Residential
Approved by:	C James 1			5/0/07
	Technical Reviewer	19.0		Date
	Lahomes	<u>A</u>		5/10/07
	QA Reviewer		7	Date
	Mu	5/1/		05/10/07
	Volpe Center Appro	val		/ / Date
				5/10/07
	EPA/Approval			Date

Section 1

Purpose

EPA will identify and delineate the extent of any visible vermiculite (VV) present in soils as part of all investigations conducted at the Libby Superfund Site and specified in governing guidance documents. The goal of this standard operating procedure (SOP) is to provide a consistent approach to identify and characterize any VV present in soils.

The semi-quantitative approach presented in this SOP for visually estimating VV in soil will be revised as required to optimize data collection as the sampling teams gain experience. This will be accomplished by expanding and/or improving this SOP, supporting pictorial standards, and additional electronic data acquisition efforts, as necessary.

Section 2 Definitions

Specific Use Area (SUA) - Discrete exterior parcels on a property with a designated specific use. Due to the nature of activities typically carried out in SUAs, residents may be especially vulnerable to exposures when Libby amphibole asbestos (LA) contaminated soil becomes airborne. SUAs may be bare or covered with varying amounts of vegetation. SUAs include:

- Flower Pot
- Flowerbed
- Garden
- Stockpile
- Play Area
- Dog Pen
- Driveway (non-paved)
- Parking Lot (non-paved)
- Road (non-paved)
- Alley (non-paved)

<u>Common Use Area (CUA)</u> - Exterior parcels on a property with varied or generic use. CUAs may be bare or covered with varying amounts of vegetation. CUAs include:

- Walkway
- Yard (front, back, side, etc.)
- Former Garden
- Former Flowerbed



<u>Limited Use Area (LUA)</u> – Exterior parcels on a property that are accessed, utilized, and maintained on a very limited basis. LUAs may be bare or covered with varying amounts of vegetation. LUAs include:

- Pasture
- Maintained/Mowed Fields
- Underneath porches/decks¹
- Overgrown Areas (with trails/footpaths, or between SUAs/CUAs)

<u>Interior Surface Area (ISA)</u> – Interior soil surfaces of buildings such as garages, pumphouses, sheds, and crawlspaces.

<u>Non-Use Area (NUA)</u> - Exterior parcels on a property with no current use (e.g., areas that are un-maintained and not accessed). NUAs may be bare or covered with varying amounts of vegetation. NUAs include:

- Wooded Lots
- Un-maintained Fields

Since NUAs are not currently accessed, they are not presently considered a complete exposure pathway. As such, semi-quantitative visual estimates of vermiculite in soil will not be captured at this time. However, to the extent that NUAs may become a complete exposure pathway in the future, EPA may revisit these NUAs at a later date.

Zone² – Parcels on a property that share a similar land use or subdivisions of a land use area based on site conditions (e.g., access, construction setup considerations, etc.) or sampling requirements. No area type may be combined with any other area type. For example, driveways and flowerbeds are both SUAs but will be separated into unique zones for visual inspection. Similarly, large CUAs such as yards may be subdivided into front yard, side yard, and back yard zones dependent on site conditions. Sectioning properties into additional zones will be at the discretion of the field team leader but consistent among the teams.

It is anticipated that SUAs and ISA zones will generally tend to be smaller parcels. Combining small, proximal SUAs into one zone will be at the discretion of the field team leader but consistent among teams. No ISA will be combined with any other ISA for visual inspection. There is not a maximum square footage restriction on any zone.

¹ The soils underneath porches and decks will be classified as LUAs depending on ground clearance and accessibility to homeowners and pets. If these areas are not accessible, they will be classified as NUAs.

² The restriction on the maximum square footage of SUA zones (1,000 ft2) and non-SUA zones (2,500 ft2) was eliminated from the previous iteration of this SOP after the data were reviewed by EPA and determined to sufficiently characterize the presence of VV regardless of zone square footage. Additionally, this will allow the flexibility necessary for field teams to identify areas of zones most cost effectively for removal purposes.



<u>Point Inspection (PI)</u> – Used in SUA, CUA, LUA, and ISA zones. A PI is an intrusive visual inspection of the top portions of the soil at a randomly selected point within a zone. A PI consists of the active displacement of the surface soil with a small shovel and visual inspection of the displaced soil to determine if VV is present. If VV is observed during the PI, the location and a semi-quantitative estimate of VV contamination will be recorded.

Section 3 Applicability

This SOP applies to properties within the Libby Superfund Site at varying stages of the removal process including, but not limited to, all screening and risk-based investigations, pre-design inspections, and removal actions. Investigation-specific modifications to this SOP are outlined in the governing guidance document for each investigation. The following locations on a property will be evaluated for the presence/absence of VV:

- All parcels on a property where soil samples are being collected.
- All parcels on a property where soil was non-detect for LA during previous sampling activities.
- All SUA parcels on a property that have not been previously characterized as containing VV

Section 4

Procedure

Figure 1 illustrates the procedures and decision rules for this SOP. The three primary procedural steps are listed below:

- Establish zones
- Perform PI
- Perform semi-quantification of visual vermiculite

Each is described in the following subsections.

4.1 Establish Zones

Upon arrival at the property, the field team will locate all areas requiring sample collection (i.e., where previous soil sample results were non-detect for LA or SUAs have not been previously characterized for VV). Parcels will be identified as SUA zones, CUA zones, LUA zones, NUA zones, or ISA zones. The field team will measure the zone sizes and note them on the field sketch and/or design drawings. Zones will be assigned according to the definitions provided above.



4.2 Point Inspections³

As defined above, a PI is an intrusive visual inspection performed for the entire surface of a zone. Professional judgment may be used to determine the exact location of PIs; however, the following guidelines will be implemented to maintain consistency.

A minimum of 30 PIs will be evaluated per zone if sampling is required within that zone. If soil sampling is not required, a minimum of 5 PIs will be evaluated within each zone. Zones larger than 500 square feet (ft²) will require evaluation at a minimum of 1 PI per 100 ft² (10 ft by 10 ft area). The PI locations will be randomly selected and will be spatially representative of the entire zone. Locations of the PIs and semi-quantitative estimates of VV (i.e., low, intermediate, or high) will be recorded on the field sketch for each PI. While a minimum of 5 PIs will be conducted per zone, there is no set maximum. Rather, the maximum number of PIs is variable—dependent upon the total area of the zone and achieving the minimum required frequency of 1 PI per 100 ft².

The following sections outline procedures for inspecting each use area (e.g., SUA, CUA, LUA, ISA). The procedure for semi-quantification of VV is provided in the next section.

SUA Zone:

- Visually inspect the PI point using a spade or trowel to remove any cover material, including excess debris (e.g., mulch, rock, etc.) and organic material, from the surface of the soil. Remove and visually inspect soil to a depth of 0-6 inches below ground surface⁴.
- If a depth of 6 in. cannot be attained given the varying levels of compaction in driveways, roads, etc. the maximum depth attainable will be documented in the field logbook.
- Record semi-quantitative estimate of VV observed as described in the following section.
- Replace soil and cover material.
- Repeat as necessary employing procedure outlined above.

CUA and LUA Zones:

Visually inspect the PI point using a spade or trowel, carefully removing organic material, including grass, from the surface of the soil. Remove and visually inspect soil to a depth of 0 - 3 inches below ground surface⁵.

³ Surface Inspections- The non-intrusive visual inspection of the immediate surface of a zone was eliminated from the previous iteration of this SOP after their data were reviewed and determined by EPA to provide no additional information over that gained through Point Inspections.

⁴ A solid death of Circles 6. 2011

⁴ A soil depth of 6 inches for SUAs was chosen to approximate the depths to which digging would be expected during typical activities occurring in these SUA zones (e.g., gardening, child digging in dirt, etc.)
⁵ A soil depth of 0-3 inches was chosen to approximate the depths to which soil disturbance would be most likely during typical activities occurring in these CUA and LUA zones (e.g., lawn mowing, etc.)

- Record semi-quantitative estimate of VV observed as described in the following section.
- Carefully replace all soil and organic material.
- Repeat as necessary employing procedure outlined above.

ISA Zone:

- Move items as necessary to access the soil surface.
- Visually inspect the PI points using a spade or trowel, remove and visually inspect soil to a depth of 0 - 3 inches below ground surface⁶.
- Record semi-quantitative estimate of VV observed as described in the following section.
- Repeat as necessary employing procedure outlined above.

If during the PI, VV is observed to be localized within a zone, the portion with vermiculite will be denoted on the field sketch. If additional PIs are necessary to determine the boundaries of the area, approximately 10 to 20% additional PIs will be evaluated to determine the extent of localized vermiculite.

4.3 Semi-Quantification of Visual Vermiculite

During PI, the field team will estimate the quantity of vermiculite observed. Each PI location for all zones will be assigned a semi-quantitative estimate of visible vermiculite content using a 4-point scale: none (blank), low (L), intermediate (M), and high (H)⁷. For PI locations where VV is observed, semi-quantitative estimates (e.g., L, M, or H) will be recorded on the field sketch. PI locations where VV is not observed will not be recorded on the field sketch. Photographs illustrating these quantities are attached to this SOP as Figure 2. Additionally, jars of vermiculite-containing soils representing these three levels will be available for training and reference.

Under the current version of this SOP, there will be no effort to design an approach to combine vermiculite levels for PIs within or among zones. While the viability of combining semi-quantitative visual estimates within or among zones may be assessed as a pilot-scale evaluation, any PI with visible vermiculite qualifies as vermiculite-containing soil for the area represented by the inspection point or inspection zone.

⁷ Based on EPA's review of previous data, the 5-level scale VV identification scheme was not meaningful and will be reduced to a 4-level scale. As such the quantity of "Gross" VV in the previous iteration of this SOP was combined with High. Previously collected data of Gross VV should be considered analogous to High VV under this revised SOP.



⁶ A soil depth of 0-3 inches was chosen to approximate the depths to which soil disturbance would be most likely during typical activities occurring in these IS zones (e.g., entering crawlspace, retrieving items from shed, etc.)

Section 5

Health & Safety/Engineering Controls

All personnel will carry out visual inspections in accord with proper personal protective equipment (PPE) and other monitoring/governing requirements outlined in the most recent version of the Site Health and Safety Plan governing the work being conducted.

All visual inspections will employ appropriate engineering controls to minimize dust (e.g., wetting soil during inspection) as prescribed in the Site-Specific Standard Operating Procedure for Soil Sample Collection (CDM-LIBBY-05, Revision 2).

Section 6

Equipment Decontamination

Equipment decontamination is not required between each PI from the same zone, but is required before moving to another inspection zone. Decontamination of equipment will be conducted as required by the governing guidance documents.

Section 7

Documentation

As noted above, information about the presence of vermiculite will be recorded on the field sketch or design drawing for the property under investigation. Each zone will be marked with:

- Zone type (i.e., SUA, CUA, LUA, NUA, or ISA)
- Zone area in ft²
- PI locations/points
- Semi-quantitative estimate of VV content for each PI (i.e., L, M, H)

In addition to field sketch/design drawing documentation, each field team will generate a Visual Vermiculite Estimation Form (VVEF) (Figure 3) to document the semi-quantitative visual estimates of VV for each PI for possible future information use. This form will be managed according to governing guidance documents.

Section 8 Training

Every effort will be made to ensure consistency in the semi-quantitative evaluation of VV in soil to the extent possible. This will include training (e.g., field calibration), specimen examples (i.e., jars/photographs of low, intermediate, and high quantities of vermiculite, etc.), designated field staff, and oversight by the field team leader. Figures illustrating none, low, intermediate, and high quantities of vermiculite are attached to this SOP for reference (Figure 2).

CDM

CDM-LIBBY-06 Visual Estimation of Vermiculite in Soil Revision 1

To ensure consistency over time, the field team leader will verify semi-quantitative assignments at a rate of one property per team per week. The field team leader will sign off on those field sketches that were verified. If inconsistencies are noted, the field team leader will hold re-training with all teams participating simultaneously. Updates to the SOP and its attached specimen examples will occur as necessary and the EPA Project Team Leader and Technical Assistance Unit will be notified when these updates are recommended by the field team leader or field investigation manager.



Figure 1 – Visible Vermiculite Inspection Process






Figure 2a: Low Visible Vermiculite – A maximum of a few flakes of vermiculite observed within a given visual inspection point



Figure 2b: Intermediate Visible Vermiculite – Vermiculite easily observed throughout visual inspection point, including the surface.



Figure 2c: Intermediate Visible Vermiculite – Vermiculite easily observed throughout visual inspection point, including the surface.



Figure 2d: High Visible Vermiculite – Vermiculite easily observed throughout visual inspection point, including the surface.

LIBBY SUPERFUND SITE Visual Vermiculite Estimation Form (VVEF)

				TISUAL TOTALISE	into Estimation i oini	(VVEF)			
Field Logbook No.: Page N			Page No.:		Site Visit Date:		BD Number:		
Address:			•		Structure Description:	Property	•		
	Occupant:				Phone No.:			_	
	Owner (I	f different than occupant):			Phone No.:				
		Investigation Team:			Investigation Name:	al Verification by Field Tea			
Field	Form Check Compl	leted by (100% of Forms):			Visua	al Verification by Field Tea	m Leader (10% of forms):		
							· · · · · · · · · · · · · · · · · · ·		
		Zone 1	Zone 2	Zone 3	Zone 4	Zone 5	Zone 6	Zone 7	Zone 8
	/pe IA/LUA/IS)								
Desci	ription								
	size re feet)								
	Comment er, etc.)								
, H=High)	x								
PIs =Intermediate	L								
PIs (X=None, L=Low, M=Intermediate, H=High)	ev.								
(X=None,	н								
Total 0 0 0		0	0	0	0	0	0		
Areas previously	identified for remo	val not inspected for vis	ble vermiculite?	-	Yes No NA	Location(s):			

Page 1 of :

Project-Specific Standard Operating Procedure Libby Asbestos Project

SOP No.: CDM-LIBBY-09, Revision 0

SOP Title: Global Positioning Satellite (GPS) Coordinate Collection and Handling

Project: Libby Asbestos Project

Project No.: 2616

Client U.S. Department of Transportation (DOT)/Volpe Center

Authored by:

Date: 5-21-07
Diane Rode

Approved by:

Themas E. Cook
CDM Technical Reviewer

CDM Libby IMS Support

Date: 3/21/07

Terry Crowell

CDM Quality Assurance Reviewer

1.0 Objective

The objective of this standard operating procedure (SOP) is to provide a standardized approach for the collection and handling of GPS data at the Libby Asbestos Site (Site).

2.0 Background

2.1 Definitions

Libby_Sampling Data Dictionary - All Trimble handheld units used at the Site are preprogrammed with the Libby _Sampling data dictionary, specific to the spatial data collection needs for the Libby Asbestos Project. All personnel required to collect GPS data will be familiar with the contents of the Libby_Sampling data dictionary, which contains the following features: Soil Sample, Air Sample, Dustfall (Settled Dust) Sample, Water/Sediment Sample, Building Location, Interest Point, Sample Area, and Interest Area. The Trimble units also are loaded with a generic data dictionary that handles collection of generic lines, points and areas.

2.2 Discussion

The following attributes are required to be collected as indicated in Table 1 for each feature type when a GPS coordinate is collected:

Table 1 – Attributes Collected in the Libby_Sampling Data Dictionary		
Feature Name	Attributes Collected	
Building Location	LocationID, Address, Comments	
Soil Sample	LocationID, IndexID, Sample_Type, SamplGroup, Upper_Depth, Lower_Depth, Comment	
Air and Dustfall Samples	LocationID, IndexID, Sample_Type, SamplGroup , Comment	
Water/Sediment Sample	LocationID, IndexID, Matrix_Type, Comment	
Interest Point	Location, Land_Use, Comment	
Interest Area	Location, Land_Use, Comment	
Sample Area	LocationID, IndexID, Num_of _Composites, Upper_Depth, Lower_Depth, Comment	

These attributes are discussed in detail in Section 4 of this document.

3.0 Responsibilities

GPS data is collected by investigation, pre-design, and removal oversight staff as specified in the sampling and analysis plans specific to those programs. Transfer of GPS data from the field

equipment to the onsite server, as well as initial data review, processing, and transmittal of data off-site will be performed by a designated on-site IMS staff member during peak field season (April through November), and by administrative support staff during the off season. These additional procedures are documented separately and are posted on CDM's e-room at: https://team.cdm.com/eRoom/R8-RAC/Libby/0_290a.

4.0 Procedures

The following sections describe how GPS points are collected and handled for features commonly used at the Site.

4.1 GPS Point Collection

Building Locations

For building locations, a GPS point is collected near the front door or main entrance of the building. Location IDs beginning with the prefix "BD" (indicating a building point), are used for such locations.

Soil Samples

For **Grab** samples, a GPS point is collected directly above the location where each sample is collected. Location IDs beginning with the prefix "SP" (indicating a sample point), are used for such locations.

For Composite samples, a GPS point is collected at the approximate center of each sample area. In the case of an irregular-shaped sample area or sample area that is non-continuous (e.g., a flowerbed that wraps around a house), a GPS point is collected at the center of the largest continuous sample area. Location IDs beginning with the prefix "SP" are used for such locations.

Outdoor Stationary Air and Dustfall (Settled Dust) Samples

For permanent (i.e., samples represent a consistent monitoring zone or area and are collected on a routine schedule) outdoor stationary air and dustfall sample locations, a GPS point is collected at each unique sample location. All subsequent samples taken at that location will be assigned the same Location ID and X,Y coordinates. The GPS point is only collected once. Location IDs beginning with the prefix "SP" (indicating a sample point), are used for such locations.

GPS points are not collected for the following features:

- Stationary air, dust, and soil samples collected inside or beneath structures (locations are associated with the X,Y coordinate of the building where the sample was collected)
- Stationary air samples, with the exception of permanent monitoring locations as designated in site-specific removal work plans or Response Action Work Plan Addenda
- Duplicate or Replicate air or dust samples (assigned the same location ID as the parent sample)
- Soil samples taken at depth from the same X,Y location as a previously collected sample. The atdepth soil sample will be assigned the same Location ID as the shallower sample in order to relate both samples to the same X,Y coordinate.
- Duplicate or split soil samples (assigned the same location ID as the parent sample)
- Personal air samples (locations are associated with the X,Y coordinate of the building or property where the sample was collected)

Interest Point, Interest Area, Sample Area

GPS points for these features are not routinely collected on the Libby Asbestos Project. However, they are included in the Libby_Sampling data dictionary in the event that a GPS point is collected for an area where no sampling is involved, or a series of points is collected to document the perimeter of an interest area or sample area.

4.2 Operation of Trimble Pro XRS and GeoXT Handheld Units:

Operators must be standing at the sample location *before* the unit starts to collect positions. Once the unit has started collecting positions, the operator must remain standing at the sample location until the minimum required positions have been collected. A minimum of 30 positions will be collected for each GPS location. More positions will be required in circumstances where the position dilution of precision (PDOP) is greater than the default setting of 4.5. Plan GPS collection around satellite availability & times when PDOP is < 4.5.

Record-keeping Requirements:

Serial numbers of the Trimble datalogger, receiver, and antenna will be recorded in a field logbook. GPS filenames will be recorded in the logbook and on field sample data sheets (FSDSs).

Data Collection Instructions for Trimble Pro XRS:

Turn on the unit and select *Data Collection* from the main menu. You will be prompted to create a new file, open an existing file, or create a base file. Choose *create new file* and press Enter. There will be a generic default file name that begins with "RO..." followed by the date. Create a new file name using the following naming convention: **T1A10204**, where **T1** refers to the specific Trimble unit you are using, **A** refers to the first file of the day (**B** would be the second file of the day, and so on), and **10204** refers to October 20, 2004. You are limited to only 8 characters so the date notation will be MMDDY. The setting for data dictionary should always be set to Libby_Sampling. Press Enter to bring up the Start Feature menu.

From the Start Feature menu you will select the type of location data that you want to collect. Press the F1 key to pause the unit until you are ready to start collecting data. Highlight the appropriate data type and press Enter. (Note, if you do not have the unit paused it will start collecting data as soon as you press Enter.) Using the alphanumeric keypad and the directional keypad enter the *Index* and *Location ID* exactly as they appear on the printed labels. Under the *Sample Type* field you will see an arrow indicating a drop-down menu with preset options. If you scroll to the right while *Sample Type* is highlighted you will see the available options. Select the option you want and then scroll to the right again to exit the drop down menu.

Enter any additional information such as Owner, Sample Grid, Sample Location, etc. in the *Comments* field. Press the F1 key to *resume* collecting positions. The unit will beep for every position it collects displaying the total positions in the lower right corner. After the counter has reached the desired number of positions (30 positions), press Enter and then F1 to confirm and save your data point. Repeat this process for every new location.

Review all entries and correct any mistakes before downloading. You can view and edit the data you have collected by pressing F2 (*Review*) from the Start Feature menu. Use the directional pad to scroll through the locations and press Enter to view the sample information.

If changes are made to the data, be sure to press Enter to save the changes, otherwise just press Esc. Press F2 (*New*) to return to the Start Feature menu.

Additional useful handheld features:

- Review feature allows you to quickly view keyed data for errors, making changes as necessary.
- Repeat feature saves time & reduces keystroke errors when collecting multiple samples of the same type.
- Offset reduces the headache and extra time associated with trying to capture GPS data under bridges, large trees, porches, facades and awnings, or while standing close to a building or other object that can deflect satellites signals from the GPS receiver.
- **Delete Feature** allows you to delete a feature from a file if, for example, no positions were collected or the sample is voided. This will save time & confusion during the QC process.
- Rename File will allow you to browse through the file names you have created, and quickly edit them if necessary. This will save time if it is done before the files are downloaded.
- Delete File will allow you to delete a file from the handheld when necessary. This will save time during the QC process if it is done before the files are downloaded.

Data Collection Instructions for Trimble GeoXT:

Turn on the unit and with the stylus, select GPS from the lower right menu. This will open the Terra Sync software. Wait for the GPS status screen to recognize at least 4 satellites. Depending on your location, this can take several minutes. If you do not wait long enough, you will you not succeed in collecting your data. The connected satellite names will appear on the left side of the screen - they will be highlighted to indicate that they are connected. Select Data from the drop down menus at upper left. There will be a generic default file name that begins with "RO..." followed by the date. Create a new file name using the following naming convention: T1A10204, where T1 refers to the specific Trimble unit you are using, A refers to the first file of the day (B would be the second file of the day, and so on), and 10204 refers to October 20, 2004. You are limited to only 8 characters so the date notation will be MMDDY. The setting for data dictionary should always be set to Libby_Sampling. Select Create. Confirm the antennae height by selecting ok. Highlight the appropriate feature name and select Create. The unit will begin logging the point automatically. Enter the attribute data using the stylus and the keyboard icon located at the bottom of the touch screen. When you are finished recording, hit ok, which saves the file and location information. If you have other points to collect within the same file, select the Options menu then select Repeat.

4.3 GPS Data Transfer

GPS File Transfer to Libbysvr02 from Trimble Pro XRS

- Turn on the Trimble Unit
- The unit will try to connect to the GPS receiver press the Esc button
- Select File Manager
- Select File Transfer currently the data consists of .ssf files and is transferred to Libbysvr02\Pfdata\Libby - the file is named with an 8character identifier: T+TrimbleUnitNo+ file number(A for first file collected that day)+mmddy
- Open Pathfinder Office

- Select Utilities
- Select Data Transfer
- Select Add
- Select Datafile Pathfinder will search for a connection to the Trimble Unit
- Connect the cable from the computer to the Trimble Unit
- A list of files will appear when the connection is complete
- Select Open
- Select Transfer All
- When the download is complete, close the data transfer window if downloading files from several units, close and reopen this window between downloads
- Delete files from the Trimble Unit all of the files will be listed double check that all the files were transferred to libbysvr02 before deleting

GPS File Transfer to Libbysvr02 from Trimble Pro GeoXT

The Trimble GeoXT connects to a PC through the charger unit using a USB cable (type A to type B), and Microsoft Active Sync software. (There are Active Sync connection settings to enable or disable once the device is connected to the PC. From the Active Sync menu, select Tools, select Options. These connect the Trimble to other Windows applications on the PC eg; email, task managers, etc. The main reason to disable these settings at Libby, is that the Trimble Units are shared and it does not make sense to activate them.)

- Turn on the Trimble Unit
- Select GPS from lower right corner (This opens up the TerraSync GPS software.)
- Select Setup
- Select Options
- Select Disconnect from GPS
- Select Data
- At the bottom of list, select File Manager
- Open Pathfinder
- Select Utilities
- Select Data Transfer
- From the Device list, select GIS Datalogger on Windows CE
- Click on the connect icon (the button with the checkmark circled in green). A picture on the right will indicate the connection status.

4.4 Preliminary On-site Data Quality Control

Following the download of files from the Trimble units, a copy of each file is made and filed in Libbysvr02 \Pfdata\Libby\RawFiles. The raw files are not modified but kept as the only copy of the complete set of original downloaded data files. Using the Pathfinder export utility, shapefiles (.shp) of the non-quality control checked (QC'd) files located in Libbysvr02\Pfdata\Libby are exported. These shapefiles are opened in ArcMap. A new export file of the attribute tables from Arcmap is created and saved as a .dbf file, then opened and saved in Excel workbook format. The Excel file is imported as a new table into a recent copy of the Electronic Libby Asbestos Sample Tracking Information Center (eLASTIC). A report is generated linking the index_id of the imported table with the index_id of the eLASTIC sample Page 6 of 11

table. This report is saved in Excel. An Excel comparison function is used to compare location ids from the GPS files with the eLASTIC Location IDs. Any discrepancies are researched to determine if the error resides on the FSDS, was a data entry error in eLASTIC, or a data entry error in the GPS .ssf file. Errors in the .ssf files are corrected using Pathfinder Office. Files used for this data review process (.shp, .dbf files and .xls files) are not retained. The QC'd .ssf files are then emailed in a .zip file from the Libby Office to off-site GIS staff for processing. The QC'd and .zip files are moved to Libbysvr02\Pfdata\Libby\QC and sent zip files.

For reference on using Pathfinder export and ARCMap attribute tables see Eroom: Libby GIS folder: GPS to GIS procedure posted by Mike Schultz on August 29, 2006.

4.5 Equipment, Software & Configuration

For Trimble Pro XRS or Trimble GeoXT:

Software used

for data transfer:

GPS Pathfinder Office 2.90 and 3.10

TerraSync

Software used

for on-site QC:

GPS Pathfinder Office 2.90 and 3.10

ArcGIS ArcMap Microsoft Excel eLASTIC

Configuration Settings (TSC1 5.27 software)

Software can vary with rental equipment. Some settings can be changed to accommodate data collection needs.

Table ·	2 Configuration Settings f	or Trimble Pro XRS		
GPS Rover Options - Loggi				
Logging Intervals	Point feature	1 s		
	Line / area	3 s		
	Not in feature	none		
	Velocity	none		
Confirm end feature	no			
Minimum Positions	30			
Carrier phase	Carrier mode	off		
•	Minimum time	10mins		
GPS Rover Options - Posit	ion Filters			
Position mode	Manual 3D			
Elevation mask	15 degrees			
SNR mask	6.0			
DOP type	PDOP			
PDOP mask	6.0	6.0		
PDOP switch	4.0	4.0		
GPS Rover Options – Real-time input				
Preferred correction source				
GPS Rover Options – General real-time settings				
Correction age limit 10s				
GPS Rover Options – Antenna options				
Height 6.000USft				
Dece 7 of 11				

Measure	Vertical			
Confirm	Never			
Туре	Integrated GPS/ Beacon/Sat			
Part number	33580-50			
GPS Rover Options - Initial Pos				
North USft				
East	USft			
GPS Rover Options – 2D altitude				
Altitude(MSL)	USft			
Computed at	time			
Computed at	date			
GPS Base Station Options - Lo				
Logging Intervals	Measurements	5s		
Logging thorton	Positions	30s		
Audible Click	Yes			
Log DOP data	Yes			
GPS Base Station Options - Po				
Position mode	Manual 3D			
Elevation mask	15 degrees	***		
SNR mask	4.0			
PDOP mask	6.0			
PDOP switch	4.0			
GPS Base Station Options - Re	1			
Real-time output mode	off	······································		
Radio type	Custom	· · · · · · · · · · · · · · · · · · ·		
Baud rate	9600			
Data bits	8			
Stop bits	1			
Parity	Odd			
RTCM options	Station	1		
KT CIVI options	Message type	Type 1		
	Message interval	5s		
	Message suffix	None		
	CTS flow control	Off		
j	CTS now control CTS xmit delay	0ms		
	RTS mode			
	RTS edge delay	High Oms		
CDC Base Station Onlines - Be		Toms		
GPS Base Station Options - Re				
Datum	NAD 1983 (Conus) 11 North			
Zone NMEA/TSIP Output options	1 I NOILII			
<u></u>	TSIP			
Output	38400	· · · · · · · · · · · · · · · · · · ·		
Baud rate	NI			
Coordinate System	UTM			
Map display options	All show with no background			
Unite and Display				
Units and Display	Dietanos/2D)	LIC Curvey Et		
Units	Distance(2D) Area	US Survey Ft		
1		Square feet		
	Velocity	Miles/Hour		
İ	Angle formet	DDMMCCoo		
	Angle format	DDMMSSss		
	Order	North/East		
	North reference	True		
<u></u>	Magnetic declination	Auto		

	Null string	
	Language	English
Time and Date	24 hour clock	Yes
	Time	##:##:##
	Date format	MM/DD/YYYY
	Date	MM/DD/YY weekday
Quickmarks	Attributes	Repeat
	Confirm	No
Hardware(TSC1) softwa	are version 5.27	

Table - 3 Libby Sampling Data Dictionary
"Libby Sampling", Dictionary
"Soil Sample", point, "", 1, seconds, 1, Code
"LocationID", text, 30, required, "SP-000001", required, SP-
"IndexID", text, 30, required, required, Label1
"Sample_Type", menu, required, required, Label2
"COMPOSITE", default
"GRAB"
"SamplGroup", menu, required, required
"BARN"
"BARROW SOURCE"
"BASEMENT"
"BLANK"
"DRIVEWAY"
"FIELD"
"FLOWER BED"
"GARAGE"
"GARDEN"
"HOUSE"
"PARK"
"PROPERTY"
"ROAD"
"SCHOOL"
"SHED"
"WALKWAY"
"YARD", default
"STOCKPILE"
"Upper_Depth", text, 30, required, "Inches", required
"Lower Depth", text, 30, required, "Inches", required
"Comment", text, 30, normal, normal
"Air Sample", point, "", 1, seconds, 1, Code
"LocationID", text, 30, required, required
"IndexID", text, 30, required, required, Label1
"Sample_Type", menu, required, required, Label2
"PERSONAL"
"STATIONARY", default
"SamplGroup", menu, required, required
"BARN"
"BARROW SOURCE"
"BASEMENT"
"BLANK"
"DRIVEWAY"
"FIELD"
Pose 0 of 11

"ELOWED DED"
"FLOWER BED"
"GARAGE"
"GARDEN"
"HOUSE", default
"PARK"
"PROPERTY"
"ROAD"
"SCHOOL"
"SHED"
"WALKWAY"
"YARD"
"Comment", text, 30, normal
"Dustfall Sample", point, "", 1, seconds, 1, Code
"LocationID", text, 30, required, required, Label1
"IndexID", text, 30, required, required, Label2
"Sample_Type", menu, required, required
"BUILDING", default
"VEHICLE"
"NA"
"OTHER"
"SamplGroup", menu, required, required
"BARN"
"BARROW SOURCE"
"BASEMENT"
"BLANK"
"DRIVEWAY"
"FIELD"
"FLOWER BED"
"GARAGE"
"GARDEN"
"HOUSE", default
"PARK"
"PROPERTY"
"ROAD"
"SCHOOL"
"SHED"
"WALKWAY"
"YARD"
"STOCKPILE"
"Comment", text, 30, normal, normal
UD italia a La codi a ti una indutti di coccando di Condo
"Building Location", point, "", 1, seconds, 1, Code
"LocationID", text, 30, required, "BD-000001", required, BD-, Label1
"Address", text, 50, required, normal, Label2
"Comments", text, 30, normal, normal
market - O desired Orange of the Bill A consider the A
"Water_Sedmnt Sample", point, "", 1, seconds, 1, Code
"LocationID", text, 30, required, required, Label1
"IndexID", text, 30, required, required, Label2
"Matrix_Type", menu, required, required
"Surface"
"Weil", default
"Comment", text, 30, normal, normal

"Interest Point", point, "", 1, seconds, 1, Code
"Location", text, 30, required, required, Label1
"Land_Use", text, 30, required, required, Label2
"Comment", text, 30, normal, normal
"Interest Area", area, "", 3, seconds, Code
"Location", text, 30, required, required, Label1
"Land_Use", text, 30, required, required, Label2
"Comment", text, 30, normal, normal
"Sample Area", area, "For odd composits", 3, seconds, Code
"LocationID", text, 30, required, "SP-000001", required
"IndexID", text, 30, required, required, Label1
"Num_of_Composits", numeric, 0, 0, 100, 5, required, "Number of Composits", required, Label2
"Upper_Depth", text, 30, required, "Inches", required
"Lower_Depth", text, 30, required, "Inches", required
"Comment", text, 30, normal, normal

Project-Specific Modification

SOP No.: <u>EPA-2084</u>

SOP Title: Activity-Based Air Sampling for Asbestos

Project: Libby Superfund Site

Project No.: 58570-013

Client: Department of Transportation-Volpe Center

Technical Reviewer: Summer Date: 7/8/07

QA Reviewer: Date: 7/0/07

Volpe Approval: Mally Date: 7/9/0.7

EPA Approval: Date: 7/9/07

Reason for and duration of modification: Activity based air sampling for asbestos procedures for the Libby superfund site vary slightly from EPA SOP 2084. These modifications are necessary for the entire duration of the project.

Activity-based air sampling for asbestos will be in accordance with EPA SOP 2084, with the following modifications:

Section 7.6.6. Lawn Mowing – Mowing will be conducted over an entire yard area with similar contamination (i.e., Libby amphibole concentration, visual vermiculite). The scenario will be repeated as many times as possible within the two hour sampling period. If multiple passes over the scenario area are required due to the size of the yard, the first will proceed from east-west and the second pass will be north-south.

Section 7.8 Background/Reference Sampling - Background/reference samples will not be collected as described in the SOP. Data collected during the current outdoor ambient air sampling program should be sufficient to address background/reference concentrations.



7.5

STANDARD OPERATING PROCEDURES

SOP: 2084 PAGE: 1 of 29 REV: 0.0

DATE: 05/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

CONTENTS

1.0	SCOPE AND APPLICATION			
2.0	METHOD SUMMARY			
3.0	SAMPLE PRESERVATION, CONTAINERS, HANDLING AND STORAGE			
	3.1 3.2	Sample Preservation Sample Handling, Container and Storage Procedures		
4.0	INTERFERENCES AND POTENTIAL PROBLEMS			
	4.1 4.2 4.3	Area Selection Flow Rate Considerations Transmission Electron Microscopy (TEM) Specimen Preparation Methods 4.3.1 Direct-Transfer TEM Specimen Preparation Methods 4.3.2 Indirect TEM Specimen Preparation Methods		
	4.4	Sampling Cassette Orientation		
5.0	EQUIP	MENT/APPARATUS		
6.0	REAGENTS			
7.0	PROCEDURES			
	7.1 7.2	Pre-Site Sampling Preparation Calibration Procedures		
		 7.2.1 Calibrating a Personal Sampling Pump with a Rotameter 7.2.2 Calibrating a Personal Sampling Pump with an Electronic Calibrator 		
	7.3 Meteorology			
	7.4 General Sampling Information			

Generic Activity-Based Sampling Scenario/Raking



8.0

9.0

10.0

11.0

12.0

13.0

HEALTH AND SAFETY

REFERENCES

APPENDICES

A - Tables

STANDARD OPERATING PROCEDURES

SOP: 2084 PAGE: 2 of 29 REV: 0.0 DATE: 05/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

CONTENTS (cont'd)

7.6	Site-Sp	ecific Activity-Based Sampling Scenarios
	7.6.1	ATV Riding
	7.6.2	Child Playing in the Dirt
	7.6.3	Gardening/Rototilling
	7.6.4	Weed Whacking/Cutting
	7.6.5	Digging
	7.6.6	Lawn Mowing
	7.6.7	Walker with Stroller
	7.6.8	Jogging
	7.6.9	Two Bicycles
	7.6.10	Basketball Scenario
7.7	Cumula	tive Exposure Scenario
7.8	Backgro	ound/Reference Sampling
7.9	Perimet	er Sampling
7.10	Soil Sar	mpling
CALC	ULATION	NS
QUAL	ITY ASSI	URANCE/QUALITY CONTROL
DATA	VALIDA	TION



SOP: 2084 PAGE: 3 of 29 REV: 0.0 DATE: 05/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

1.0 SCOPE AND APPLICATION

As a result of a directive issued by the United States Environmental Protection Agency (U.S. EPA) Office of Solid Waste and Emergency Response (OSWER Directive 9345.4), estimating asbestos exposures resulting from suspension of soils is an area of increased importance to the Superfund Program. Such exposures may be estimated via monitoring and/or modeling methods. At present, models are not available to accurately estimate asbestos exposure associated with the disturbance of contaminated soil. Therefore, personal monitoring in the form of activity-based sampling (ABS) is the most appropriate technique to estimate exposure. Personal exposure is influenced by the activities performed, the duration of the activity and the site-specific soils of interest.

At a number of diverse sites across the county (Clear Creek Management Area, San Benito County, California (CA), El Dorado Schools, North Ridge Estates, Klamath Falls, Oregon, Slodusty Road, Garden Valley CA, Ambler Alaska), the U.S. EPA has demonstrated that disturbance of soil with low levels of asbestos (including soil concentrations less than 1.0 percent (%) as measured by Polarized Light Microscopy) can potentially result in significant concentrations (>0.1 structures per cubic centimeter) of respirable asbestos fibers in the breathing zone of individuals engaged in various physical activities. This may result in a cancer risk in excess of Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) remedial objectives.

Since personal monitoring is more representative of actual exposure than samples obtained from a fixed downwind location (McBride 1999, Rodes 1995, Hildemann 2005), personal monitoring results are generally most relevant to CERCLA risk characterizations. Thus the best measure of actual exposure to an individual would be through the collection of personal air samples over the exposure period of interest (NIOSH 1977). However, at CERCLA sites, it is neither always possible nor practical to do so. EPA has thus developed a sampling procedure called ABS, designed to mimic the activities of a potential receptor.

As part of ABS, U.S. EPA or contractor personnel trained in hazard recognition and mitigation, serve as surrogates for the potentially exposed populace of interest. ABS simulates routine activities in order to mimic and evaluate or predict personal exposures from disturbance of materials potentially contaminated with asbestos. Similar sampling approaches have been used to assess exposures to pesticides and lead (U.S. EPA 2000) and this technique has long been a cornerstone of industrial hygiene wherein workplace exposures are routinely assessed via personal exposure monitoring.

This document provides guidance for ABS for a particular set of activities or scenarios. Personal monitoring may be conducted during various activities such as raking, All-Terrain Vehicle (ATV) riding, rototilling, digging, a child playing in the dirt, weed whacking, lawn mowing, walking with a stroller, bicycling, and playing basketball.

These are standard (i.e., typically applicable) operating procedures which may be varied or changed as required, dependent upon site conditions, equipment limitations or limitations imposed by the procedure. In all instances, the ultimate procedures employed should be documented and associated with the final report.



SOP:

2084 PAGE: 4 of 29

REV: 0.0

DATE: 05/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

This document is not intended to be used as a substitute for a site-specific Quality Assurance Project Plan (QAPP) or a detailed Sampling and Analysis Plan (SAP). This document is intended to be used as a reference for developing site-specific QAPPs and SAPs.

Mention of trade names or commercial products does not constitute U.S. EPA endorsement or recommendation for use.

2.0 METHOD SUMMARY

There are two types of ABS that can be employed in the field: generic ABS and site-specific ABS. Generic ABS can be used with potentially contaminated soil and utilizes a rake to disturb the soil over a known area in conjunction with the collection of air samples to characterize potential exposure. Site-specific ABS is also used with contaminated soil; however, it utilizes site-specific activities to disturb the soil, such as riding ATVs, jogging or riding bikes. Although site-specific ABS provides a more realistic measure of fiber release, it can also be more resource intensive and it is recommended to be used after the generic ABS, if results deem necessary.

For all ABS events, asbestos samples should be collected from the breathing zones of the subjects at an appropriate flow rate. Special consideration should be given to characterizing exposure to children as it has been hypothesized that children are more prone to exposure than adults (U.S. EPA 2000) because they tend to be closer to the source. Sample flow rates, duration and final volume will need to be weighed against the number of grid openings that must be counted (cost factor) to obtain the needed sensitivity. Sampling periods should be of sufficient durations (averaging time) to facilitate collection of a representative sample and achieving the required level of sensitivity.

SAMPLE PRESERVATION, CONTAINERS, HANDLING AND STORAGE 3.0

3.1 Sample Preservation

No preservation is required for asbestos samples.

3.2 Sample Handling, Container, and Storage Procedures

- 1. Place a sample label on the cassette indicating a unique sampling number. Do not put sampling cassettes in shirt or coat pockets as the filter can pick up fibers or a static charge that could disturb the dust deposited on the filter media.
- 2. Samples must be handled gently with the filter inlet facing upward to avoid disturbing the particulate deposited on the filter and to minimize the potential of imparting a static charge to the cassette, which might alter the particulate deposition on the filter media.
- Place the cassette individually in a manila-type envelope. Each envelope should be 3. marked with the sample identification number, total volume, and date.



SOP: 2084 PAGE: 5 of 29 REV: 0.0 DATE: 05/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

- 4. To the best extent possible, the sampling cassettes in the manila envelopes should be placed right side up so that the cassette inlet cap is on top and cassette base is on bottom. Place samples into a shipping container and use enough packing material to prevent jostling or damage. Samples must be handled gently so as not to disturb the dust deposited on the filter media. Do not use vermiculite or any other type of fibrous packing material for samples. If possible, hand carry to lab.
- 5. Provide appropriate documentation with samples (i.e., chain of custody and requested analytical methodology).

4.0 INTERFERENCES AND POTENTIAL PROBLEMS

4.1 Area Selection

When selecting areas for ABS, consideration should be given to the potential for off-site migration of contaminants and possible exposure of the public. Within the constraints of ABS, to the degree practical, particulate generation migration off-site should be minimized, and constraints or mitigation protocols established to eliminate public exposure. These constraints/mitigation protocols may include conducting the ABS in remote areas of the site, dust suppression using water mist, building a containment structure, etc. Air sampling should be conducted to document the airborne concentration of asbestos at the site perimeter during activities.

4.2 Flow Rate Considerations

For activities that generate a large quantity of dust (i.e., particulates), sample flow rates may need to be reduced accordingly to avoid overloading the filters. For example, a sampling pump flow rate of approximately 3.0 liters per minute (L/min) was found most effective at one site for monitoring for asbestos while riding ATVs on dusty soils while high soil moisture and reduced particulate generation at another site permitted a 5.0 L/min flow rate.

High flow rates may result in filter damage due to failure of its physical support associated with increased pressure drop, leakage of air around the filter mount so that the filter is bypassed or damage to the asbestos structures (breakup of bundles and clusters) due to increased impact velocities (ISO 10312). High flow rates can also tear the filters during initial pump startup due to the shock load placed on the filter when the pump is first started.

Sampling larger volumes of air and analyzing greater areas of the filter media can theoretically lower the limit of detection indefinitely. In practice, the total suspended particulate (TSP) concentration limits the volume of air that can be filtered as TSP can obscure asbestos fibers. The International Organization for Standardization (ISO) Method 10312 states that the direct analytical method cannot be used if the general particulate loading exceeds approximately 10% coverage of the collection filter. An airborne concentration of approximately 10 micrograms per cubic meter



SOP: 2084 PAGE: 6 of 29 REV: 0.0 DATE: 05/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

(μ g/m³), corresponding to clean rural air, results in approximately 10% coverage of the filter media based on a 4000-L sample.

The following formula from ISO 10132 may be used to calculate the analytical sensitivity:

$$S = \frac{A_t}{KA_gV}$$

Where:

S = Analytical sensitivity expressed in structures per liter

 A_i = Active area in square millimeters of the collection media or filter

 $A_g = Mean$ area in square millimeters (mm²) of the grid openings examined,

K = Number of grid openings examined

V = Volume of air sampled, in liters

NOTE: 25-millimeter (mm) cassettes have an effective filter area of 385 mm² and 37-mm cassettes have an effective filter area of 855 mm². The typical grid opening is 0.0057 mm². Note: Grid size will vary between laboratories and dimensions should be verified prior to calculating the number of grid openings that must be counted to achieve a particular level of sensitivity.

Table 1 provides an example of the minimum number of grid openings that must be counted in order to achieve various sensitivity and detection limits.

It is frequently more efficient to employ co-located samplers to collect a high and low volume of air. This increases the likelihood of at least one of the two samples being readable using the direct analytical method (ISO 10312) than to lose the sample due to overloading or having to analyze by the indirect method (ISO 13794).

4.3 Transmission Electron Microscopy (TEM) Specimen Preparation Methods

It can be argued that direct methods yield an under-estimate of the asbestos structure concentration because other particulate material with which they are associated conceals many of the asbestos fibers present. Conversely, indirect methods can be considered to yield an over-estimate because some types of complex asbestos structures disintegrate during the preparation, resulting in an increase in the numbers of structures counted.



SOP: 2084 PAGE: 7 of 29 REV: 0.0 DATE: 05/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

4.3.1 Direct-Transfer TEM Specimen Preparation Methods

Direct-transfer preparation methods are intended to retain all particles in the same relative positions with respect to each other on the final TEM grids as on the original filter. The membrane filter, or a portion of it, is placed on a microscope slide with the sample face upward, and then collapsed by exposure to acetone vapor. The cleared filter is then etched in a low-temperature plasma asher, subsequently coated with carbon in a sputtering device and then peeled from the glass slide. A portion of the collapsed, etched and carbon-coated filter is then transferred to an electron microscope grid and then extracted with dimethylformamide, glacial acetic acid and water to remove the filter. Once the process is complete, the particles originally collected on the filter are bound in the carbon film and the grids can be observed on a transmission electron microscope (ISO 1995). Direct-transfer TEM specimen preparation methods have the following significant interferences:

- The particulate density on the filter, which in turn is controlled by the sampled air volume and the total suspended particulate concentration in the atmosphere being sampled, restricts the achievable detection limit.
- The precision of the result is dependent on the uniformity of the deposit of asbestos structures on the sample collection filter.
- Air samples must be collected so that they have particulate and fiber loadings
 within narrow ranges. If too high a particulate loading occurs on the filter, it is
 not possible to prepare satisfactory TEM specimens by a direct-transfer method.
 If too high a fiber loading occurs on the filter, even if satisfactory TEM
 specimens can be prepared, accurate fiber counting may not be possible.

4.3.2 Indirect TEM Specimen Preparation Methods

In the indirect preparation method the membrane filter, or a portion thereof, is placed on a microscope slide, sample face downward, and ashed in a low temperature asher until complete calcination of the filter is achieved. The ash is then recovered in distilled water and the solution then filtered on a polycarbonate filter. The indirect transfer method redistributes the particulate on a new membrane filter.

Indirect TEM specimen preparation methods have the following interferences:

- The size distribution of asbestos structures is modified (clusters, matrices bundles, etc. may be broken up during sample preparation).
- There is increased opportunity for fiber loss or introduction of extraneous contamination from laboratory glassware, process water, etc.



SOP: 2084 PAGE: 8 of 29 REV: 0.0 DATE: 05/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

 When sample collection filters are ashed, any fiber contamination in the filter medium is concentrated on the TEM specimen grid.

The direct analytical method (ISO 10312) is the preferred method and every reasonable effort should be made to prevent overloading of the filter, which would necessitate use of the indirect method. Samples that are overloaded may, at the discretion of the project management team, be analyzed by ISO Method 13794 "Ambient air – Determination of asbestos fibres – Indirect-transfer transmission electron microscopy method" (ISO 1999). Results of the ISO 13794 analysis should be reviewed discrete of the ISO 10312 samples and a decision made regarding combining the two data sets.

4.4 Sampling Cassette Orientation

Air sampling cassettes must be oriented with the open face pointing down to preclude large non-respirable particles from falling or settling onto the filter media.

5.0 EQUIPMENT/APPARATUS

- Personal sampling pumps, providing a flow rate from 0.020 L/min up to 4.0 L/min, battery powered
- High flow sampling pumps (i.e., Quik Take 30 or AirCon II), capable of providing a flow rate from 4.0 to 12 L/min, battery or alternating current (AC)
- Mixed cellulose ester (MCE) filter cassettes, 0.45 or 0.8 micrometer (μm), 25-mm diameter, purchased from a certified vendor with appropriate documentation (low filter background counts, consistent filter area, certified leak-free cassettes)
- Sampling setups, Tygon[®] tubing with Luer type adaptor
- Backpacks
- Sampling stands, for perimeter sampling
- Duct tape
- Tools, miscellaneous (e.g., screwdrivers, pliers, cutting tool, etc.)
- Envelopes, manila-type
- Whirlpak[®] bags
- Sample labels



SOP: 2084 PAGE: 9 of 29

REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

- Chain of custody (COC) records
- Logbook and/or sampling worksheets
- Precision rotameter or primary flow standard appropriate for sampling flow rate
- Personal protective equipment (PPE), including but not limited to respirators, boots, gloves, eye
 protection, hard hat, to be determined based on type of activity and possible exposure
- Decon equipment (Plastic sheeting, liquinox®, buckets, brushes, water, Hudson sprayers, garbage bags, etc.)
- Power sources, e.g., line power, solar recharging batteries, power inverters, generators, etc.

6.0 REAGENTS

Reagents are not required for the preservation of asbestos samples.

7.0 PROCEDURES

7.1 Pre-Site Sampling Preparation

- 1. Determine the extent of the sampling effort (number of locations, repetitions, number of samples, etc.), the sampling methods to be employed, and the types and amounts of equipment and supplies needed.
- 2. Obtain necessary sampling equipment and ensure it is in working order and fully charged (if necessary).
- 3. Perform a general site survey prior to site entry in accordance with the site-specific Health and Safety Plan (HASP).
- 4. Once on-site the calibration is performed in the clean zone. The calibration procedures are listed in Section 7.2.
- 5. After calibrating the sampling pump, mobilize to the sampling location.



SOP: 2084

PAGE: 10 of 29

REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

7.2 Calibration Procedures

To determine if a sampling pump is measuring the flow rate or volume of air correctly, it is necessary to calibrate the equipment. Sampling pumps should be calibrated on a routine basis and prior to use.

A rotameter can be used provided it has been calibrated with a primary calibrator. Typically rotameters are calibrated on a yearly basis. Sampling pumps can be calibrated prior to coming onsite in order to expedite on-site calibration. However, calibration must be verified on-site prior to use.

7.2.1 Calibrating a Personal Sampling Pump with a Rotameter

- 1. Refer to the manufacturer's manual for the Rotameter Operational Instructions.
- 2. Set up the calibration train using a rotameter, sampling pump and the sampling cassette that will be used during the sampling event. This train may be set up prior to field mobilization and will be checked in the field again prior to use.
- 3. To set up the calibration train, attach one end of the polyvinyl chloride (PVC) tubing (approx. 2 ft) to the cassette base; attach the other end of the tubing to the inlet plug on the pump. Another piece of tubing is attached from the cassette cap to the rotameter. Insure that the tubing and rotameter used to calibrate the pump do not restrict the airflow.
- 4. Assemble the base of the flow meter with the screw provided and tighten in place. The flow meter should be mounted within 6 degrees (°) of vertical (Omega 1987).
- 5. Turn the sampling pump on.
- 6. Turn the flow adjust screw (or knob) on the personal sampling pump until the float ball on the rotameter is lined up with the pre-calibrated flow rate value on the rotameter. Note: rotameters should be marked with the previous calibration date and corresponding flow rates and scale.
- 7. A verification of calibration is generally performed on-site in the clean zone immediately prior to the sampling.



SOP: 2084 PAGE: 11 of 29 REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

7.2.2 Calibrating a Personal Sampling Pump with an Electronic Calibrator

- 1. Refer to the manufacturer's manual for operational instructions.
- Set up the calibration train using a sampling pump, electronic calibrator, and the
 actual sampling cassette or a representative filter cassette. The same lot of
 cassettes used for sampling should also be used for calibration.
- 3. To set up the calibration train, attach one end of the PVC tubing (approx. 2 foot) to the cassette base; attach the other end of the tubing to the inlet plug on the pump. Another piece of tubing is attached from the cassette cap to the electronic calibrator.
- Turn the electronic calibrator and sampling pump on. Select a flow rate to calibrate.
- 5. Turn the flow-adjust screw or knob on the pump until the desired flow rate is attained on the rotameter.
- 6. Using the primary calibrator, obtain approximately 10 readings three times until the flow rate of \pm 5% of the required flow is attained.

7.3. Meteorology

It is recommended that an onsite, portable, 3-meter meteorological station be established. If possible, sample after two to three days of dry weather and when wind conditions are representative for the climatology of the location based on month and time of day. Historical hourly wind speed and wind direction data should be analyzed before mobilization. Wind speed, wind direction, temperature, and station pressure should be recorded on the meteorological station data logger and real-time data should be available for review on the station display panel. Suggested meteorological station specifications can be found in Table 2, Appendix A or ERT SOP #2129, Met One Remote Meteorological Station. Alternatively, a nearby representative meteorological station, as determined by a meteorologist, may be used to acquire the necessary data.

7.4 General Sampling Information

For all activity-based sampling events, except as noted otherwise, asbestos samples will be collected from the breathing zones of the event participants. The breathing zone can be visualized as a hemisphere approximately 6 to 9 inches around an individual's face. Breathing zone samples provide the best approximation of the concentration of contaminants in the air that an individual is



SOP: 2084 PAGE: 12 of 29 REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

actually breathing. Specific breathing zone heights should be determined on a project-by-project basis based on the anthropometrics for the study population and the participants' positions during the performance of each task.

If it is necessary to relieve a participant from the activity, another sample collector should be suited and ready to participate in the ABS prior to the personnel exchange. The participant will stop the activity, remove the backpack or belt, and pass it to the relief participant similar to the transfer of a baton in a relay race. The original participant will assist the relief participant with donning and adjusting the backpack or belt. The exchange is anticipated to take less than 60 seconds, therefore the sampling pumps and event time clock will not be halted during the exchange. If the exchange requires more than 60 seconds, the pump and event clock will be stopped until activity is reinitiated.

Sample volumes and detection/quantification limits should be specified in the site-specific QAPP with flow rates and sampling periods adjusted accordingly. Typical sensitivity limits that have been employed for risk assessment have been approximately 0.001 S/cc for ABS samples and 0.0001 S/cc for background or reference samples. Based on ISO 10312 Table 1, a sensitivity limit of 0.001 S/cc would require a sample volume of greater than 500 liters to keep the number of grid openings to be counted below 100. Similarly, a sample volume greater than 5000 L would be required to reach 0.0001 S/cc and count fewer than 100 grid openings. For all asbestos sampling, an asbestos sampling train consisting of 0.8-\mum, 25-mm mixed cellulose ester (MCE) filter connected to a personal sampling pump will be used. The top cover from the cowl extension on the sampling cassette shall be removed ("open-face") and the cassette oriented face down for all asbestos filters. All samples should be collected open-faced unless a specific requirement for sampling closed-faced exists.

For activity based sampling, a personal sampling pump (or equivalent) or SKC Quick Take 30 will be calibrated to collect between 2 and 12 L/min of air through the filter depending on the capacity of the pump. The flow rate will be based upon the duration of time required to collect a minimum target volume of 560 L and provide a sensitivity limit of 0.001 S/cc.

Generally each activity based sampling event should be repeated a minimum of three times in an area to expose trends. This can be accomplished by a single participant repeating the activity three or more times or by having a single simulation with three or more participants. If soil moisture or seasonal variability is a concern, then three events for each different season or meteorological conditions may be appropriate.

The sampling pumps used should provide non-fluctuating airflows through the filter, and should maintain the initial volume flow rate to within \pm 10% throughout the sampling period. A constant flow or critical orifice controlled pump typically meets these requirements. If the flow rate changes by more than 5% during the sampling period, the average of the pre- and post-sampling



SOP: 2084 PAGE: 13 of 29 REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

rates will be used to calculate the total sample volume. If at any time the measurement indicates that the flow-rate has decreased by more than 30%, sampling should be terminated. Depending on the type of sampling pump used, it may be possible to salvage the sample if sufficient volume was collected; however, it may not be representative of the time it takes for the actual activity to be completed. Depending on the type of sampling pump used, the actual sampling time in hours and minutes before the sampling fault may be displayed and an actual sample volume calculated. If the fault was due to battery failure, it may be possible to check the post-sampling flow.

During certain ABS activities, participants may be fitted with two sampling pumps to collect a high-flow or volume and a low-flow or volume sample. Co-located samples are collected to sample a high and low volume of air to increase the likelihood of at least one of the two samples being readable using the direct analytical method (ISO 10312). Approximately 560 L (40 CFR 763) is collected for the low-flow samples and up to 4000 L for the high-flow samples. The targeted high volume is typically 1200 L, which permits counting approximately 54 grid openings for a sensitivity level of 0.001 S/cc.

7.5 Generic Activity-Based Sampling Scenario / Raking

The raking scenario, also referred to as the generic scenario, is appropriate for all sites with soils potentially contaminated with asbestos. Generic ABS should be employed in a grid pattern to evaluate the potential for fiber release from soil over a portion of the site. If the analytical results are above the criteria that were derived for the site, then remediation or institutional controls should be implemented or additional site-specific ABS should be undertaken. If the analytical results are below the criteria that were derived, then no further action may be necessary.

In this activity or simulation a participant will rake a lawn or garden area to remove debris such as rocks, leaves, thatch and weeds using a leaf rake with a rake width of approximately 20 to 28 inches. Participants should strive to disturb the top half-inch of soil with an aggressive raking motion. This depth will vary based on the objective of the scenario.

Each raking participant donning appropriate PPE will be fitted with a personal sampling pump contained in a backpack with the cassette secured to the shoulder straps near the operator's lapels in the breathing zone. Personnel will rake a lawn or garden area to remove debris for a minimum of 1 to 2 hours (flow rate and sensitivity level dependent). Raking will occur in a measured area with vegetation, soil or rocks/gravel and will occur in an arched motion raking from the left of the participant to the right. The participants will rake the debris towards themselves facing one side of the square for 15 minutes then the participant will turn 90 degrees clockwise and begin a new side. Participants will continue to rake each side of the square and rotate 90 degrees. Once several small piles of debris have been made, the participant shall pick up the debris and place it in a trashcan. The sequence of raking, rotating and picking up debris shall be repeated for the duration of the sampling period. The participant should stay in the same plot for the entire sampling period.



SOP: 2084 PAGE: 14 of 29 REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

7.6 Site-Specific Activity-Based Sampling Scenarios

If site-specific ABS is undertaken, the number and types of activities as well as the types of scenarios should be based on current and potential land use. Reference to current and currently planned future land use and the effectiveness of institutional or legal controls placed on the future use of the land should be evaluated. Probable land use should be selected based on zoning and the existing land use of the site and adjacent areas.

Land use assumptions should be based on a factual understanding of site-specific conditions and reasonably anticipated use. The land use evaluated for the assessment should be based on a residential exposure scenario (i.e., the default worst-case) unless residential land use is not plausible for the site. Future land use assumptions should be consistent with reasonably anticipated future land use based on input from planning boards, appropriate officials, and the public.

7.6.1 ATV Riding

This scenario might be appropriate for recreational areas or other areas where ATVs are typically ridden where asbestos contamination is present. This activity is designed to be representative of two or more ATV participants riding on a course or trail. Riders should maintain their relative position (lead, middle, tail) throughout the activity.

Each ATV rider wearing appropriate PPE will be fitted with two personal sampling pumps set at two distinct flow rates, to collect approximately 560 and 1200 liters of air, because of filter overloading concerns. The cassettes for the personal sampling pumps will be attached to the shoulder straps of the backpack proximal to the riders' lapels in the breathing zone. It may be beneficial to attach a dust monitor (e.g., DataRAM) to the tail ATV to record dust levels and gauge dust loading. The sampling pumps will be carried in a backpack while the dust monitor, if used, will be mounted to the ATV.

Personnel will ride the ATVs around a course at the same time until a sufficient volume of air has been collected to achieve the required sensitivity limit of 0.001 S/cc of air. The riders, one lead rider and one following rider, will vary the vehicle speed between 5 and 30 miles per hour (mph). Riders will strive for an average speed of 10 mph. The average speed is a target speed only; vehicle speeds will be adjusted to meet track conditions. Vehicles will be equipped with a speedometer and odometer to record speeds and distance traveled. ATV riding and sampling should be conducted for 30 to 120 minutes in duration, depending on dust loading and required detection limits.

ATVs and ATV tires should be selected as appropriate for the area being studied. Specifically, the size (i.e., weight, horsepower, etc.) of the ATV should be appropriate for



SOP: 2084 PAGE: 15 of 29 REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

the study area. The vehicle tires should have a tread pattern that is representative of those typically used in the area. Local ATV shops or ATV clubs should be consulted for guidance.

7.6.2 Child Playing in the Dirt

This scenario might be appropriate for sites where schools, playgrounds, parks or residential areas, etc. are contaminated with asbestos; the overarching criteria being areas where a child might be expected to play or dig in the dirt. This scenario was designed to be representative of a child playing in the dirt with a shovel and pail.

The event participant wearing appropriate PPE will be fitted with a personal sampling pump; the inlet to the filter will be at a height of approximately 1 to 3 feet above the ground to simulate a child's breathing zone. The actual pump unit should be secured in a backpack or on a belt.

A participant should sit on the ground while digging or scraping the top 2 to 6 inches of surface soil, placing it in a small bucket or pail and dumping it back on the ground. The activity will be paced such that soil will be placed in the bucket and dumped approximately every two to five minutes, regardless of the amount of material in the bucket. The bucket should be emptied rapidly from a height of approximately 12 inches, based on observations of two to four-year-olds playing in a sandbox.

A sampling period and flow rate to collect a sufficient volume of air will be determined as to achieve the project-specific detection/quantification limit. The sampling period will be divided into equal sub-periods to facilitate having the participant face each compass direction for an equal amount of time during the activity. This approach is designed to mitigate the effect of wind direction on potential exposure. Random head and body movement during the activity should further mitigate the impact of wind direction on exposure. Ideally, the participants will face each compass direction at least twice during the sampling event. For example, during a two-hour or 120-minute event, the participant might face North for 15 minutes, rotate to the East for 15 minutes, then South for 15 minutes, then West for 15 minutes and return to the North to repeat the cycle. Participants should move to a fresh patch of soil after the completion of each cycle (360 degree rotation).

7.6.3 Gardening/Rototilling

This scenario might be appropriate for sites where gardening or surface disturbance to a depth of approximately one foot is anticipated. This activity is designed to be representative of individuals participating in gardening activities using a rototiller.



SOP:

2084 PAGE: 16 of 29

REV: 0.0

DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

Each rototilling participant donning appropriate PPE will be fitted with a personal sampling pump. The actual pump unit will be contained in a backpack with the cassette secured to the shoulder straps near the operator's lapels in the breathing zone.

Personnel will operate a rototiller for a minimum of two hours to loosen soil in the yard to a depth of approximately 12 inches. The depth chosen is area-specific and will need to be determined on a case-by-case basis. A rear tine rototiller in the six to eight horsepower range will be selected. Other types or sizes of tillers may be appropriate based on the soil conditions and type of gardening being conducted.

A 100 to 720-square-foot plot of land will be selected to till. The average size of a community garden in New Jersey was 720 square feet based on a survey conducted by Rutgers University in 1991 (Patel 1991). The edges will be delineated. Square plots are preferred. The rototiller operator will conduct typical associated activities such as removing rocks and debris from the tilled area. To account for the effects of varying wind direction on potential exposure, the operator will till the soil back and forth towards each side of the square continuously for 10 minutes, shut down the machine or place it in neutral, and rake or sort through the material for five minutes. The operator will then turn 90 degrees in a clockwise direction and repeat the previous 15-minute procedure. The operator will continue to rotate 90 degrees clockwise every 15 minutes until the two-hour sampling period is complete. The participant should stay in the same plot for the entire sampling period.

7.6.4 Weed Whacking/Cutting

This scenario might be appropriate for sites where lawn maintenance might be conducted such as in residential and commercial areas. This activity is designed to simulate a person trimming weeds and grasses.

Each weed-whacking participant will be fitted with a personal sampling pump. The actual pump unit will be contained in a backpack with the cassette secured to the shoulder straps near the operator's lapels in the breathing zone. Personnel wearing appropriate PPE will operate a gas or electric-powered string trimmer. A 25 to 35-cc gas or electric-powered trimmer with a 16 to 18- inch cutting swath will be selected. Trimming and edging will occur in a measured area with thick vegetation (typically 100 to 720-square feet, based on a typical residential garden) (Patel 1991). Trimming will be done using a side to side sweeping motion with the operator moving in a series of straight lines back and forth towards one side of the selected area for 10 minutes, resting five minutes, and turning 90 degrees in a clockwise direction before repeating this 15-minute procedure for the



SOP: 2084 PAGE: 17 of 29 REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

duration of the sampling period. The participant should stay in the same plot for the entire sampling period.

7.6.5 Digging

Digging might be appropriate for sites where construction projects are likely to occur or where plants might be planted. Digging will occur in a measured area with vegetation, soil or rocks/gravel.

Each digger participant donning appropriate PPE will be fitted with a personal sampling pump contained in a backpack with the cassette secured to the shoulder straps near the operator's lapels in the breathing zone. The participants will dig a hole to approximately two feet deep and two feet (representative of planting a small shrub or digging a fencepost; site-specific dimensions should be specified in the QAPP/SAP) in diameter (Vodak 2004) and will place the soil next to the hole. The participants will then refill the hole with the soil that had been removed. Participants will then rotate 90 degrees in a clockwise direction and continue to dig and refill additional holes until the sampling period is complete. The sequence of digging, filling and rotating shall be repeated for the duration of the sampling period.

7.6.6 Lawn Mowing

Lawn mowing might be appropriate for sites where lawn maintenance might be conducted such as residential and commercial areas.

Each lawn-mowing participant will be fitted with a personal sampling pump contained in a backpack with the cassette secured to the shoulder straps near the operator's lapels in the breathing zone. Personnel wearing appropriate PPE will operate a gas-powered lawn mower. Mowing will occur in a measured area with thick vegetation and will occur in a shrinking square pattern. Participants will divide the area into a number of squares that decrease in size towards the center of the square by the width of the mower swath. Mower blades will be set at approximately 2 to 2.5 inches. A bag-less side discharge 3-to 5-horsepower lawn mower will be used for this exercise.

7.6.7 Walker with Stroller

This scenario might be appropriate for sites such as parks, paths or open-space. The actual pump unit will be secured in a backpack. The cassette for the personal sampling pump will be attached to the shoulder straps of the backpack proximal to the walker's lapel in the breathing zone. A second pump will be placed in the stroller at a child's breathing zone height.



SOP:

2084 PAGE: 18 of 29

REV: 0.0

DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

During these events, walkers wearing appropriate PPE pushing a stroller will walk back and forth along a portion of a path until a sufficient volume of air has been collected to achieve the required detection limit. The walkers will vary their speed between 1.5 and 4 mph. Walkers will strive for an average speed of 2 mph. The average speed is a target speed only; speeds will be adjusted to meet trail conditions. Walkers should be equipped with a global positioning system (GPS) unit to estimate average speed and distance traveled.

7.6.8 **Jogging**

This scenario might be appropriate for sites such as parks, paths or open-space. The actual pump unit will be secured in a backpack. The cassette for the personal sampling pump will be attached to the shoulder straps of the backpack proximal to the jogger's lapel in the breathing zone.

During these events, joggers wearing appropriate PPE will run/jog back and forth along a portion of a path until a sufficient volume of air has been collected to achieve the required detection limit. The joggers will vary their speed between 2.5 and 5 mph. Joggers will strive for an average speed of 4 mph. The average speed is a target speed only; speeds will be adjusted to meet trail conditions. Joggers should be equipped with a GPS unit to estimate average speed and distance traveled.

Two or more joggers can participate in this activity. When multiple joggers participate, they should maintain their relative position throughout the event (lead, middle, tail). Joggers should be spaced five feet apart.

7.6.9 Two Bicycles

Bicycling might be appropriate for sites such as parks, paths or open-space. Two bicyclists wearing appropriate PPE will ride back and forth with one leading and one following along the length of the site portion of a path or ride around a site (no trail) until a sufficient volume of air has been collected to achieve the required detection limit.

The bicycling participants will each be fitted with personal sampling pumps. The actual pump units will be contained in backpacks with the cassettes secured to the shoulder straps near the cyclists' lapels in the breathing zone.

During these events, the bicycle riders will vary their speed between 3 and 15 mph. Riders will strive for an average speed of 8 mph. The average speed is a target speed only; bicycle speeds will be adjusted to meet trail conditions. Bicycles will be equipped



SOP: 2084 PAGE: 19 of 29 REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

with a GPS to estimate average speed and distance traveled. Riders should maintain their relative position (lead, tail) throughout the activity.

7.6.10 Basketball Scenario

This scenario might be appropriate for sites where basketball courts are present. The basketball scenario was developed to simulate a group of recreational basketball players gathering to play a casual game of basketball for 120 minutes on an outdoor concrete or macadam court. Between four and 10 players wearing appropriate PPE can participate in this exercise.

- From 0 to 15 minutes, two of the players will sweep court with push brooms from the perimeter of the court to the center. While these two people are sweeping the court, the remaining personnel should mill about under the basket and take a few shots.
- From 15 to 30 minutes, shot practice participants stand around the key as for a free throw, with the exception that one of the participants is positioned under the basket to retrieve the ball after each shot. The player closest to the basket on the left side (facing the basket) takes two shots and the ball/shooter rotates counter clockwise after those two shots. Each person shoots consecutively until everyone has taken two shots. The entire group then rotates clockwise. This sequence should be repeated until time expires. Ideally, each player should shoot from each key position and take a turn retrieving the ball under the basket.
- From 30 to 45 minutes, each player takes turns practicing lay-ups. All players line up on the left side of the basket (facing the basket) and shoot one after another. The first person shoots then retrieves the ball for next person in line and so on. Players should use two basketballs with the second person bouncing the ball outside of the key as the first person shoots. Players should run a full cycle from left then a full cycle from right; repeating the left, right cycles until the interval time is up.
- From 45 to 60 minutes, shot practice as described in the 15 to 30 minute interval above will be conducted.
- From 60 to 75 minutes, a half-court game will be played to the degree practical.
- From 75 to 100 minutes, shot practice as described in the 15 to 30-minute interval above will be conducted.



SOP: 2084

PAGE: 20 of 29 REV: 0.0

DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

From 100 to 120 minutes, a lay-up drill as described in the 30 to 45 minute interval above will be conducted.

7.7 Cumulative Exposure Scenario

A cumulative exposure study might be appropriate for sites where individuals move about a site during the course of a day, with varying levels of exposure at multiple indoor and outdoor locations. The objective is to estimate aggregate and cumulative exposure to asbestos over the course of a day. Cumulative exposure studies should be conducted in order to increase understanding of linkages between sources of asbestos and subsequent exposure and dose to humans for use in mitigating risk and reducing exposure and disease.

Over periods of weeks, years or decades, exposures to environmental agents such as asbestos occur intermittently rather than continuously. Yet long-term health effects, such as cancer, are routinely projected based on an average dose over the period of interest (typically years), rather than as a series of intermittent exposures. Consequently, long-term doses are usually estimated by summing doses across discrete exposure episodes and then calculating an average dose for the period of interest (e.g., year, lifetime).

For the cumulative exposure studies, representative members of the population of interest should be selected for 24 hour sampling. The volunteers should be instructed to go about their day as usual. That is, they should not modify their schedule or activities just because they will be wearing a sampling pump.

A minimal description of exposure for a particular route must include exposure concentration and the duration. This is the method of choice to describe and estimate short-term doses, where integration times are of the order of minutes, hours or days. When projecting long term exposures, on the order of years or a lifetime, since it is typically impractical to sample for the entire exposure period, short-term exposure estimates are assumed to be representative of long-term periods and are integrated to estimate long-term exposures, typically with a safety factor to account for variability.

Observations of activities should be recorded throughout each cumulative exposure study, together with the other relevant factors including locations and activities during the study.

Samples will be collected using a personal air pump with a flow rate of approximately 3.5 L/min. Samples shall be collected open-faced with the inlet facing downward at a personal breathing zone height of 4 to 6 feet for 24 hours. Because the battery life for a personal monitor is typically eight to 10 hours, the pump shall be changed out at approximately 8-hour intervals (keeping the same filter cassette). Each pump shall be pre-calibrated to 3.5 L/min prior to use. Each monitor shall be worn at normal breathing height during all waking hours. During sleep, the monitor will be placed



SOP: 2084 PAGE: 21 of 29 REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

in the same room as the sleeping individual. The sampling cassette will be placed proximal to the breathing zone of the reclined participant.

Should a study subject participate in a high dust generating activity such as riding an ATV, the 24 hour sampling cassette event should be paused and a short term exposure sample should be collected on a separate cassette with an appropriately calibrated sampling pump. Once the high dust activity has been terminated, the original 24-hour cassette and pump should be resumed for the remainder of the sampling period. Results of the 2 or more samples, depending on the number of high dust generating events should be summed to derive the total 24-hour exposure data.

7.8 Background/Reference Sampling

Background/reference samples should be collected for all sampling events. A background or reference sample is defined as a sample collected upwind at a distance sufficient to prevent being influenced by the simulated activities and outside the site perimeter. To the degree practical, the area selected for background or reference sampling should be free of known asbestos contamination. The background level should reflect the concentration of asbestos in air for the environmental setting on or near a site or activity location and can be used to evaluate whether or not a release from the site or activity has occurred. Background level does not necessarily represent pre-release conditions or conditions in the absence of influence from source at the site. A background level may or may not be less than the detection limit, but if it is greater than the detection limit, it should account for variability in local concentrations. Background or reference samples should be collected concurrent with ABS using stationary sampling pumps. Sampling and analytical parameters (sample volume grid opening count, etc.) should be prescribed to permit a detection limit approximately an order of magnitude below that of the ABS detection limit.

An Aircon II sampling pump (or equivalent) will be calibrated to collect 10 L/min for on-site and off-site air samples through the filter. The flow rate will allow a minimum target volume of 4000 L and will provide a sensitivity limit of 0.0001 S/cc. Lower volume air samples will be collected concurrently at the ambient air sampling locations. Personal sampling pumps will be utilized in the same manner with the same media at a flow rate between 2- and 3- L/min in order to collect a sample volume of approximately 1000 L. The target sensitivity of these samples is also 0.0001 S/cc when additional grids are counted in accordance with the method. Co-located samples are collected to sample a high and low volume of air to increase the likelihood of at least one of the two samples being readable using the direct analytical method (ISO 10312).

7.9 Perimeter Sampling

Perimeter samples are defined as samples collected upwind, downwind or crosswind of a specific activity. When selecting areas for ABS, consideration should be given to the potential for off-site migration of contaminants and possible exposure of the public. Within the constraints of ABS, to



SOP: 2084 PAGE: 22 of 29 REV: 0.0

DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

the degree practical, particulate generation migration off-site should be minimized, and constraints or mitigation protocols established to eliminate public exposure. These constraints/mitigation protocols may include conducting the ABS in remote areas of the site, dust suppression using water mist, building a containment structure, etc. Air sampling should be conducted to document the airborne concentration of asbestos at the site perimeter during activities. Perimeter air monitoring should be conducted to:

- Document air quality during ABS and establish background or upwind levels of asbestos during site activities
- Monitor and document air quality during site activities near sensitive receptors
- Provide risk management information and address public confidence
- Reduce possible liabilities associated with ABS

Perimeter air sampling should be performed to ensure that ABS activities do not result in excessive airborne asbestos emissions from the site. Air samples should be collected and analyzed to determine the concentrations of asbestos at the site perimeter.

An Aircon II sampling pump (or equivalent) will be calibrated to collect 10 L/min for on-site and off-site air samples through the filter. The flow rate will allow a target volume of 4000 L and will provide a sensitivity limit of 0.0001 S/cc. Lower volume air samples will be collected concurrently at the perimeter sampling locations using personal sampling pumps, if loading is an issue. These pumps will be utilized in the same manner with the same media at a flow rate between 2- and 3-L/min in order to collect a sample volume of approximately 1000 L. The target sensitivity of these samples is also 0.0001 S/cc when additional grids are counted in accordance with the method. Co-located samples are collected to sample a high and low volume of air to increase the likelihood of at least one of the two samples being readable using the direct analytical method (ISO 10312).

7.10 Soil Sampling

A sufficient number of soil samples should be collected to characterize the study area. Since particulates are expected to be released from the entire study area, the primary objective of the soil sampling is to estimate the populations mean concentration. Composite samples are appropriate for characterizing study areas and a sampling design program such as Visual Sampling Plan is recommended for calculating the number and location of samples with the appropriate confidence intervals. Soil sampling should be conducted in accordance with ERT SOP #2012, Soil Sampling.

Soil characteristics should be documented in conjunction with the activity-based personal exposure monitoring using American Society of Testing and Materials (ASTM), Method D2488 - 00: Description and Identification of Soils (Visual-Manual Procedure), soil moisture by ASTM Method D2216-05: Standard Test Methods for Laboratory Determination of Water (Moisture)



SOP: 2084

PAGE: 23 of 29

REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

Content of Soil and Rock by Mass and grain size by ASTM Method D6913-04e1: Standard Test Methods for Particle-Size Distribution (Gradation) of Soils Using Sieve Analysis or Method D422-63 (2002): Standard Test Method for Particle-Size Analysis of Soils.

Soil samples should be representative of the soil. Table 3 provides examples of soil sampling depths, which may be disturbed by the activity being performed.

The relationship between the concentration of asbestos in a source material (typically soil) and the concentration of fibers in air that results when the source is disturbed is very complex, depending on a wide range of variables. To date, no method has been found that reliably predicts the concentration of asbestos in air given the concentration of asbestos in the source. Because of this limitation, this SOP emphasizes an empiric approach, where concentrations of asbestos in air at the location of a source disturbance are measured rather than predicted.

8.0 CALCULATIONS

The sample volume is calculated from the average flow rate of the pump multiplied by the number of minutes the pump was running (volume = flow rate X time in minutes). The sample volume should be submitted to the laboratory and identified on the chain of custody for each sample (zero for lot, and field blanks).

The concentration result is calculated by dividing the number of asbestos structures reported after the application of the cluster and matrix counting criteria by the sample volume (concentration = number of asbestos structures / sample volume).

9.0 QUALITY ASSURANCE/QUALITY CONTROL (QA/QC)

The following general QA procedures apply:

- 1. All data must be documented on field data sheets or within site logbooks. Record the following: date, time, location, sample identification number, pump number, flow rate, and cumulative time.
- 2. All instruments/equipment must be operated in accordance with operating instructions as supplied by the manufacturer, unless otherwise specified in the work plan. Equipment checkout and calibration activities must occur prior to sampling/operation and they must be documented.
- 3. Field blanks should be collected at a rate of one per twenty samples or one per sampling event, whichever is greater
- 4. Lot blanks should be collected at a rate of at least two per lot



SOP: 2084 PAGE: 24 of 29 REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

5. Collocated samples should be collected at the frequency of one per sampling event

For TEM analysis, the following QC procedures apply:

- Examine lot blanks to determine the background asbestos structure concentration.
- Examine field blanks to determine whether there is contamination by extraneous asbestos structures during specimen preparation or handling.
- 3. Examine laboratory blanks to determine if contamination is being introduced during critical phases of the laboratory program.
- 4. To determine if the laboratory can satisfactorily analyze samples of known asbestos structure concentrations, reference filters shall be examined. Reference filters should be maintained as part of the laboratory's Quality Assurance program.
- 5. To minimize subjective effects, some specimens should be recounted by a different microscopist.
- 6. Asbestos laboratories shall be accredited by the National Voluntary Laboratory Accreditation Program.
- 7. At this time, performance evaluation samples for asbestos in air are not commonly available for Removal Program Activities; however, they should be considered on a case-by-case basis.

10.0 DATA VALIDATION

Results of QC samples will be evaluated for contamination. This information will be utilized to qualify the environmental sample results accordingly with the project's data quality objectives.

11.0 HEALTH AND SAFETY

When working with potentially hazardous materials, follow U.S. EPA, OSHA, and corporate health and safety procedures. More specifically, when entering an unknown situation involving asbestos, a powered air-purifying respirator (PAPR) (full face-piece) is necessary in conjunction with high-efficiency particulate air (HEPA) filter cartridges. See applicable regulations for action levels, permissible exposure levels (PEL) and threshold limit values (TLV). If previous sampling indicates asbestos concentrations are below personal health and safety levels, then Level D personal protection is adequate.

For all ABS, appropriate PPE, including Tyvek coveralls, protective gloves and foot wear, and a respirator with HEPA filter cartridges (P-100 or equivalent) should be worn to protect participants. Details regarding PPE and other protective measures should be specified in the site-specific Health and Safety Plan. Special



SOP: 2084 PAGE: 25 of 29 REV: 0.0

DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

consideration should be given to the physical safety of the event participants as well as heat stress associated with performing vigorous activities in impermeable clothing.

12.0 REFERENCES

40 CFR Part 763 Asbestos Worker Protection

ERT SOP #2015, Asbestos Sampling.

Berman, Mark, Anthony Kolk, 2000. DRAFT: Modified Elutriator Method for the Determination of Asbestos in Soil and Bulk Materials, Revision 1.

Hildemann, L. 2005. Major Sources of Personal Exposure to Airborne Particulate Matter, Seminar at EPA Region IX, March 15, 2005.

International Organization for Standardization. 1995. Ambient air - Determination of asbestos fibres - Direct-transfer transmission electron microscopy method, Method 10312.

International Organization for Standardization. 1999. Ambient air - Determination of asbestos fibres - Indirect-transfer transmission electron microscopy method, Method 13794.

Januch, Jed. 2005. EPA Region 10 Standard Operating Procedure 10-1EU-001, Standard Operating Procedure for Sampling Airborne Asbestos Fibers in a Laboratory Enclosure- a Qualitative Procedure.

McBride, SJ et al. 1999. Investigations of the proximity effect for pollutants in the indoor environment. J Expo Anal Environ Epidemiol. 1999 9(6): 602-621. Nov-Dec.

National Institute for Occupational Safety and Health. 1977. Occupational Exposure Sampling Strategy Manual, Publication No. 77-173, January 1977.

Omega. 1987. FL-1600 Series Rotameters, http://www.omega.com/Manuals/manualpdf/M0379.pdf accessed February 2007.

Patel, Ishwarbhai, "Gardening's Socioeconomic Impacts", Journal of Extension, Volume 29, Number 4, Winter 1991, http://www.joe.org/joe/1991 winter/a1.html, accessed January 2004.

Rodes, CE., Kamens, RM and Wiener, RW. 1995. Experimental considerations for the study of contaminant dispersion near the body. Am Ind Hyg Assoc J; 56: 535-45.

U.S. EPA. 2000. Strategy for Research on Environmental Risks to Children, EPA/600/R-00/068, Office of Research and Development.



SOP: 2084 PAGE: 26 of 29 REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

U.S. EPA. 2004. Clarifying Cleanup Goals and Identification of New Assessment Tools for Evaluating Asbestos at Superfund Cleanups, OSWER Directive 9345.4-05, August 10, 2004.

Vodak, Mark C., Arthur J. Vrecenak, 2004. Transplanting Trees and Shrubs. New Jersey Agricultural Experimentation Center, Rutgers Cooperative Research & Extension, Agricultural Experiment Station, Rutgers, The State University of New Jersey, Fact Sheet 376.

13.0 APPENDICES

TABLE 1. Minimum Number of Grid Openings Required To Be Counted to Achieve a Given Analytical Sensitivity and Detection Limit. (Adapted from ISO 10312)

TABLE 2. Suggested Meteorological Station Specifications

TABLE 3. Soil Sampling Depth Based on Activities Performed



SOP: 2084 PAGE: 27 of 29 REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

TABLE 1. Minimum Number of Grid Openings Required To Be Counted to Achieve a Given Analytical Sensitivity and Detection Limit. (Adapted from ISO 10312)

Analytical	Limit of	Volume of Air Sampled (Liters)							
Sensitivity Structures/cc	Detection - Structures/cc	500	1000	2000	3000	4000	5000		
0.0001	0.0003	1066	533	267	178	134	107		
0.0002	0.0006	533	267	134	89	67	54		
0.0003	0.0009	358	178	89	60	45	36		
0.0004	0.0012	267	134	67	45	34	27		
0.0005	0.0015	214	107	54	36	27	22		
0.0007	0.0021	153	77	39	26	20	16		
0.001	0.003	107	54	27	18	14	11		
0.002	0.006	54	27	14	9	7	6		
0.003	0.009	36	18	9	6	5	4		
0.004	0.012	27	14	7	5	4	4		
0.005	0.015	22	11	6	4	4	4		
0.007	0.021	16	8	4	4	4	4		
0.01	0.030	11	6	4	4	4	4		



SOP: 2084 PAGE: 28 of 29

REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

TABLE 2. Suggested Meteorological Station Specifications

Variable	Accuracy	Resolution
Wind Speed (horizontal and vertical)	\pm (0.2 m/s + 5% of observed)	0.1 m/s
Wind Direction (azimuth and elevation)	± 5 degrees	1.0 degrees
Ambient Temperature	± 0.5 °C	0.1 °C
Precipitation	± 10% of observed or ± 0.5 mm	0.3 mm
Pressure	± 3 mb (0.3 kPa)	0.5 mb
Solar Radiation	± 5% of observed	10 W/m ²

m/s = meters per second
C = degrees Centigrade
mm = millimeters
mb = millibar
W/m² = watts per square meter

kPa = kilopascal



SOP: 2084

PAGE: 29 of 29

REV: 0.0 DATE: 5/10/07

ACTIVITY-BASED AIR SAMPLING FOR ASBESTOS

TABLE 3. Soil Sampling Depth Based on Activities Performed

Activity Based Sampling Scenario	Soil Sampling Depth
Raking (metal garden rake)	Surface to 3 inches
Raking (leaf rake)	Surface to 2 inch
ATV riding	Surface to 2 inch
Rototilling	Surface to 12 inches
Digging	Surface to depth of excavation
Child Playing in the dirt	Surface to 3 inches
Weed Whacking	Surface to 2 inches
Lawn Mowing	Surface to 2 inch
Walking with Stroller	Surface to 2 inch
Two Bicycles	Surface to 2 inch
Activities on solid surfaces such as asphalt or concrete	Microvacuum ASTM D 5755

APPENDIX B ACTIVITY-BASED SAMPLING PROPERTY BACKGROUND AND SAMPLING FORM

BD#

LIBBY ASBESTOS PROJECT Activity-Based Sampling (ABS) Property Background and Sampling Form

Address:				
Resident:	Phone	ne Number:		
Owner (if different than occupant):	Phone			
Data Item	Value	Notes		
ABS Category (completed after receipt of	Int1: VCS- and PLM-	Ext1: Clean fill		
soil sample results)	Int2: VCS+ and/or PLM +	Ext2: VCS- and PLM-		
	Int3: Exterior Removal and VCS-	Ext3: VCS+ and PLM-		
	Int4: Exterior Removal and VCS+	Ext4: PLM Bin B1		
(Circle all that apply)	N/A	Ext5: PLM Bin B2		
Primary Structure Description and Resid	dent Information			
Primary structure descriptions and resident	t information were gathered from a verbal intervie	w conducted on by		
All data be	elow were provided by the resident during the inte	erview.		
	Section Check Co	ompleted By:		
Number of Floors Above Ground	1 2 3 Other:			
Understructure	Basement: Living Space Non-Living Space	If basement is both a living/non-living		
	Crawlspace N/A	space- specify percentage of each:		
(Circle all that apply)				
Wood Stove	Is there a wood stove?	If so, is it used?		
	Yes No	Yes No		
Heating Source	Wood/Coal Electric Propane/Gas Oil			
	Other:			
Heat Distribution	Forced air Radiant			
•	Other:			
Carpeting	Approximate age of carpet per floor:	Additional Comments:		
	1: 2: 3: BSMT:			
	Choose age from the following categories			
	<5 5-10 10-20 20+			

Data Item	Value	Notes
Was the residence/building remodeled?	Yes No	
	If yes,	
	When (years): <2 2-5 >5	
	Where: Attic Living Areas Garage	
	Basement	
	Other:	
Is there any knowledge of former miners, close relatives of miners, or any highly exposed persons living or visiting the property?	Yes No	Explanation:
Is the resident, past or present, diagnosed with an asbestos-related disease?	Yes No Unknown	If unknown, why?
Total number of occupants		Explanation of part-time occupants:
Age and number of occupants	Age: 0-5 5-12 12-18 18-35 35-60 60+	
Number and type of pets	Dogs:Cats:	Are pets indoor only, outdoor only, or both?
Are the windows kept open during the day when weather conditions permit?	Yes No	During what approximate temperature range?
Do you regularly use a vacuum equipped with a HEPA filter? (if applicable)	Yes No N/A	
During the passive phase of the sampling, may we use your radio or television?	Yes No	Additional comments/restrictions on use:

Address:		
Are there any additional restrictions accessing, items not to be disturbed,	s on activities performed at the property? (firearms, scheduling requests (day of the wee	e.g., rooms prohibited from k, start time, split days}, etc.)
<u> </u>		
Interior Contamination- Data summarize the ABS investigation.	d from IFF. Additional indoor inspections for verm	culite were not conducted as a part of
Section Check Completed By:		Attached completed IFF to this form
Current location of indoor vermiculite	Attic Walls Crawlspace None Visual in Living Space: Basement, Ground Floor, Second Floor, Attached Garage	If in living space, provide specific location:
(Circle all that apply)	Other:	
Are there vermiculite additives in any of the building materials?	Yes No	Type and location of building material:
Removal History- Data summarized from	PCC.	
Section Check Completed By:		Attached completed PCC to this form
Has EPA performed an interior remediation at the property?	Yes No	In what year(s)?
Has EPA performed an exterior remediation at the property?	Yes No	In what year(s)?
Location of clean fill	Driveway Flowerbed Garden Yard Stockpile None N/A	Approximate location:
(Circle all that apply)	Other:	

Address: **Outdoor Characterization** ☐ Outdoor Characterization Date Completed:_____ Section Check Completed By:_____ ☐ Attached completed VVEF to this form Page Number(s):______ Team Members:____ Field Logbook: ___ Location of outdoor vermiculite Driveway Flowerbed Garden Yard Visual vermiculite override needed? Stockpile None Yes No Other (Circle all that apply) Are there known areas of the property Location: Yes No with LA? (previously sampled) Samples collected from (circle all that **NSUA** SUA apply) **Indoor Characterization** ☐ Indoor Characterization Date Completed:_____ Section Check Completed By:_____ Square Footage of House Number of Rooms Per Floor 1:____ Basement:____ Square Footage of Rooms on Ground Name of Room Square Footage Name of Room Square Footage Floor Square Footage of Rooms on Second Name of Room **Square Footage** Name of Room Square Footage Floor (if applicable)

Address:		-						
Square Footage of Rooms in Basement (if applicable)	Name of Room	Square Footage	Name of Roo	m Square Footag				
Percentage of each floor covered by carpet	1:% 2:% 3:%							
	BSMT:%							
Indoor ABS Event 1	J	☐ Indoor ABS	S- Event 1 Date	Completed:				
		Section Check Completed By:						
Field Logbook: Page	Number(s):	Team Membe	ers:					
Activity Summary	Passive	Active	Comments (schedule delays)				
	Date:AM PM	Date:AM PM						
Total number of samples collected:	Air: FB: Dust: FD:							
Outdoor ABS Event 1		C Outdoor ABS	S- Event 1 Date	Completed:				
Oddoor ADO EVERT				oompieted				
Field Logbook: Page	Number(s):							
Scenario Area 1	Day 1		Day 2 (if appl	icable)				
Soil Condition Data	100% M	oderately coarse texture	100% N	Moderately coarse texture				
	75-100% M	edium texture	75-100% N	Medium texture				
	50-75% Fi	ne and very fine texture	50-75% F	Fine and very fine texture				
Scenario Area 1 Ground Cover and Soil Texture	Grass% Mulch%	Bare soil% Rocks%	USDA Soil Te	exture:				
Scenario Area 1 Activity Summary	Raking	Mowing	(Child's Play				
	Date:	Date:		Date:				
Soil Category:	AM PM	AM F	M	AM PM				

Property Background and Sampling Form (continued) Address: Air: _____ FB: ____ Total number of samples collected: Soil: _____ FD: ____ ☐ Indoor ABS- Event 2 Date Completed:____ **Indoor ABS Event 2** Section Check Completed By:_____ Page Number(s):______ Team Members:_____ Field Logbook: ___ Passive **Activity Summary** Active Comments (schedule delays) ____ Date:_ Date: AM PM AM РМ Air: _____ FB: ____ Total number of samples collected: Dust: _____ FD: ____ FB: ____ ☐ Indoor ABS- Event 3 Date Completed:_____ **Indoor ABS Event 3** Section Check Completed By:_____ Field Logbook: _____ Page Number(s):____ ____ Team Members:_ Active Passive Comments (schedule delays) **Activity Summary** Date:____ _ Date: PM AM AM PM Air: _____ FB: ____ Total number of samples collected: Dust: _____ FD: ____ FB: ____ **Indoor ABS Event 4** ☐ Indoor ABS- Event 4 Date Completed: Section Check Completed By:_____ Field Logbook: _____ Page Number(s): _____ Team Members: Passive **Activity Summary** Active Comments (schedule delays) Date:___ __ Date:_ AM PM AM PM Air: _____ FB: ____ Total number of samples collected:

Dust: _____ FD: _____FB: ____

Address: **Outdoor ABS Event 2** Outdoor ABS- Event 2 Date Completed: Section Check Completed By:_____ Field Logbook: _____ Page Number(s):____ Team Members: Day 1 Day 2 (if applicable) Scenario Area 1 Soil Condition Data Moderately coarse texture 100% 100% Moderately coarse texture 75-100% Medium texture 75-100% Medium texture 50-75% Fine and very fine texture 50-75% Fine and very fine texture **USDA Soil Texture:** Scenario Area 1 Grass _____% Bare soil _____% Ground Cover and Soil Texture Mulch _____% Rocks _____% Scenario Area 1 Raking Mowing Child's Play **Activity Summary** Date:____ Date:_ Date: AM PM AM PM AM PM Soil Category:____ Air: _____ FB: ____ Total number of samples collected: Soil: _____ FD: ____ **ADDITIONAL INFORMATION**

Property Background and Sampling Form (continued)	
Address:	

FIELD DIAGRAM OF PROPERTY

Identify important features (i.e. trees, structures, flowerbeds, utility poles, sample locations, etc). Include north arrow.

- Sketch of the yard to illustrate location and size of any area with visible vermiculite along with the relative amount observed.
- Approximate location and size of any SUA
- Approximate locations of all sub-samples used to represent SUAs and NSUAs
- Location of previously excavated and backfilled areas
- Approximate location and size of the ABS scenario area (index IDs and composite points of scenario area samples)
- The sketch should indicate the soil condition at the ABS scenario area, including the extent of vegetative cover and any other important visual features.
- Location of MET station

^{*}Reinspect areas where removal has taken place for VCS and include as subsample for NSUA but use the surveyed property drawing if available.

APPENDIX C FIELD SAMPLE DATA SHEETS

Sheet No.: S- 00«seq»

LIBBY FIELD SAMPLE DATA SHEET (FSDS) FOR SOIL

Field Logbook No:	Page No:	•	
Business Name: Land Use: Residen		al Mining Roadway	
Data Item	Sample 1	Sample 2	Sample 3
Index ID			
Location ID			
Sample Group			
Location Description (circle)	Back yard Front yard Side yard Driveway Other	Back yard Front yard Side yard Driveway Other	Back yard Front yard Side yard Driveway Other
Category (circle)	FS FD of EB LB	FS FD of EB LB	FS FD of EB LB
Matrix Type (Surface soil unless other wise noted)	Surface Soil Other	Surface Soil Other	Surface Soil Other
Type (circle)	Grab Comp. # subsamples	Grab Comp. # subsamples	Grab Comp. # subsamples
GPS Status (circle)	Collected Previously Collected Not Collected-no signal (3 attempts) Not Collected-not required for sample	Collected Previously Collected Not Collected-no signal (3 attempts) Not Collected-not required for sample	Collected Previously Collected Not Collected-no signal (3 attempts) Not Collected-not required for sample
GPS File (fill in or circle)	Filename: NA	Filename: NA	Filename: NA
Sample Time			
Top Depth (inches below ground surface)			
Bottom Depth (inches below ground surface)			
Field Comments Note if vermiculite is visible in sampled area	BD	BD	BD
Entered (LFO)	Volpe: Entered Validated	Volpe: Entered Validated	Volpe: Entered Validated

For Field Team Completion (Provide Initials) Completed by: QC by:

Sheet No.: PA- 00«seq»

LIBBY FIELD SAMPLE DATA SHEET (FSDS) FOR PERSONAL AIR

Field Logbook No:		-		Owns		Sampling D			
Address: Business Name:				_ Owne	ii i enan	t:			
Land Use: Residenti Sampling Team: CDM	1 Other _		Names:_)
Person Sampled:			_ SSIN:_		1 ask				
Data Item	C	assette 1		C	assett	e 2		Cassette :	3
index ID									
Location ID									
Sample Group									
Location Description									
Category (circle)	FS FB-(fiel	d blank) LB-	(lot blank)	FS FB-(fi	eld blank)	LB-(lot blank)	FS FB-(fi	eld blank) LB	-(lot blank)
Matrix Type (circle)	Indoor	Outdoo	r	Indoor	Out	door	Indoor	Outdoo	or
Filter Diameter (circle)	25mm	37mm		25mm	37m	ım	25mm	37mm	
Pore Size (circle)	TEM45 PCM- 0.8		TEM45 PCM- 0.8		TEM45 PCM- 0.8		.8		
Flow Meter Type (circle)	Rotometer DryCal NA		Rotometer	Rotometer DryCal NA		Rotometer DryCal NA		NA	
Pump ID Number									
Flow Meter ID No.									
Start Date									
Start Time									
Start Flow (L/min)									
Stop Date									
Stop Time									
Stop Flow (L/min)									
Pump fault? (circle)	No Y	es NA	\	No	Yes	NA	No	Yes NA	\
MET Station onsite?	No Y	es NA	\	No	Yes	NA	No	Yes NA	\
Sample Type	TWA E	XC NA	•	TWA	EXC	NA	TWA	EXC NA	
Field Comments									
Cassette Lot Number:	Archive Blank	r (circle). Ye	s No	Archive Blar	ok (circle):	Voc. No.	Archivo Blav	ok (airala): Va	n No
	Volpe:	. (011010). 16	- 110	Volpe:	ik (Circle).	Yes No	Volpe:	nk (circle): Ye	s No
Entered (LFO)	Entered	Validate	ed	Entered	Vali	dated		Validat	ed

For Field Team Completion	Completed by	00 5
(Provide Initials)	Completed by	QC by

APPENDIX D LIBBY ASBESTOS PROJECT RECORD OF MODIFICATION FORM

Record of Modification



to the Libby Sampling and Quality Assurance Project Plan Field Activities LFO-0000

Instructions to Requester: Fax to contacts at bottom of form for review and approval.

File approved copy with Data Manager at the Libby Field Office (LFO).

Data Manager will maintain legible copies in a binder that can be accessed by LFO personnel.

Project QAPP (circle one):	Removal Acti	roved 4/00) on (approved 7/00) nd approval date):	Contamir		g Study (approved 5/02)	
SOP (Number and Revision	n No.):	· · · · · · · · · · · · · · · · · · ·			-	
Other Document (Title, Nur	nber/Revision):					
				ile: ate:		
Description of Modification that are affected by the pro		tion):				
Field logbook and page nur	mber where Mo	dification is documen	ited (or attac	ch associated	correspondence):	
Potential Implications of Mo	dification:					
Res	e(s):ident address(e	s):ttach a list of all appl	·		· · · · · · · · · · · · · · · · · · ·	
		ation Section) Effe				
Proposed Text Modification	s in Associated	Guidance Documen	t (attach add	ditional sheets	if necessary):	
Data Quality Indicator (circle indicators:	e one) – Please	reference definitions or	reverse side	for direction on	selecting data quality	
Not Applicable	Reject	Low Bias E	stimate	High Bias	No Bias	
Technical Review and Appr (Volpe Project Manager or o		4. 44. 4.		Date:		
EPA Review and Approval: (USEPA RPM or designate))			Date:		

DATA QUALITY INDICATOR DEFINITIONS

Reject - Samples associated with this modification form are not useable. The conditions outlined in the modification form adversely effect the associated sample to such a degree that the data are not reliable.

Low Bias - Samples associated with this modification form are useable, but results are likely to be biased low. The conditions outlined in the modification form suggest that associated sample data are reliable, but estimated low.

Estimate - Samples associated with this modification form are useable, but results should be considered approximations. The conditions outlined in the modification form suggest that associated sample data are reliable, but estimates.

High Bias - Samples associated with this modification form are useable, but results are likely to be biased high. The conditions outlined in the modification form suggest that associated sample data are reliable, but estimated high.

No Bias - Samples associated with this modification form are useable as reported. The conditions outlined in the modification form suggest that associated sample data are reliable as reported.